

**Report on**  
**Topographic and Bathymetric Survey of Reservoirs**  
**for Water Resources Department, Govt. of Gujarat**  
**at Saurashtra and Northern Gujarat Region, Gujarat**

**Bhadar - 1 Reservoir**

**Owner**



**Narmada Water Resources, Water Supply & Kalpsar Department.**

W.R.I. Division,  
C-9 Multistoried Building, Lal Darwaja,  
Ahmedabad-380001,  
Gujarat, India  
Email : [ewriabad@gmail.com](mailto:ewriabad@gmail.com)

**Survey Contractor**



**Ocean Science & Surveying Pvt. Ltd.**

C-005/006, Platform Floor, Tower No. 8  
Railway Station Complex  
CBD Belapur, Navi Mumbai-400 614  
Maharashtra, India  
Tel: +91-22-27595100 / 27575104  
Fax: +91-22-27579272 / 27595110.  
URL: [www.oceanscience.in](http://www.oceanscience.in)  
E-mail: [mail@oceanscience.in](mailto:mail@oceanscience.in)

**OSAS Report no.**

**OSaS/P34320/WRD/Reservoirs/Bhadar-1/178a**

19<sup>th</sup> July 2021

Rev 4

### DOCUMENT ISSUE FORM

Document Type		Survey Report			
Prelim/Draft/Final/Other		Draft			
Document Title		Topographic and Bathymetric Survey of Reservoirs for Water Resources Department, Govt. of Gujarat at Saurashtra Region, Gujarat – Bhadar - 1 Reservoir			
Document No.		OSaS/P34320/WRD/Saurashtra/Bhadar 1/178a Rev 4			
Prepared at		Ocean Science & Surveying Pvt. Ltd. Data Processing Centre, Navi-Mumbai.			
Submitted to		Narmada Water Resources, Water Supply & Kalpsar Department			
No. of Copies		By email			
Project No.		P34320			
<b>Revisions</b>					
Rev	Date	Description	Prepared by		Checked by
0	24.04.2021	Draft	Binny Mathew		Farokh Patel
1	29-05-2021	Amended as below	Binny Mathew		Farokh Patel
2	15.06.2021	Amended as below	Binny Mathew		Farokh Patel
3	07.07.2021	Amended as below	Binny Mathew		Farokh Patel
4	19.07.2021	Amended as below	Binny Mathew		Farokh Patel
<p>This document and any drawings accompanying it are confidential and contain confidential and privileged information, which is intended solely for the recipient(s) mentioned above.</p> <p>Any unauthorised use, review, retransmission, dissemination, distribution, printing or copying of this document or any part thereof is strictly prohibited.</p>					
Amendments in Revision 1			Amendments in Revision 3		
No.	Section, Page	Description			
1	-, 5	Chart names changed. Overview & Contour charts added	1	8.4, 27	Table 7, text updated
2	2.1, 13	Table 1 added	2	8.4, 27	Figure 7, text updated
3	3.2.1, 14	TBM names changed to actual			
4	8.8, 34-35	Loss/increase of storage capacity between 1979 and 2021 data amended			
Amendments in Revision 2			Amendments in Revision 4		
1.	-,4	List of Annexures amended	1	1.2, 11	Figure 2 updated
2.	2.1,12	Heading changed	2	Revision no. changed to 4 in footer	
3.	2.2, 12	Details of survey area added	3	Various places	Sq.K.ft changed to M.Sq. ft Sq km changed to M.Sq.m
4.	3.2.1, 16	Table 3 updated			
5.	8.3.3, 26	Text updated	4	8.6, 31	Table 8 added
6.	8.4, 27	Table 7 added for comparative statement	5	8.9, 36	Table 11 updated
7.	8.4,28	Curves annotated with arrows			
8.	8.6, 31	Table 9 updated			
9.	8.8, 34	Table 10 added			
10.	9, 40	Text updated			

CONTENTS	Page No.
<b>1 INTRODUCTION.....</b>	<b>10</b>
<b>1.1 Background of survey area.....</b>	<b>10</b>
<b>1.2 General Location.....</b>	<b>10</b>
<b>2 SCOPE OF WORK .....</b>	<b>12</b>
<b>2.1 Salient Features of Survey Area.....</b>	<b>12</b>
<b>2.2 Survey Design .....</b>	<b>12</b>
<b>3 SURVEY CONTROL.....</b>	<b>13</b>
<b>3.1 Geodesy .....</b>	<b>13</b>
<b>3.2 Horizontal and vertical Control.....</b>	<b>13</b>
3.2.1 Topographic survey.....	13
3.2.2 Bathymetric survey.....	17
<b>3.3 Survey Vessel.....</b>	<b>19</b>
<b>4 PERSONNEL .....</b>	<b>19</b>
<b>5 SURVEY EQUIPMENT DETAILS.....</b>	<b>20</b>
<b>5.1 General.....</b>	<b>20</b>
<b>5.2 RTK Positioning and Navigation .....</b>	<b>20</b>
<b>5.3 Single Beam Echo Sounder System .....</b>	<b>21</b>
<b>5.4 Heave Sensor .....</b>	<b>21</b>
<b>5.5 Auto Level Geomax .....</b>	<b>21</b>
<b>5.6 Real Time Kinematic (RTK) For Topographic Survey .....</b>	<b>21</b>
<b>5.7 HyPack Software .....</b>	<b>21</b>
<b>6 DATA PROCESSING AND INTERPRETATION.....</b>	<b>22</b>
<b>6.1 Navigation Data.....</b>	<b>22</b>
<b>6.2 Bathymetric Data .....</b>	<b>22</b>
<b>6.3 Topographic Data .....</b>	<b>22</b>
<b>6.4 Charting .....</b>	<b>22</b>
<b>7 SURVEY RESULTS.....</b>	<b>23</b>
<b>7.1 Survey Area .....</b>	<b>23</b>
<b>7.2 Longitudinal Profile .....</b>	<b>24</b>
<b>7.3 Cross Section Profiles.....</b>	<b>24</b>
<b>8 CAPACITY SURVEY RESULTS .....</b>	<b>25</b>
<b>8.1 General.....</b>	<b>25</b>
<b>8.2 Effect of Sedimentation in Planning of Reservoirs .....</b>	<b>25</b>
<b>8.3 EARLIER CAPACITY SURVEY .....</b>	<b>26</b>
8.3.1 Capacity survey of 1964.....	26
8.3.2 Capacity survey of 1979.....	26
8.3.3 Capacity survey of 2021.....	26
<b>8.4 ELEVATION-AREA-CAPACITY CURVES .....</b>	<b>27</b>
<b>8.5 DATA COMPARISON BETWEEN 1964 AND 2021 .....</b>	<b>29</b>
8.5.1 Rate of siltation .....	29
8.5.2 Loss of gross storage capacity at F.R.L.....	29
8.5.3 Loss of dead storage capacity .....	29
8.5.4 Loss of live storage capacity .....	30
<b>8.6 SUMMARY OF CAPACITY SURVEYS (1964 and 2021).....</b>	<b>31</b>
<b>8.7 DATA COMPARISON BETWEEN 1964, 1979, 2003, 2004 AND 2021 .....</b>	<b>32</b>
<b>8.8 DATA COMPARISON BETWEEN 1979 AND 2021 .....</b>	<b>34</b>
8.8.1 Rate of erosion.....	34

8.8.2	Increase in Gross storage capacity at 107.89m.....	34
8.8.3	Increase in dead storage capacity .....	34
8.8.4	Increase in live storage capacity .....	35
<b>8.9</b>	<b>SUMMARY OF CAPACITY SURVEYS (1979 and 2021).....</b>	<b>36</b>
<b>8.10</b>	<b>LOSS OF STORAGE DUE TO SEDIMENT DEPOSIT .....</b>	<b>37</b>
<b>8.11</b>	<b>CONTROL OF SEDIMENTATION IN RESERVOIRS .....</b>	<b>38</b>
8.11.1	Suitable design of reservoir.....	39
8.11.2	Restrict the sediment inflow .....	39
8.11.3	Limit sediment deposition.....	40
8.11.4	Regular removal of deposited sediment .....	41
<b>9</b>	<b>CONCLUSIONS.....</b>	<b>42</b>
<b>10</b>	<b>REFERENCES.....</b>	<b>43</b>

### LIST OF FIGURES

Figure 1:	Survey areas/reservoirs of Saurashtra and Northern Gujarat regions .....	11
Figure 2:	Survey area – Reservoir Bhadar-1 .....	11
Figure 3:	Details of OSaS-BH-TBM-01 .....	14
Figure 4:	Details of OSaS-BH-TBM-02 .....	15
Figure 5:	Survey vessel – SMB Ocean .....	19
Figure 6:	2D image of the Bhadar 1 reservoir area.....	24
Figure 7:	Elevation-Area-Capacity Curves.....	28

### LIST OF TABLES

Table 1:	Surveyed areas for Bhadar-1 reservoir .....	12
Table 2:	Geodetic Parameters .....	13
Table 3:	Details of TBMs .....	16
Table 4:	Observed Water Levels.....	18
Table 5:	Survey Personnel .....	19
Table 6:	Classification of gradients .....	22
Table 7:	Comparative statement of Bhadar-1 reservoir .....	27
Table 8:	Rate of Sedimentation at F.R.L (107.90m) .....	31
Table 9:	Dates of the previous surveys.....	32
Table 10:	Rate of Sedimentation at 106.41m (1.49m below F.R.L).....	33
Table 11:	Rate of Sedimentation at F.R.L (107.89m) .....	36
Table 12:	Loss/increase of storage capacity between 1979 and 2021 .....	38

### LIST OF ANNEXURES

Annexure 1:	Elevation-Area-Capacity Table.....	44
Annexure 2:	Mobilisation and Calibration Report.....	74
Annexure 3:	Previous Data.....	82
Annexure 4:	Daily Progress Reports.....	104

### ACCOMPANYING CHARTS

SI.No	Chart Name	Details
1.	OSaS_P34320_WRD_Bhadar-1_OV_01	Overview Map Scale: 1:20000
2.	OSaS_P34320_WRD_Bhadar-1_CC_02	Contour Map Scale: 1:20000
3.	OSaS_P34320_WRD_Bhadar1_03	Bathymetry and Topography Chart Scale: 1:5000; Grid: 25m X 25m
4.	OSaS_P34320_WRD_Bhadar1_04	Bathymetry and Topography Chart Scale: 1:5000; Grid: 25m X 25m
5.	OSaS_P34320_WRD_Bhadar1_05	Bathymetry and Topography Chart Scale: 1:5000; Grid: 25m X 25m
6.	OSaS_P34320_WRD_Bhadar1_06	Bathymetry and Topography Chart Scale: 1:5000; Grid: 25m X 25m
7.	OSaS_P34320_WRD_Bhadar1_07	Bathymetry and Topography Chart Scale: 1:5000; Grid: 25m X 25m
8.	OSaS_P34320_WRD_Bhadar-1_LP_08	Longitudinal Profile Along Lowest Line Scale: 1:5000 KP 0 – KP 16
9.	OSaS_P34320_WRD_Bhadar-1_LP_09	Longitudinal Profile Along Lowest Line Scale: 1:5000 KP 16 – KP 26.806
10.	OSaS_P34320_WRD_Bhadar-1_CP_10	Cross Section Profiles 1 - 14 Scale: 1:5000
11.	OSaS_P34320_WRD_Bhadar-1_CP_11	Cross Section Profiles 15 - 23 Scale: 1:5000
12.	OSaS_P34320_WRD_Bhadar-1_CP_12	Cross Section Profiles 24 - 30 Scale: 1:5000
13.	OSaS_P34320_WRD_Bhadar-1_CP_13	Cross Section Profiles 31 - 37 Scale: 1:5000
14.	OSaS_P34320_WRD_Bhadar-1_CP_14	Cross Section Profiles 38 - 43 Scale: 1:5000
15.	OSaS_P34320_WRD_Bhadar-1_CP_15	Cross Section Profiles 44 - 49 Scale: 1:5000
16.	OSaS_P34320_WRD_Bhadar-1_CP_16	Cross Section Profiles 50 - 55 Scale: 1:5000
17.	OSaS_P34320_WRD_Bhadar-1_CP_17	Cross Section Profiles 56 - 61 Scale: 1:5000
18.	OSaS_P34320_WRD_Bhadar-1_CP_18	Cross Section Profiles 62 - 67 Scale: 1:5000
19.	OSaS_P34320_WRD_Bhadar-1_CP_19	Cross Section Profiles 68 - 72 Scale: 1:5000
20.	OSaS_P34320_WRD_Bhadar-1_CP_20	Cross Section Profiles 73 - 78 Scale: 1:5000
21.	OSaS_P34320_WRD_Bhadar-1_CP_21	Cross Section Profiles 79 - 85 Scale: 1:5000
22.	OSaS_P34320_WRD_Bhadar-1_CP_22	Cross Section Profiles 86 - 93 Scale: 1:5000

23.	OSaS_P34320_WRD_Bhadar-1_CP_23	Cross Section Profiles 94 - 101 Scale: 1:5000
24.	OSaS_P34320_WRD_Bhadar-1_CP_24	Cross Section Profiles 102 - 109 Scale: 1:5000
25.	OSaS_P34320_WRD_Bhadar-1_CP_25	Cross Section Profiles 110 - 116 Scale: 1:5000
26.	OSaS_P34320_WRD_Bhadar-1_CP_26	Cross Section Profiles 117 - 123 Scale: 1:5000
27.	OSaS_P34320_WRD_Bhadar-1_CP_27	Cross Section Profiles 124 - 130 Scale: 1:5000
28.	OSaS_P34320_WRD_Bhadar-1_CP_28	Cross Section Profiles 131 - 138 Scale: 1:5000
29.	OSaS_P34320_WRD_Bhadar-1_CP_29	Cross Section Profiles 139 - 151 Scale: 1:5000
30.	OSaS_P34320_WRD_Bhadar-1_CP_30	Cross Section Profiles 152 - 172 Scale: 1:5000

## ABBREVIATIONS

WRD	Water Resources Department
BM	Benchmark
C.M.	Central Meridian
CD	Chart Datum
cm	Centimetre
ddmm.mmm	Degrees minutes. decimal minutes
DGPS	Differential Global Positioning System
DTM	Digital Terrain Model
DSL	Dead Storage Level
FRL	Full reservoir Level
GPS	Global Positioning System
HSE	Health, Safety & Environment
ID	Identification name/number
IHO	International Hydrographic Organization
kHz	Kilohertz
km	Kilometre
KP	Kilometre Post
Lat	Latitude
LBM	Local Benchmark
Long	Longitude
m	Metre
MCum	Million Cubic Meter
MDDL	Minimum Drawn Down Level
MSL	Mean Sea Level
MSqm	Million Square Meter
MV	Motor Vessel
NA	Not Applicable
NU	North Up
SOW	Scope of Work
SVP	Sound Velocity Profile
UTM	Universal Transverse Mercator projection
w.d.	Water depth
WGS84	World Geodetic System 1984

## EXECUTIVE SUMMARY

Ocean Science & Surveying Pvt. Ltd. (OSaS) was contracted by Narmada Water Resources, Water Supply & Kalpsar Department (WRD) to carry out topographic and bathymetric surveys of thirteen reservoirs in the Saurashtra region; namely Bhadar-1, Bhadar-2, Brahmani-1, Und-1, Machhu-1, Machhu-2, Khodiyar, Aaji-1, Nara, Tappar, Rudramata, Mitti and Fatehgadh.

This report describes the results of the topographic and bathymetric survey services provided by OSaS to the WRD for topographic and bathymetric mapping of the Bhadar-1 reservoir, Saurashtra region, Gujarat.

The vessel SMB Ocean, owned by OSaS, was used for conducting the survey. The mobilisation of equipment started on 15<sup>th</sup> January 2021. A DGPS consistency check was done on 14<sup>th</sup> January through establishing two reference stations (TBMM) using RTK systems. The bathymetric and topographic survey commenced on 17<sup>th</sup> January 2021 at Bhadar-1 reservoir. Bathymetric survey was completed on 24<sup>th</sup> February 2021 and topographic survey was completed on 06<sup>th</sup> March 2021.

The survey data was processed on the site on a daily basis and reporting and charting was completed in the OSaS data processing centre in Navi-Mumbai after the survey.

All the co-ordinates in the report and charts are referenced to WGS 84 datum, UTM projection, CM 69° east, zone 42, northern hemisphere.

All bathymetric and topographic data has been reduced to M.S.L using the observed average water level of each day during the survey period.

The survey was carried out in daylight hours keeping in mind the safety of personnel and survey equipment.

Construction of the Bhadar-1 reservoir was completed in 1964. Reports of four capacity surveys were provided to us for comparison with the current survey; 1964, 1979, 2004 and 2008 (period 2001 -2003) using hydrographic and remote sensing techniques.

In the current bathymetric and topographic survey, a minimum elevation of 95.8m was observed in the southwestern portion of the survey area within the bathymetric section. A maximum topographic elevation value of 117.22m is observed in the northwestern portion of the survey area.

The survey was extended till the High Flood Level (H.F.L.:110.33m). Except near the survey boundary, most of the river channels are observed running from north to south and east to west, with elevation contours between 100m and 98m and covering a wide area of 99m contour within the area near the dam gates.

The comparison between 1964 and 2021 (57 years) data results in a rate of siltation (Silt Index) of 1.80 Ha.m/100sq.km./year. Annual percentage loss of gross storage capacity, live storage capacity and dead storage capacity are 0.18%, 0.08% and 1.73% respectively.

The comparison between 1964 and 1979 (15 years) data results shows a rate of siltation (Silt Index) at a rate of 13.78 Ha.m/100sq.km./year. Annual percentage loss of gross storage capacity is 1.39.

The comparison between 1979 and 2021 (42 years) data indicates a significant increase in water spread area observed from 42.25 km<sup>2</sup> to 46.96 km<sup>2</sup> at 107.89m. The corresponding increase in volume resulted in an erosion phase during this period. The rate of erosion is calculated as 2.4 Ha.m/100 sq.km./year.

The comparison of 1979, 2003, 2004 and 2021 data with respect to 1964 impounding data at 106.41m (1.49m below F.R.L) results in a silt index of 12.99, 4.31, 3.35 and 2.04 respectively at the rate of Ha.M/100 km<sup>2</sup>/year.



The comparison of current capacity data to the previous capacity data of 1964 survey shows a decrease in capacity at all levels, resulting in a decrease in gross storage capacity, with a corresponding volume of sediment deposited at all levels of the reservoir.

The detailed comparison of current capacity data at different levels with the previous capacity data of the 1979 survey shows an increase in capacity within the dead storage and live storage areas except at 98.02m elevation, where sediment deposition was noticed.

The increase in capacity from 1979 to 2021 is possibly due to the further deepening of the river channel or sediment removal, possibly due to a flood or changes in the water spread area at FRL by the conversion of irregular land area into levelled cultivation fields.

The removal or deposition of the sediment within the reservoir results in a corresponding increase or loss of storage capacity.

## 1 INTRODUCTION

The Water Resources Department, Govt. of Gujarat is engaged in developing water reservoirs within the state of Gujarat, under a World Bank funding programme towards National Hydrology Projects of Govt. of India. Towards this end, the Water Resources Department, Govt. of Gujarat requires services for conducting bathymetric survey of reservoirs of Saurashtra and northern Gujarat regions under its National Hydrology Project.

Ocean Science & Surveying Pvt. Ltd. (OSaS) was contracted by Narmada Water Resources, Water Supply & Kalpsar Department (WRD) to carry out topographic and bathymetric surveys of thirteen reservoirs in the Saurashtra and northern Gujarat regions; namely Bhadar-1, Bhadar-2, Brahmani-1, Und-1, Machhu-1, Machhu-2, Khodiyar, Aaji-1, Nara, Tappar, Rudramata, Mitti and Fatehghadh.

This report describes the results of the topographic and bathymetric survey services provided by OSaS to WRD for topographic and bathymetric mapping of the Bhadar-1 reservoir in Saurashtra, Gujarat.

### 1.1 Background of survey area

Bhadar river is in the Saurashtra peninsula, in the western Indian state of Gujarat. It flows south from its origin through Jasdan, then turns south-west and generally heads west until it empties into the Arabian sea near Porbandar. The total catchment area of the basin is 7,094 sq km. It is impounded by two reservoirs; Bhadar-1 reservoir with a capacity of 238 M.cu.m and downstream from that, Bhadar-2 reservoir with a capacity of 49 M.cu.m.

The average rainfall in the Bhadar basin is 625 mm. In winter, the temperature varies between 4°C and 15°C in different parts of the region. May is the hottest month. Maximum temperature varies between 40°C and 45°C. At present, there are 12 completed structures, either reservoirs or weirs, in Bhadar catchment.

Bhadar-1 dam was constructed in the year 1964 with a gross storage of 238Mm<sup>3</sup>. It is an earthen and masonry type dam on basaltic bedrock. This dam fulfills its operating purpose of flood management and irrigation efficiently.


### 1.2 General Location

The reservoirs of Saurashtra and Northern Gujarat region are shown on the Google Earth image in **Figure 1**.



**Figure 1: Survey areas/reservoirs of Saurashtra and Northern Gujarat regions**

This report specifically focuses on the results of topographic and bathymetric survey in and around the Bhadar-1 reservoir situated within the Saurashtra region, shown in the Google earth image below:



**Figure 2: Survey area – Reservoir Bhadar-1**

## 2 SCOPE OF WORK

The scope of work for the survey was:

- To mobilize requisite topographic equipment and personnel at the sites specified by the client.
- To mobilize a suitable vessel along with requisite bathymetric equipment and personnel at the sites specified by the client.
- To carry out topographic and single beam echo sounder bathymetric survey in the specified areas.
- To estimate and study the sedimentation behaviour of the reservoirs in different zones including horizontal zones throughout the reservoirs as well as vertical zones namely (a) dead storage (b) live storage (c) flood storage, if any.
- The integrated bathymetric system will be used to collect data on depth and bottom topography of the reservoirs and rivers. Primary application is reservoir sedimentation surveying; products will be reservoir capacity figures as a function of depth, depth contours and bottom topography change over time.
- To upgrade elevation-area-capacity tables /curves of the reservoirs.
- To prepare contour plan, Longitudinal profile (L-section), Cross section profiles...etc.

### 2.1 Salient Features of Survey Area

The Bhadar-1 reservoir with a capacity of 238 M.cu.m is situated across the Bhadar River in the Saurashtra peninsula, in the Western Indian state of Gujarat. This reservoir was impounded in the year 1964 and its storage is mainly for irrigation purposes. The salient features of Bhadar – 1 reservoir at the time of impounding are given below.

- |                                    |                 |
|------------------------------------|-----------------|
| a. Location                        |                 |
| Latitude                           | : 21° - 51' N   |
| Longitude                          | : 70° - 46' E   |
| b. Catchment Area                  | : 2406 Sq.Km    |
| c. Full Reservoir Level (F.R.L)    | : 107.90 m      |
| d. Low Water Level (M.D.D.L/L.W.L) | : 97.56 m       |
| e. Dead Water Level (D.W.L/O.S.L)  | : 97.54 m       |
| f. Gross Storage                   | : 237.86 M.Cu.m |
| g. Dead Storage                    | : 14.16 M.Cu.m  |
| h. Live Storage                    | : 223.70 M.Cu.m |
| i. Area at F.R.L                   | : 44.00 Sq.Km   |

### 2.2 Survey Design

The topographic and bathymetric survey lines were planned and executed at intervals of 25m throughout the area of survey. Topographic survey was conducted using RTK base and rover system. The limit of topographic survey was up to the H.F.L of the reservoir, which is 110.33m (362.00 ft.) above MSL, as provided by the client. The bathymetric survey was conducted using RTK positioning system and single beam echo sounder.

The topographic and bathymetric surveyed areas (in sq.km) for the Bhadar-1 reservoir are provided in **Table 1** below.

Name of Reservoir	Bathymetric area surveyed (sq. km.)	Topographic area surveyed (sq.km.)
Bhadar-1	32.7	26.372

**Table 1: Surveyed areas for Bhadar-1 reservoir**

### 3 SURVEY CONTROL

#### 3.1 Geodesy

The survey operations were conducted in WGS 84 Spheroid, Universal Transverse Mercator projection system, based on the geodetic parameters as presented below. All co-ordinates given within this document are with reference to it.

GEODETTIC PARAMETERS	
Satellite Datum	
Datum, Spheroid	WGS-84
Semi-Major Axis	6378137.000 m
Semi Minor Axis	6356752.314 m
Inverse Flattening	298.2572
Projection Parameters	
Grid Projection	Universal Transverse Mercator
Latitude of Origin of Projection	0° (Equator)
Longitude of Origin of Projection	69° E, Zone 42 North
Hemisphere	North
False Easting (metres)	500000 E
False Northing (metres)	0
Scale Factor on CM	0.9996
Units	Metres

**Table 2: Geodetic Parameters**


#### 3.2 Horizontal and vertical Control

##### 3.2.1 Topographic survey

Two reference stations were established as temporary control points/temporary benchmarks (TBM). The levelling of these TBMs was carried out using an auto level with respect to the known level of F.R.L which is given as 107.90m above MSL, as provided by the client. The base stations of the RTK were set up at these positions and two-hour long continuous observations were conducted using a Hemisphere RTK positioning system to fix the consistency of the position for horizontal control. The system provides real time correction signals, providing centimetre level accuracy. Additional TBMs were established at various parts of the survey area to keep the rover in range with respect to the base station.


The details of the reference stations OSaS-BH-TBM-01 and OSaS-BH-TBM-02 are given in **Figure 3** and **Figure 4**.

<b>Station Number:</b>	OSaS-BH-TBM-01	<b>Latitude:</b>	21° 48' 35.984" N
<b>Locality:</b>	Gondal, Gujarat	<b>Longitude:</b>	70° 46' 7.761" E
<b>Geodetic Datum:</b>	WGS84	<b>Northing:</b>	2412845.20 m N
<b>Projection:</b>	Universal Transverse Mercator	<b>Easting:</b>	682842.74 m E
<b>Date:</b>	17 <sup>th</sup> January 2021	<b>Elevation:</b>	112.980m above MSL
<b>Station Description:</b>	A circle with text OSaS-BH-TBM-01 is drawn with yellow paint on the walkway to the Val (valve) tower.		
<b>Access:</b>	Road to the top of the reservoir near the spillway. TBM is situated on the walkway to the Val (valve) tower. TBM-1 lies about 28m SW of the Val (valve) tower.		



**Figure 3: Details of OSaS-BH-TBM-01**

<b>Station Number:</b>	OSaS-BH-TBM-02	<b>Latitude:</b>	21° 48' 36.158"N
<b>Locality:</b>	Gondal, Gujarat	<b>Longitude:</b>	70° 46' 08.048"E
<b>Geodetic Datum:</b>	WGS84	<b>Northing:</b>	2412850.62 m N
<b>Projection:</b>	Universal Transverse Mercator	<b>Easting:</b>	682850.92 m E
<b>Date:</b>	17 <sup>th</sup> January 2021	<b>Elevation:</b>	113.140m above MSL
<b>Station Description:</b>	A circle with text OSaS-BH-TBM-02 is drawn with yellow paint on the walkway to the Val (valve) tower.		
<b>Access:</b>	Road to top of the reservoir near spillway and TBM is situated on the walkway to the Val (valve) tower. TBM-2 lies about 18m SW of the Val (valve) tower.		



**Figure 4: Details of OSaS-BH-TBM-02**

Additional temporary control points were established in the field to maintain the moving rover within the range of the base reference point. The following table summarises the details of all the temporary control points (TBMs) established at the site during the survey.

Sr. No.	Station Name	Latitude (N)	Longitude (E)	Easting (m)	Northing (m)	Elevations (m) w.r.t MSL
1	OSAS-BH-TBM-01	21° 48' 35.984"	70° 46' 07.761"	682842.74	2412845.20	112.980
2	OSAS-BH-TBM-02	21° 48' 36.158"	70° 46' 08.048"	682850.92	2412850.62	113.140
3	OSAS-BH-TBM-03	21° 49' 55.398"	70° 45' 31.788"	681781.69	2415275.83	114.690
4	OSAS-BH-TBM-04	21° 50' 59.546"	70° 45' 52.521"	682354.47	2417255.59	118.508
5	OSAS-BH-TBM-05	21° 52' 54.576"	70° 45' 08.949"	681063.08	2420779.14	116.260
6	OSAS-BH-TBM-06	21° 54' 03.861"	70° 46' 06.444"	682689.00	2422929.02	112.164
7	OSAS-BH-TBM-07	21° 52' 58.182"	70° 45' 38.240"	681902.63	2420899.68	119.411
8	OSAS-BH-TBM-08	21° 52' 19.342"	70° 46' 00.474"	682554.62	2419712.43	117.464
9	OSAS-BH-TBM-09	21° 51' 00.411"	70° 47' 04.926"	684433.09	2417306.14	116.941
10	OSAS-BH-TBM-10	21° 50' 20.053"	70° 47' 24.739"	685016.41	2416071.50	115.942
11	OSAS-BH-TBM-11	21° 49' 35.886"	70° 47' 40.988"	685498.83	2414718.51	113.125
12	OSAS-BH-TBM-12	21° 49' 08.421"	70° 48' 16.437"	686526.73	2413885.66	113.504
13	OSAS-BH-TBM-13	21° 49' 17.689"	70° 49' 00.814"	687797.83	2414185.70	111.451
14	OSAS-BH-TBM-13A	21° 49' 55.325"	70° 49' 42.115"	688970.20	2415357.30	114.371
15	OSAS-BH-TBM-13B	21° 49' 55.914"	70° 49' 41.909"	688964.07	2415375.33	114.931
16	OSAS-BH-TBM-15	21° 49' 29.995"	70° 50' 22.386"	690135.97	2414592.00	112.971
17	OSAS-BH-TBM-16	21° 49' 32.483"	70° 51' 23.147"	691879.99	2414689.43	113.613
18	OSAS-BH-TBM-17	21° 49' 13.873"	70° 52' 05.423"	693101.04	2414131.71	113.713
19	OSAS-BH-TBM-18	21° 49' 12.468"	70° 52' 49.758"	694374.84	2414103.99	114.165
20	OSAS-BH-TBM-19	21° 49' 38.553"	70° 53' 49.926"	696092.98	2414927.48	117.887
21	OSAS-BH-TBM-20	21° 48' 49.574"	70° 53' 50.990"	696142.09	2413421.38	115.110
22	OSAS-BH-TBM-2A	21° 47' 33.273"	70° 47' 17.153"	684858.08	2410939.41	113.515
23	OSAS-BH-TBM-2B	21° 47' 13.896"	70° 48' 12.770"	686462.61	2410362.04	112.682
24	OSAS-BH-TBM-2C	21° 47' 06.300"	70° 48' 39.532	687234.08	2410137.43	115.206
25	OSAS-BH-TBM-2D	21° 47' 06.207"	70° 49' 13.442"	688208.22	2410146.02	113.773
26	OSAS-BH-TBM-2E	21° 47' 02.235"	70° 49' 51.111"	689291.75	2410036.66	115.576
27	OSAS-BH-TBM-2F	21° 47' 10.837"	70° 50' 20.620"	690136.30	2410311.30	115.034
28	OSAS-BH-TBM-2G	21° 47' 21.619"	70° 50' 52.684"	691053.40	2410653.94	113.533
29	OSAS-BH-TBM-2H	21° 47' 20.306"	70° 51' 18.528"	691796.26	2410622.45	116.111
30	OSAS-BH-TBM-2I	21° 47' 56.591"	70° 51' 49.480"	692671.89	2411749.21	112.537
31	OSAS-BH-TBM-2J	21° 47' 58.714"	70° 52' 16.720"	693453.53	2411823.98	115.445
32	OSAS-BH-TBM-2K	21° 48' 52.087"	70° 52' 46.683"	694294.19	2413476.04	112.944
33	OSAS-BH-TBM-A	21° 49' 07.802"	70° 52' 42.159"	694158.37	2413957.83	109.260
34	OSAS-BH-TBM-B	21° 48' 54.574"	70° 52' 24.099"	693644.63	2413544.64	112.033

**Table 3: Details of TBMs**



### 3.2.2 Bathymetric survey

The same two reference stations, established as temporary control points/temporary benchmark (TBM) for topographic survey were also used as the base stations for RTK positioning during the bathymetric survey. The rover fixed in the survey boat can receive calculated X Y Z of its position at any point with centimeter level accuracy with respect to the known base positions. The details of these reference stations are given in **Figure 3** and **Figure 4**

The water level of the reservoir with respect to the known value of F.R.L (107.90 above MSL) was measured twice a day during the survey. The mean value of these two readings was taken as the datum for the day's work. The depths recorded by the echo sounder were deducted from these levels to obtain the bed levels with respect to M.S.L. The observed water levels are given in **Table 4**.

Date	Water level				Average level in metres (MSL)
	Start		End		
	Time (AM)	Level (MSL)	Time (PM)	Level (MSL)	
17-01-21	9:00	106.950	5:00	106.940	106.945
18-01-21	9:00	106.923	5:00	106.908	106.916
19-01-21	9:00	106.893	5:00	106.881	106.887
20-01-21	9:00	106.868	5:00	106.859	106.864
21-01-21	9:00	106.845	5:00	106.837	106.841
22-01-21	9:00	106.823	5:00	106.814	106.819
23-01-21	9:00	106.802	5:00	106.794	106.798
24-01-21	9:00	106.779	5:00	106.769	106.774
25-01-21	9:00	106.753	5:00	106.743	106.748
26-01-21	9:00	106.722	5:00	106.711	106.717
27-01-21	9:00	106.694	5:00	106.680	106.687
28-01-21	9:00	106.663	5:00	106.648	106.656
29-01-21	9:00	106.634	5:00	106.619	106.627
30-01-21	9:00	106.600	5:00	106.589	106.595
31-01-21	9:00	106.574	5:00	106.562	106.568
01-02-21	9:00	106.544	5:00	106.533	106.539
02-02-21	9:00	106.517	5:00	106.505	106.511
03-02-21	9:00	106.489	5:00	106.480	106.485
04-02-21	9:00	106.466	5:00	106.456	106.461
05-02-21	9:00	106.441	5:00	106.429	106.435
06-02-21	9:00	106.410	5:00	106.393	106.402
07-02-21	9:00	106.379	5:00	106.365	106.372
08-02-21	9:00	106.348	5:00	106.336	106.342

Date	Water level				Average level in metres (MSL)
	Start		End		
	Time (AM)	Level (MSL)	Time (PM)	Level (MSL)	
09-02-21	9:00	106.320	5:00	106.308	106.314
10-02-21	9:00	106.290	5:00	106.277	106.284
11-02-21	9:00	106.261	5:00	106.252	106.257
12-02-21	9:00	106.239	5:00	106.226	106.233
13-02-21	9:00	106.211	5:00	106.197	106.204
14-02-21	9:00	106.173	5:00	106.157	106.165
15-02-21	9:00	106.143	5:00	106.128	106.136
16-02-21	9:00	106.111	5:00	106.101	106.106
17-02-21	9:00	106.084	5:00	106.075	106.080
18-02-21	9:00	106.061	5:00	106.044	106.053
19-02-21	9:00	106.029	5:00	106.012	106.021
20-02-21	9:00	105.993	5:00	105.979	105.986
21-02-21	9:00	105.958	5:00	105.945	105.952
22-02-21	9:00	105.924	5:00	105.910	105.917
23-02-21	9:00	105.891	5:00	105.878	105.885
24-02-21	9:00	105.864	5:00	105.850	105.857

**Table 4: Observed Water Levels**

### 3.3 Survey Vessel

A company owned boat, SMB Ocean, was utilised for conducting the survey operations.



**Figure 5: Survey vessel – SMB Ocean**

## 4 PERSONNEL

The following survey personnel were involved during the survey period.

Name	Designation	Duration
Santokh Chand	Project Manager	Project Duration (In Navi-Mumbai office)
Sunil Kumar Yadav	Party Chief / Surveyor	13 <sup>th</sup> January - 09 <sup>th</sup> February 2021
Salman	Surveyor	13 <sup>th</sup> January - 31 <sup>st</sup> January 2021
Amit Bhardwaj	Surveyor	13 <sup>th</sup> January - 08 <sup>th</sup> February 2021
Binu Kumar	Surveyor	24 <sup>th</sup> January - 08 <sup>th</sup> February 2021
Gaurav Sharma	Party Chief / Survey Engineer	13 <sup>th</sup> January - 08 <sup>th</sup> February 2021
Samson Chacko	Processor	13 <sup>th</sup> January - 08 <sup>th</sup> February 2021
Usha Kadam/ Santosh Wakankar	CAD Processor	Project duration (data processing in office)
Hiraan Joshi	Client Representative	Project duration

**Table 5: Survey Personnel**

## 5 SURVEY EQUIPMENT DETAILS

### 5.1 General

The equipment used for the survey is described below.

#### Bathymetry:

Hemisphere GPS S320 GNSS RTK Base and Rover system with accessories

Odom MK III dual frequency single beam echo sounder system with accessories

TSS HS50 heave sensor

Hypack navigation system

2 x computers with associated accessories

#### Topography:

Hemisphere GPS S320 GNSS RTK Base and Rover system with accessories

Geomax Auto Level with accessories.

Adequate spares and back-ups for critical items will be carried on board the survey vessel to ensure that failure of any hardware unit does not adversely affect progress of field work.

### 5.2 RTK Positioning and Navigation

An RTK system was mobilised at the site to carry out the topographic and bathymetric survey. The system comprises the following:

- Hemisphere GPS R320 GNSS base station
- Hemisphere GPS R320 rover

The base station of the RTK was set up at the temporary benchmark. Real Time Kinematic (RTK) is a technique used to increase the accuracy of GPS signals by using a fixed base station which wirelessly sends out corrections to a moving receiver. By utilising these corrections, the GPS engine can fix the position of the antenna to within 1 - 2cm. GPS Real-Time Kinematic (RTK) operation provides centimetre-level accuracy by eliminating errors that are present in the GPS system. For obtaining corrected positions, a rover receiver and a source of corrections from a base station were used.

Vessel positioning was carried out by the RTK DGPS system and its heading determined by the course made good method (CMG). The positioning system was interfaced to the Hypack navigation software. Vessel track and offset positions were recorded digitally in the navigation software. DGPS positioning accuracy of the moving vessel was better than  $\pm 1\text{m}$ .

The vessel's computed position from the DGPS receiver was interfaced to the navigation computer system. Hypack navigation and data acquisition software was used to provide track guidance information for the survey crew and also output the vessel position to assist the helmsman in maintaining the selected track guidance line. The VDU displays the selected survey line, the vessel position in relation to that line and numerical data to assist the helmsman such as the along-line and off-line distances, vessel speed and course made good, gyro heading, distance and bearing to end of line and water depth. The position of each fix, together with other information such as fix numbers, depths, and down line distances were logged to the hard drive.

Sensor offsets on the survey vessel were accurately measured during mobilisation and are included in the mobilisation report.

### **5.3 Single Beam Echo Sounder System**

Bathymetry data was acquired using a dual frequency 33/200 kHz Echotrac DF 3200 MK III single beam echo sounder. The SBES transducer assembly was side-mounted on a pole on the port side of the boat. A hard copy (paper) record was produced in real-time, annotated with line name, fix number, time and date. The digital output was logged by the navigation computer for post-processing.

#### Calibration

The echo sounder was calibrated at the survey location by conducting a bar-check. The bar-check is carried out by lowering a horizontal steel plate to known, fixed depths below the water surface directly below the echo sounder transducer. Acoustic reflections from the plate at different depths are then recorded and adjustments made to the settings for sound velocity and draft to get accurate results. A bar-check was carried out before commencing the survey and the average speed of sound obtained was entered into the unit.

### **5.4 Heave Sensor**

A TSS HS-50 heave sensor was fixed to the side-mount pole above the SBES. Its output was given to the SBES unit.

### **5.5 Auto Level Geomax**

A Geomax Auto Level was used to transfer the benchmark provided by the client to a local benchmark for easy installation of the ATG at Birla Copper Jetty. It was used to level this local benchmark which was fixed at a depth of 14.96m above CD.

### **5.6 Real Time Kinematic (RTK) For Topographic Survey**

A Hemisphere R320 GNSS RTK system with base station and rover was used to conduct the survey. Base stations were established with respect to F.R.L at the TBM and rover used to fix the positions. This is a positioning system which can measure and calculate the X Y Z of any given point with centimeter level accuracy with respect to the known base positions. An AutoCAD drawing can be generated with the help of the XYZ values obtained from this equipment.

### **5.7 HyPack Software**

Navigation data was processed using the Hypack navigation software. Single beam data from the Echotrac DF 3200 MK III echo sounder was also processed using the Hypack software. Hypack provides all of the tools necessary to complete the hydrographic survey requirements. It provides a tool to design a survey, collect data, apply corrections to soundings, remove outliers, plot field sheets, export data to CAD, compute volume quantities, generate contours, create side scan mosaics and create/modify electronic charts.

## 6 DATA PROCESSING AND INTERPRETATION

This section explains the established terminology and standards for the project and how they were applied to the survey data.

### 6.1 Navigation Data

Raw DGPS and gyro data were processed and merged to form an edited vessel track file. The final navigation data was reviewed in AutoCAD to confirm the validity of the vessel's position and to aid in the correlation between navigation data and chart location.

The survey track plots were then used for data interpretation and generation of the survey charts.

### 6.2 Bathymetric Data

Single beam data from the Echotrac DF 3200 MK III echo sounder was processed using the Hypack navigation package. The vertical datum for all bathymetric measurements was the known MSL value of F.R.L. The depth soundings obtained from the single beam echo sounder were reduced to MSL with the help of the observed water level in the reservoir.

Recorded depth data was adjusted for transducer draft and changes in water mass acoustic velocity as measured during the bar-check.

#### Lakebed Gradient Classification

The following terms were used to describe the lakebed gradients.

CLASSIFICATION	GRADIENT (in terms of Degrees and Slope Interval)	
Very Gentle	<1°	< 1 in 57
Gentle	1° – 4.9°	1 in 57 to 1 in 11.7
Moderate	5° – 9.9°	1 in 11.7 to 1 in 5.7
Steep	10° – 14.9°	1 in 5.7 to 1 in 3.7
Very Steep	>15°	> 1 in 3.7

**Table 6: Classification of gradients**

Gradients documented in the report should be taken as an indication of general slopes for the area. The localised gradients, particularly near features such as depressions or trenches may occasionally be steeper.

Following the data processing and interpretation phase, the charts were prepared at the OSaS data processing centre, in Navi Mumbai. A team comprising a bathymetry data processor, CAD processor and geophysicist prepared the report and accompanying charts to WRD's specifications.

### 6.3 Topographic Data

A Hemisphere R320 GNSS RTK system with base station and rover was used to conduct the survey. This is a positioning system which can measure and calculate the X Y Z of any given point with centimeter level accuracy with respect to the known base positions. The data is downloaded from the controller system, processed in the OSaS Data Processing Centre in Navi Mumbai and formatted to a compatible ASCII format for plotting in AutoCAD.

### 6.4 Charting

The results of the survey conducted during January to March 2021 are presented in twenty-eight charts. The chart details are given after the List of Tables in the beginning of this report.

## 7 SURVEY RESULTS

### 7.1 Survey Area

The elevations mentioned in this report and associated charts have been reduced to Mean Sea Level (M.S.L) using the observed average water level of the Bhadar 1 reservoir for the corresponding survey day. So all the bathymetric and topographic values mentioned in this report are with respect to M.S.L

The M.S.L-reduced bathymetric and topographic data are plotted in 1:5000 scale in a 25m X 25m grid. A total of five charts were created for the purpose of plotting bathymetric and topographic data. For more details refer to **Charting**

The RTK positioning accuracy is metric, resulting in a similar positioning accuracy of single beam echo sounder data since the sensor was side mounted on the vessel.

The following observations are obtained after the processing and interpretation of all the bathymetric and topographic data acquired during the entire period of survey.

A minimum elevation of 95.8m was observed in the southwestern portion of the survey area within the bathymetric section. A maximum topographic elevation value of 117.22m is observed in the northwestern portion of the survey area.

Within the survey area, two major rivers and a few small rivers bring water to the dam area. One major river flows from the north to south and another major river flows from east to west. The average elevation change within the bathymetric area is between 95.83m and 106.96m. Within the bathymetric area, two islands were observed in the southwestern portion and one exposed bridge was observed in the eastern portion.

The processed topographic data shows the land is sloping from all the sides of the survey area towards the dam area. The average elevation change within the topographic area is between 95.83m and 106.96m. Features like temples, ponds, houses, and crematorium were observed within the topographic survey area.

Most of the outer survey area is observed around the 110m elevation contour. In the northwestern portion of the survey area, the elevation slopes from both sides to the central river area with a change in elevation contours from 110m to 98m. The morphology shows a further slope towards the dam gate area in the southwestern portion of the survey area. Irregular topography was observed in the extreme western portion of the survey area.

The central portion of the survey area exhibits a very gentle slope towards the central portion of the dam area from the sides. Moderately irregular bed levels are observed in the central portion of the dam especially south of the dam gates.

The extreme eastern portion of the survey area shows sudden changes from 111m to 103m in elevation contours from both the sides towards the river. Further toward the west the survey area widens and the slope is gentle towards the centre from sides and shows a change in elevation contours between 110m and 98m.

Except near the survey boundary, most of the area of river channels, from north to south and east to west exhibit elevation contours between 100m and 98m, covering a wider area than the 99m contour within the reservoir near to the dam wall

Bathymetric and topographic survey was restricted at some places due to the presence of bushes, ponds, small streams with unsafe and inaccessible marshy ground, exposed rocks in the river and very irregular rock quarries.

The following **Figure 6** shows a 2-dimensional image of the Bhadar 1 reservoir area using the gridded bathymetric and topographic data.




Figure 6: 2D image of the Bhadar 1 reservoir area

## 7.2 Longitudinal Profile

A longitudinal profile of the reservoir was prepared from the line created by connecting the lowest bed level for each survey line. This longitudinal profile is provided in two charts. For more details refer to the charts listed in the section on **Charting**.

## 7.3 Cross Section Profiles

Cross section profiles consist of the bed levels along the survey lines at 100m intervals. The cross section profiles will also be provided in a Compact Disk/USB as per the instructions mentioned for deliverables. For more details refer to the charts listed in the section on **Charting**.



## **8 CAPACITY SURVEY RESULTS**

### **8.1 General**

It is natural for lakes and reservoirs to trap a major part of the sediment brought into them by the streams in the catchment. Sedimentation of reservoirs is therefore a natural process resulting from the geologic and geo-morphologic processes of water borne erosion.

Sedimentation of reservoirs leads to a gradual loss of their storage capacities available for regulation of supplies. Apart from this, it can cause operational problems created by the entry of large volumes of sediments in the canals or in the turbines, as also due to jamming of hydraulic gates. Reservoir sedimentation can also cause ecological problems due to turbidity, and due to gradual delta formation at the upstream end of the reservoirs. Therefore, sedimentation of reservoirs is a matter of vital concern in all water resources development projects.

The two dominant factors which influence the rate of silting in any storage reservoir are: (i) the relationship of capacity to inflow and (ii) the content of sediment in the inflow. The other factors that modify the long-term loss of storage capacities are (a) the trap efficiency of the reservoir, (b) the character of the sediment, and (c) the method of reservoir operation. Basically, these three factors mentioned are modifiers and do not usually have a major effect as compared to the capacity-inflow ratio and the sediment content in the inflow.

It is generally recommended to carry out capacity survey of reservoirs periodically so that the quantity of sedimentation taking place can be assessed and timely remedial measures taken. This also serves as a guide for proper sedimentation planning of future reservoirs to ensure that the reservoir sedimentation does not cause unexpected problems in the useful operation of the reservoir.

The capacity surveys in general, show that the observed rate of sedimentation is higher than the rate of sedimentation adopted in the original designs. However, it is observed that the rate of sedimentation decreases with the passage of time and the useful life of the reservoir may not get unduly reduced in most cases.

### **8.2 Effect of Sedimentation in Planning of Reservoirs**

It is important to note that storage reservoirs built across rivers and streams lose their capacity on account of deposition of sediment. This deposition, which takes place progressively in time, reduces the active capacity of the reservoir to provide the outputs of water through the passage of time. Accumulation of sediment at or near the dam may interfere with the future functioning of water intakes and hence affects decisions regarding location and height of various outlets. It may also result in greater flow of water into canals / water conveyance systems drawing water from the reservoir. Problems of rise in flood levels in the head reaches and unsightly deposition of sediment from a recreation point of view may also crop up in the course of time.

In this regard, the Bureau of Indian Standards code IS: 12182 - 1987 "Guidelines for determination of effects of sedimentation in planning and performance of reservoir" is an important document which discusses some of the aspects of sedimentation that have to be considered while planning reservoirs. Some of the important points from the code are as follows:

While planning a reservoir, the degree of seriousness and the effect of sedimentation at the proposed location have to be judged from studies, which normally consist of a combination of:

1. Performance Assessment (Simulation) Studies with varying rate of sedimentation.
2. Likely effects of sedimentation at the dam face.

In special cases, where the effects of sedimentation on backwater levels are likely to be significant, backwater studies would be useful to understand the size of river water levels. The steps to be followed

for performance assessment studies with varying rates of sedimentation are as follows:

- a. Estimation of annual sediment yields into the reservoir or the average annual sediment yield and of trap efficiency expected.
- b. Distribution of sediment within the reservoir to obtain a sediment elevation and capacity curve at any appropriate time.

### 8.3 EARLIER CAPACITY SURVEY

#### 8.3.1 Capacity survey of 1964

The construction of the Bhadar-1 reservoir was completed in 1964. The following information was extracted from the following document provided by the client.

*Document:* Reservoir Capacity Survey through Remote Sensing Technique of Bhadar (S) reservoir, dated June 2008.

- a. Location
 

Latitude	: 21° - 51' N
Longitude	: 70° - 46' E
- b. Catchment Area : 2406 Sq.Km
- c. Full Reservoir Level (F.R.L) : 107.90 m
- d. Low Water Level (M.D.D.L/L.W.L) : 97.56 m
- e. Dead Water Level (D.W.L/O.S.L) : 97.54
- f. Gross Storage : 237.86 M.Cu.m
- g. Dead Storage : 14.16 M.Cu.m
- h. Live Storage : 223.70 M.Cu.m
- i. Area at F.R.L : 44.00 Sq.Km

#### 8.3.2 Capacity survey of 1979

As per the document provided by the client and the information available in the website of Narmada, Water Resources, Water Supply and Kalpsar Department, Gujarat, a capacity survey had been completed in 1979. The data was provided for intervals of 0.01m and the given report documented the F.R.L at 107.89m instead of an actual figure at 107.90m. For the ease of further calculations and preparation of Elevation-Area-capacity curve, the data has been extracted at regular intervals of approximately 0.5m. **Table 7** shows the Elevation-Area-capacity of 1979 data at these intervals.

#### 8.3.3 Capacity survey of 2021

The water spread area and its corresponding capacity has been calculated from the acquired bathymetry and topographic data. Hypack software's TIN (Triangulated Irregular Network) MODEL package was used to calculate the Area and Capacity of the Bhadar-1 reservoir at intervals of 0.01m with respect to the corresponding elevation above MSL. Within the survey area a few places were not accessible to the survey personnel due to the existing marshy streams, ponds, houses and rock quarries. However, these areas were taken into account while calculating the water spread area by assigning interpolated values with respect to the acquired values around the restricted areas. The detailed Elevation-Area-Capacity data at 0.01m is available in **Annexure 1**. The F.R.L is considered at 107.90m according to the information from the impounding reservoir data. For ease of further calculations and preparation of Elevation-Area-capacity curve, the data has been selected at regular intervals of approximately 0.5m. **Table 7** shows the Elevation-Area-capacity of 2021 data at these intervals.


## 8.4 ELEVATION-AREA-CAPACITY CURVES

One of the most important physical characteristics of dams and their reservoirs are Elevation-Area-Capacity curves. These curves are important for defining the storage capacity of the reservoir and thereby can be used in reservoir operation, reservoir flood routing, determination of capacity and water spread corresponding to each elevation. Limited data is available regarding the capacity survey conducted in 1964, whereas data is available at intervals of 0.01m from the capacity survey conducted in 1979 and 2021. For ease of further calculations and preparation of Elevation-Area-capacity curve, the data has been selected at regular intervals of approximately 0.5m. The following **Table 7** shows the comparative statement of data between 1979 and 2021 at intervals of approximately 0.5m.

Elevation (Above MSL, m)	As per 1979 survey		As per 2021 survey		Remarks
	Gross Capacity (M.Cu.m)	Area (M.Sq.m or Sq.Km)	Gross Capacity (M.Cu.m)	Area (M.Sq.m or Sq.Km)	
97.54 (D.S.L)	0.226	0.743	0.237	0.705	D.S.L
98.02	1.103	1.635	0.873	2.177	
98.51	2.365	2.565	2.404	3.932	
99.02	4.058	3.829	4.768	5.324	
99.52	6.438	4.926	7.720	6.519	
100.00	9.452	6.134	11.179	7.940	
100.52	12.496	7.528	15.719	9.516	
101.01	16.164	9.368	20.779	11.149	
101.50	21.253	11.059	26.632	12.753	
102.02	28.226	13.048	33.839	14.985	
102.50	34.489	15.037	41.518	17.091	
103.02	41.912	17.472	51.084	19.718	
103.51	51.432	19.460	61.382	22.267	
104.00	62.701	21.635	72.955	24.923	
104.51	73.848	24.089	86.302	27.434	
105.00	86.201	26.534	100.363	30.030	
105.52	101.732	29.110	116.775	33.225	
106.01	116.516	31.790	133.829	36.415	
106.50	133.009	34.390	152.483	39.661	
107.01	149.771	37.510	173.419	42.408	
107.50	170.906	39.960	194.809	44.868	
107.89	188.138	42.250	212.703	46.957	
107.90	-	-	213.172	47.013	F.R.L

**Table 7: Comparative statement of Bhadar-1 reservoir**

The above data were used for the preparation of Elevation-Area-Capacity curves. The following figure shows the Elevation-Area-Capacity curves of 2021 superimposed on the 1979 Elevation-Area-Capacity curves.



**Figure 7: Elevation-Area-Capacity Curves**

## 8.5 DATA COMPARISON BETWEEN 1964 AND 2021

### Definitions

**Full Reservoir Level:** Denoted by F.R.L this level corresponds to the storage which includes both inactive and active storage and also the flood storage, it is the highest reservoir level that can be maintained without spillway discharge.

**Minimum Drawdown Level (M.D.D.L):** This is the level below which the water from the reservoir will not be drawn down to maintain a minimum head required in power projects.

**Maximum Water Level (MWL):** This is the water level that is likely to be attained during the passage of the design flood. This level is also called the highest reservoir level or the highest flood level.

**Live storage:** This is the volume of water actually available at any time between the Dead Storage Level and the Full Reservoir Level.

**Dead Storage Level (D.S.L):** This is the level below which there are no outlets to drain the water in the reservoir by gravity.

**Dead storage:** This is the total storage below the invert level of the lowest discharge outlet from the reservoir. It may be available to contain sedimentation, provided the sediment does not adversely affect the lowest discharge.

### 8.5.1 Rate of siltation

Capacity at F.R.L (107.90m) as per pre-impoundment survey 1964	= 237.86 M.Cu.m
Capacity at F.R.L as per 2021 survey	= 213.172 M.Cu.m
Silting in 57 years (1964-2021)	= 237.86 – 213.172 = 24.688 M.Cu.m
Annual Siltation	= 24.688/57= 0.433 M.Cu.m/yr
Rate of Siltation (Silt Index)	= (0.433/2406) x 1000 = 0.18 Th.Cu.m/sq.km/year  = <b>1.80</b> Ha.m/100sq.km./year

### 8.5.2 Loss of gross storage capacity at F.R.L

Capacity at F.R.L (107.90) as per pre-impoundment survey 1964	= 237.86 M.Cu.m
Capacity at F.R.L as per 2021 survey	= 213.172 M.Cu.m
Loss of storage in 57 years (1964-2021)	= 237.86 – 213.172 = 24.688 M.Cu.m
Percentage loss of Gross storage at F.R.L in 57 years	= (24.688/237.86) x 100 = 10.38%
Annual percentage loss	= 10.38/57 = <b>0.18%</b>

### 8.5.3 Loss of dead storage capacity

Capacity at D.S.L (97.54m) as per pre-impoundment survey 1964	= 14.16 M.Cu.m
Capacity at D.S.L as per 2021 survey	= 0.237 M.Cu.m
Loss of storage up to D.S.L	= 14.16 – 0.237 = 13.923 M.Cu.m
Percentage loss of dead storage capacity in 57 years	= (13.923/14.16) x 100 = 98.33%
Annual percentage loss	= 98.33/57 = <b>1.73%</b>

#### 8.5.4 Loss of live storage capacity

Live storage capacity as per pre-impoundment survey 1964	= 237.86 – 14.16 = 223.70 M.Cu.m
Live storage capacity as per 2021 survey	= 213.172 – 0.237 = 212.935 M.Cu.m
Loss of live storage capacity	= 223.70 – 212.935 = 10.765 M.Cu.m
Percentage loss of live storage capacity in 57 years	= (10.765/223.70) x 100 = 4.81%
Annual percentage loss	= 4.81/57 = <b>0.08%</b>

## 8.6 SUMMARY OF CAPACITY SURVEYS (1964 and 2021)

### Original Reservoir Data:

Year of impounding	: 1964
Catchment Area	: 2406.00 Sq.Km
Spread area at F.R.L (107.90m)	: 44.00 Sq.Km
Gross storage at F.R.L (107.90m)	: 237.86 M.Cu.m
Dead storage at D.S.L (97.54m)	: 14.16 M.Cu.m
Live storage at F.R.L (107.90m)	: 223.70 M.Cu.m

Rate of sedimentation (at F.R.L 107.90m) with respect to impounding year 1964													
Sr. No	Year of Survey	Capacity in M.Cu.m			Silt Deposited in M.Cu.M	Period in years	Silt Rate in M.Cu.m/Year	Loss in Capacity in M.Cu.M and percentage			Silt Index ham/100 Sq.Km/Yr	Annual % loss of capacity	Remarks
		Dead	Live	Gross				Dead	Live	Gross			
1	1964	14.16	223.700	237.860	-	-	-	-	-	-	-	-	-
3	2021	0.237	212.935	213.172	24.688	57	0.433	13.923 98.33%	10.765 4.81%	24.688 10.38%	1.80	0.18	Significant Category

**Table 8: Rate of Sedimentation at F.R.L (107.90m)**

### According to IS-12182 (1987)

#### Annual % loss - Class of Reservoir

Up to 0.1	-	Insignificant
0.1 to 0.5	-	Significant
Above 0.5	-	Serious

Rate of Silt	-	Loss in Gross Capacity/No of Years
Silt Index	-	Silt rate/Catchment area) x 10000
Annual % Loss	-	Loss in % of Gross Capacity/No. of years

## 8.7 DATA COMPARISON BETWEEN 1964, 1979, 2003, 2004 AND 2021

For Bhadar-1 reservoir, a number of capacity surveys were conducted in the past. The following table gives the dates of the previous capacity surveys.

Sr. No	Year	Type of survey
1	1964	Survey at impounding
2	1979	Hydrographic survey
3	2004	Hydrographic survey
4	2008	Remote sensing survey for the period 2001 -2003

**Table 9: Dates of the previous surveys**

The available report for Bhadar-1 dam, provided by the client, is “*Reservoir Capacity Survey through Remote Sensing Technique of Bhadar (S) reservoir*”, conducted by Gujarat Engineering Research Institute. In this 2008 report of surveys carried out in 2001-2003, all the calculations were between 97.56m (M.D.D.L) and **106.41m (1.49m below F.R.L)**.

Hence the following **Table 10** summarises the results the calculations carried out for Bhadar-1 reservoir at **106.41m below F.R.L**.



**Original Reservoir Data at 106.41m (1.49m below F.R.L):**

Year of impounding : 1964  
 Catchment Area : 2406.00 Sq.Km  
 Gross storage at F.R.L (106.41m) : 176.87 M.Cu.m  
 Dead storage at D.S.L (97.54m) : 14.16 M.Cu.m  
 Live storage at F.R.L (106.41m) : 162.71 M.Cu.m

Rate of sedimentation (at 106.41m) with respect to impounding year													
Sr. No	Year of Survey	Capacity in M.Cu.m			Silt Deposited in M.Cu.M	Period in years	Silt Rate in M.Cu.m /Year	Loss in Capacity in M.Cu.M and percentage			Silt Index ham/100 Sq.Km/Yr	Annual % loss of capacity	Remarks
		Dead	Live	Gross				Dead	Live	Gross			
1	1964	14.16	162.71	176.87	46.875	0	0	0	0	0	0.00	0	-
2	1979	0.258	129.737	129.995	40.427	15	3.125	13.902 98.18%	32.973 20.26%	46.875 26.50 %	12.99	1.77	<b>Serious Category</b>
3	2008 (2001-2003)	0.286	136.157	136.443	32.23	39	1.037	13.874 97.98%	26.553 16.32%	40.427 22.86%	4.31	0.59	<b>Serious Category</b>
4	2004	0.327	144.313	144.64	27.932	40	0.806	13.833 97.69%	18.397 11.31%	32.23 18.22%	3.35	0.46	<b>Significant Category</b>
5	2021	0.251	148.687	148.938	46.875	57	0.490	13.909 98.23%	14.023 8.62%	27.932 15.79%	2.04	0.28	<b>Significant Category</b>

**Table 10: Rate of Sedimentation at 106.41m (1.49m below F.R.L)**

**According to IS-12182 (1987)**

**Annual % loss - Class of Reservoir**

Up to 0.1 - Insignificant  
 0.1 to 0.5 - Significant  
 Above 0.5 - Serious

Rate of Silt – Loss in Gross Capacity/No of Years  
 Silt Index – Silt rate/Catchment area) x 10000  
 Annual % Loss – Loss in % of Gross Capacity/No. of years

## 8.8 DATA COMPARISON BETWEEN 1979 AND 2021

As per the 1979 survey, the F.R.L was fixed at 107.89m. Therefore, for ease of calculation, all the data is compared with respect to the elevation at 107.89m. For the Bhadar-1 reservoir, the water spread area at this level decreased from 44 km<sup>2</sup> to 42.25 km<sup>2</sup> between 1964 and 1979, possibly due to sedimentation along the banks of the reservoir and also because of less rainfall and runoff to the reservoir during the time of the survey. While comparing the data of 1979 and 2021, a significant increase in water spread area was observed from 42.25 km<sup>2</sup> to 46.96 km<sup>2</sup> at the elevation of 107.89m. The increase in area may possibly have been because of the conversion of reservoir banks and irregular flood plain into more flattened agricultural land. The increase in area reflects an increase in capacity of the reservoir. This will ultimately show an erosional condition of the reservoir rather than an expected siltation and corresponding loss of storage.

### 8.8.1 Rate of erosion

Capacity at 107.89m as per the survey at 1979	= 188.138 M.Cu.m
Capacity at 107.89 as per 2021 survey	= 212.703 M.Cu.m
Erosion in 42 years (1979-2021)	= 212.703 – 188.138 = 24.565 M.Cu.m
Annual erosion	= 24.565/42 = 0.585 M.Cu.m/yr
Rate of erosion	= (0.585/2406) x 1000 = 0.24 Th.Cu.m/sq.km/year  = <b>2.4 Ha.m/100sq.km./year</b>

### 8.8.2 Increase in Gross storage capacity at 107.89m

Capacity at 107.89m as per the survey at 1979	= 188.138 M.Cu.m
Capacity at 107.89 as per 2021 survey	= 212.703 M.Cu.m
Increase in storage in 42 years (1979-2021)	= 212.703 – 188.138 = 24.565 M.Cu.m
Percentage increase of gross storage at F.R.L in 42 years	= (24.565/188.138) x 100 = 13.06%
Annual percentage increase	= 13.06/42 = <b>0.31%</b>

### 8.8.3 Increase in dead storage capacity

Capacity at D.S.L (97.54m) as per the survey at 1979	= 0.226 M.Cu.m
Capacity at D.S.L as per 2021 survey	= 0.237 M.Cu.m
Increase of storage up to D.S.L	= 0.237 – 0.226 = 0.011 M.Cu.m
Percentage increase of dead storage capacity in 42 years	= (0.011/0.226) x 100 = 4.87%
Annual percentage increase	= 4.87/42 = <b>0.12%</b>

#### 8.8.4 Increase in live storage capacity

Live storage capacity as per the survey at 1979	= 188.138 – 0.266 = 187.912 M.Cu.m
Live storage capacity as per 2021 survey	= 212.703 – 0.237 = 212.466 M.Cu.m
Increase of live storage capacity	= 212.466 – 187.912 = 24.554 M.Cu.m
Percentage increase of live storage capacity in 42 years	= (24.554/188.138) x 100 = 13.07%
Annual percentage increase	= 13.07/42 = <b>0.31%</b>

## 8.9 SUMMARY OF CAPACITY SURVEYS (1979 and 2021)

### Original Reservoir Data:

Year of impounding	: 1964
Year of silt survey	: 1979
Catchment Area	: 2406.00 Sq.Km
Spread area at F.R.L (107.89m)	: 42.25 Sq.Km
Gross storage at F.R.L (107.89m)	: 188.138 M.Cu.m
Dead storage at D.S.L (97.54m)	: 0.226 M.Cu.m
Live storage at F.R.L (107.89m)	: 187.912 M.Cu.m

Rate of erosion (at F.R.L 107.89m) with respect to silt survey in 1979													
Sr. No	Year of Survey	Capacity in M.Cu.m			Silt eroded in M.Cu.M	Period in years	Erosion Rate in M.Cu.m/Year	Increase in Capacity in M.Cu.M and percentage			Erosion Index ham/100 Sq.Km/Yr	Annual % increase of capacity	Remarks
		Dead	Live	Gross				Dead	Live	Gross			
2	1979	0.226	187.912	188.138	-	-	-	-	-	-	-	-	-
3	2021	0.237	212.466	212.703	24.565	42	0.585	0.011 4.87%	24.554 13.07%	24.565 13.06%	2.4	0.31	Significant Category

Table 11: Rate of Sedimentation at F.R.L (107.89m)

### According to IS-12182 (1987)

#### Annual % loss - Class of Reservoir

Up to 0.1	-	Insignificant
0.1 to 0.5	-	Significant
Above 0.5	-	Serious

Rate of Silt	-	Loss in Gross Capacity/No of Years
Silt Index	-	Silt rate/Catchment area) x 10000
Annual % Loss	-	Loss in % of Gross Capacity/No. of years

Note: As per the 1979 survey data, the F.R.L is marked at 107.89m. Gross storage at this elevation was used for calculations.

## 8.10 LOSS OF STORAGE DUE TO SEDIMENT DEPOSIT

Reservoirs, created by dams on rivers, lose their storage capacity due to sedimentation. A large proportion of the transported silt eventually gets deposited at different levels of a reservoir and causes reduction not only in dead storage but also in live storage capacities. The consequence of loss in storage due to sediment accumulation may even cause operational problems. Periodic capacity survey of a reservoir is thus essential to ascertain the rate of sedimentation and reduction in storage capacity for efficient and productive management of water resources. Reservoir siltation affects the safety of an old reservoir since the sediment in the reservoirs increases the load on the wall of the dam.

For Bhadar 1 reservoir, the comparison of current capacity data with the previous capacity data of 1964 survey shows a decrease in capacity at all levels, including the dead storage and live storage which ultimately results in a decrease in gross storage capacity. The change in storage capacity is directly proportional to the amount of sediment deposited. The sediment deposition may occur not only in the dead storage area but also at all levels of dead and live storage areas.

The detailed comparison of current capacity data at different levels to the previous capacity data of the 1979 survey shows an increase in capacity within the dead storage and live storage areas except at 98.02m elevation, where sediment deposition was noticed. This increase in capacity could be due to the further deepening of the river channel or the sediment removal, possibly due to a flood. Another possibility is that the changes in the water spread area at FRL due to conversion of irregular land area into levelled cultivation fields.

The increase or loss in capacity within in the reservoir is directly proportional to the amount of sediment removed or deposited within the reservoir. This sediment removal or deposition can occur at any level of the reservoir throughout the live and dead storage area. This removal or deposition of the sediment within the reservoir results in a corresponding increase or loss of capacity.

For ease of reporting, the previous capacity data in the 1979 survey and current capacity data in the 2021 survey were selected at regular intervals. The following **Table 12** shows the amount of erosion and deposition of sediment at different levels from the DSL to F.R.L and corresponding percentage increase or loss in capacity at different levels.

Elevation (Above MSL, m)	Capacity 1979 (M.Cu.m)	Area 2021 (M.Sq.m or Sq.Km)	Capacity 2021 (M.Cu.m)	Erosion / Deposition of Sediment (M.Cu.m)	% Increase / Loss of Capacity
97.54	0.226	0.71	0.237	0.011	4.64
98.02	1.103	2.18	0.873	0.230*	20.85**
98.51	2.365	3.93	2.404	0.039	1.62
99.02	4.058	5.32	4.768	0.710	14.89
99.52	6.438	6.52	7.720	1.282	16.61
100.00	9.452	7.94	11.179	1.727	15.45
100.52	12.496	9.52	15.719	3.223	20.50
101.01	16.164	11.15	20.779	4.615	22.21
101.50	21.253	12.75	26.632	5.379	20.20
102.02	28.226	14.99	33.839	5.613	16.59
102.50	34.489	17.09	41.518	7.029	16.93

Elevation (Above MSL, m)	Capacity 1979 (M.Cu.m)	Area 2021 (M.Sq.m or Sq.Km)	Capacity 2021 (M.Cu.m)	Erosion / Deposition of Sediment (M.Cu.m)	% Increase / Loss of Capacity
103.02	41.912	19.72	51.084	9.172	17.95
103.51	51.432	22.27	61.382	9.950	16.21
104.00	62.701	24.92	72.955	10.254	14.06
104.51	73.848	27.43	86.302	12.454	14.43
105.00	86.201	30.03	100.363	14.162	14.11
105.52	101.732	33.23	116.775	15.043	12.88
106.01	116.516	36.42	133.829	17.313	12.94
106.50	133.009	39.66	152.483	19.474	12.77
107.01	149.771	42.41	173.419	23.648	13.64
107.50	170.906	44.87	194.809	23.903	12.27
107.89	188.138	46.96	212.703	24.565	11.55

**Table 12: Loss/increase of storage capacity between 1979 and 2021**

Note:

- Values highlighted with single asterisks (\*) represents the volume of sediment deposited.
- Values highlighted with double asterisks (\*\*) represents the percentage (%) decrease of storage capacity.

The amount of silt present in any reservoir is attributed to the geological nature of the area surrounding the reservoir. If the area is rich in silt, definitely any reservoir located within the area will have a greater proportion of silt in any sediment transported into it. Since erosion sedimentation is a serious problem in different parts of the world today resulting in several reservoirs becoming completely silted over, designers should aim at the following mitigation measures of soil erosion and sediment transport processes:

- Prevention of further land degradation in any catchment to reduce siltation
- Prevention of soil erosion from catchment to reduce siltation of reservoir
- Ensuring adequate irrigation water to the demand area
- Improving land capability moisture regime in the watershed
- Improving land use to match capability
- Maintaining ecological balance in a catchment area
- Educating people in the management of a catchment

## 8.11 CONTROL OF SEDIMENTATION IN RESERVOIRS

Sedimentation in a reservoir is a natural process which affects the capacity of the reservoir. Excess deposition of sediment directly affects the useful capacity of the reservoir based on the project requirements like irrigation, hydroelectric power, flood control etc. The rate of deposition of sediment largely depends on the annual sediment load carried by the streams and up to what extent the sediment is retained in the reservoir. This, in turn, depends upon a number of factors such as the area and nature of the catchment, level use pattern (cultivation practices, grazing, logging, construction activities and conservation practices), rainfall pattern, storage capacity, period of storage in relation to the sediment

load of the stream, particle size distribution in the suspended sediment, channel hydraulics, location and size of sluices, outlet works, configuration of the reservoir, and the method and purpose of releases through the dam. An appropriate approach to these factors mentioned above is essential for efficient control of sedimentation and therefore to extend the life of the reservoir.

There are numerous techniques developed to control the sedimentation in reservoirs, broadly classified as

- I. Suitable design of reservoir
- II. Restrict the sediment inflow
- III. Limit the sediment deposition
- IV. Regular removal of deposited sediment

### **8.11.1 Suitable design of reservoir**

The volume of discharge directly affects the rate of sedimentation. The rate of sedimentation increases with the volume of discharge. The higher deposition of sediment within a reservoir increases the surface area of the water, thereby resulting in greater loss of water by evaporation. This will ultimately decrease of storage capacity which in turn lowers the trap efficiency of the reservoir.

The capacity of the reservoir and the size and characteristics of the reservoir and its drainage area are the most important factors governing the annual rate of accumulation of sediment. Periodic reservoir sediment surveys provide information about the rate of sediment deposited, hence can enable us to make necessary steps to limit the same. The sedimentation may take place not only in the dead storage area of a reservoir; reservoir studies have revealed significant deposition of sediment in the live storage area of a reservoir as well.

The capacity of reservoirs largely depends on various factors. Hence the following points need to be considered for their optimum design.

- Topographical, geological and geomorphological factors which directly affect the sediment yield
- Sediment delivery characteristics of the channel system
- The efficiency of the reservoir as a sediment trap
- The ratio of capacity of the reservoir to the inflow
- Configuration of the reservoir
- Method of operation of the reservoir
- Provisions for silt exclusion

### **8.11.2 Restrict the sediment inflow**

The sediment inflow to the reservoirs can be controlled by proper watershed management and soil conservation measures to check production and transport of sediment to the catchment area. Also adopt adequate preventive measures to check the inflow of sediment into the reservoir. Soil conservation involves the prevention of loss of the topmost layer of the soil from erosion or prevention of reduced fertility caused by over usage, acidification, salinization or other chemical soil contamination. The soil conservation measures are further sub-divided as

- Engineering
- Agronomy
- Forestry

#### ***Engineering methods***

##### ***Check dams***

One of the methods of soil conservation is the use of check dams. A check dam is a small dam which can be either temporary or permanent, built across a minor channel, swale, or drainage ditch. They are used to slow the velocity of concentrated water flows, a practice that helps reduce erosion.

### *Contour trenching and bunding*

In the contour trenching method, the surrounding area of the reservoir is ploughed, like contour lines. These contour lines create a water break which reduces the formation of rills and gullies during times of heavy precipitation, allowing more time for the water to settle into the soil. Also, trenches can be artificially dug along the contour lines. Water flowing down the hill is retained by the trenches, and infiltrates the soil below. Manually dug trenches are smaller, machine dug trenches can be deeper. The dimensions and the format of the trenches should correspond to the local climate and soil conditions.

A similar practice is contour bunding where stones are placed around the contours of slopes. Contour bunding or contour bundling, and contour farming involves the placement of lines of stones along the natural rises of a landscape. These techniques help to capture and hold rainfall before it can become runoff. Contour bunds also help to control soil erosion.

### *Gully Plugging*

A gully plug is a small, temporary or permanent dam constructed across a drainage ditch, swale, or channel to lower the speed of concentrated flows. These dams can be constructed using locally available materials. These small dams reduce the speed of water flow and minimise the erosive power of runoff. They also promote the deposition of eroded materials to further stabilise the gullies.

### ***Agronomy methods***

Agronomic conservation measures function by reducing the impact of raindrops through interception and thus reducing soil erosion and increasing infiltration rates, and also reducing surface runoff and soil erosion. The major agronomic soil and water conservation practices are strip cropping, mixed cropping, intercropping, fallowing, mulching, contour ploughing, crop rotation, conservation tillage, and agroforestry.

### ***Forestry methods***

Forestry measures include forest conservancy, control on grazing, lumbering operations and forest fires along with management and protection of forest plantations.

## **8.11.3 Limit sediment deposition**

The amount of suspended sediment is comparatively large during and just after flood flow. The settlement of sediment in the reservoir can be controlled by adequate operation of outlets in such a manner as to permit selective withdrawals of water having a higher-than-average sediment content. Thus, more water wasted at peak time of inflow will result a low level of sediment to deposit in the reservoir. There are two methods:

### ***Density Current***

Water at various levels of a reservoir often contains radically different concentrations of suspended sediment, particularly during and after flood flows and if all waste-water could be withdrawn at those levels where the concentration is highest, a significant amount of sediment might be removed from the reservoir. The density differences between the sediment-laden inflow and the clear water in the reservoir leads to a turbidity current which plunges beneath the clear water and moves towards the dam as a submerged current. The proper allocation of gates or sluices can remove a significant amount of sediment-saturated water and therefore can reduce the amount of sedimentation.

### ***Waste-Water Release***

This method is applicable only when a reservoir is of such a size that a small part of large flood flows will fill it. A series of outlets at various elevations can eject sediment-saturated water. This method, which can remove considerable amount of sediment from the reservoir through proper gate control, will differ greatly with different locations. The drawback of this method is that waste-water release is only possible when water can be or should be wasted.



#### **8.11.4 Regular removal of deposited sediment**

Removal of accumulated sediment is considered as the last resort as the operations are very expensive unless the excavated sediment is economically usable. The removal of sediment deposits may be accomplished by a variety of mechanical and hydraulic methods, such as excavation, dredging, draining and flushing, sluicing aided by such measures as hydraulic or mechanical agitation or blasting of the sediment.

##### ***Excavation***

Excavation is the removal of the sediment by hand or power operated shovel, dragline scraper or other mechanical means after draining most of the water. The excavation of silt and clay which constitute most of the material in larger reservoirs is more difficult than the excavation of sand and gravel. Fine-textured sediment cannot be excavated easily from larger reservoirs unless it is relatively fluid or relatively compact.

##### ***Dredging***

In this method, the deposit is removed from the bottom of the reservoir irrespective of the level of storage using mechanical or hydraulic equipment. The various types of dredging are mechanical dredging by bucket, suction dredging with floating pipeline and a pump on a barge and siphon dredging with a floating pipe extending over the dam or connected to an opening in the dam and with a pump on a barge.

##### ***Draining and flushing***

This method, also called flood sluicing, involves a relatively slow release of all stored water in a reservoir through gates or valves located near the bottom of the dam and the maintenance thereafter of open outlets for a shorter or longer period during which normal stream flow cuts into or is directed against the sediment deposits.

##### ***Sluicing with Controlled Water***

In this method the controlled water supply permits choosing the time of sluicing more advantageously and the water may be directed more effectively against the sediment deposits. While the flood sluicing depends either on the occurrence of flood or on being able to release rapidly all of a full or nearly full supply of water in the main reservoir. The advantage of this method is that generally more sediment can be removed per unit of water used than in flood scouring or draining and flushing.

##### ***Sluicing with Hydraulics and Mechanical Agitation***

In this method, stirring up, breaking up or moving deposits of a sediment into a stream current moving through a drained reservoir basin or into a full reservoir will tend to make the removal of sediment from the reservoir more complete. Wherever draining, flushing or sluicing appear to be warranted, the additional use of hydraulic means for stirring up the sediment deposits, or sloughing them off, into a stream flowing through the reservoir basin should be considered.

## 9 CONCLUSIONS

- Bhadar-1 reservoir was completed in 1964. With an area of 44.00 km<sup>2</sup>, Full Reservoir Level (F.R.L) of the Bhadar 1 reservoir is 107.90m above M.S.L over a Catchment Area of 2406 km<sup>2</sup>. The gross storage (at F.R.L:107.90) and dead storage (at D.S.L:97.54) at the time of impounding are 237.86 M.Cu.m and 14.16 M.Cu.m respectively.
- Reports of four capacity surveys were provided to us for comparison with the current survey; 1964, 1979, 2004 and 2008 (period 2001 -2003) using hydrographic and remote sensing techniques.
- In the current bathymetric and topographic survey, a minimum elevation of 95.8m was observed in the southwestern portion of the survey area within the bathymetric section. A maximum topographic elevation value of 117.22m is observed in the northwestern portion of the survey area.
- The survey was extended till the High Flood Level (H.F.L:110.33m). Except near the survey boundary, most of the area of river channels are observed running from north to south and east to west, with elevation contours between 100m and 98m and covering a wide area of 99m contour within the area near the dam gates
- The comparison between 1964 and 2021 (57 years) data results shows a rate of siltation (Silt Index) at a rate of 1.80 Ha.m/100sq.km./year. Annual percentage loss of gross storage capacity, live storage capacity and dead storage capacity are 0.18%, 0.08% and 1.73% respectively.
- The comparison between 1964 and 1979 (15 years) data results shows a rate of siltation (Silt Index) at a rate of 13.78 Ha.m/100sq.km./year. Annual percentage loss of gross storage capacity is 1.39.
- The comparison between 1979 and 2021 (42 years) data results indicates a significant increase in water spread area, from 42.25 km<sup>2</sup> to 46.96 km<sup>2</sup> at 107.89m. The corresponding increase in volume resulted in an erosion phase during this period. The rate of erosion is calculated as 2.4 Ha.m/100sq.km./year.
- The comparison of 1979, 2003, 2004 and 2021 data with respect to the 1964 impounding data at 106.41m (1.49m below F.R.L) shows the silt index at the rate of Ha.M/100 sq.km/year to be 12.99, 4.31, 3.35 and 2.04 respectively.
- The comparison of current capacity data to the previous capacity data of 1964 survey shows a decrease in capacity at all levels, resulting in a decrease in gross storage capacity, with a corresponding volume of sediment deposited at all levels of the reservoir.
- The detailed comparison of current capacity data at different levels with the previous capacity data of the 1979 survey shows an increase in capacity within the dead storage and live storage areas except at 98.02m elevation, where sediment deposition was noticed.
- The increase in capacity from 1979 to 2021 is possibly due to the further deepening of the river channel or sediment removal, possibly due to a flood or changes in the water spread area at FRL by the conversion of irregular land area into levelled cultivation fields.
- The removal or deposition of the sediment within the reservoir results in a corresponding increase or loss of storage capacity.

## 10 REFERENCES

1. Wikipedia - [https://en.wikipedia.org/wiki/Bhadar\\_River](https://en.wikipedia.org/wiki/Bhadar_River)
2. Website - <https://guj-nwrws.gujarat.gov.in/showpage.aspx?contentid=1&lang=English>
3. CE IIT, Kharagpur - <https://nptel.ac.in/content/storage2/courses/105105110/pdf/m4I05.pdf>
4. *Siltation in reservoirs* by C.N. Mama and F.O. Okafor
5. *Space Technology in Assessment of Loss in Live Storage Capacity of Reservoir* by Karishma Bhatnagar Malhotra, Rishi Srivastava and Amrendra Kumar Singh.
6. *Erosion and reservoir sedimentation* by The McGraw Hill Companies.
7. *Soil erosion, sediment yield and sedimentation of reservoir* by S. Dutta
8. *Statement showing the details of dams in Gujarat (report\_15-03-2021)* by N.W.R.W.S.AND KALPSAR DEPARTMENT.
9. *Hydrological model for design flood estimation for the Bhadar dam* by Jahnvi Bhatt, P.H. Pandya and Prof H.M. Gandhi

**Annexure - 1**  
**Elevation Area Capacity**  
**Bhadar 1 Reservoir**

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
314.40	95.83	0.005	0.000	0.000	0.000	0.00	0.000
314.44	95.84	0.006	0.001	0.000	0.000	0.00	0.000
314.47	95.85	0.007	0.001	0.000	0.000	0.00	0.000
314.50	95.86	0.008	0.001	0.000	0.000	0.00	0.000
314.53	95.87	0.010	0.001	0.000	0.000	0.00	0.000
314.57	95.88	0.011	0.001	0.000	0.000	0.00	0.000
314.60	95.89	0.013	0.001	0.000	0.000	0.00	0.000
314.63	95.9	0.015	0.001	0.000	0.000	0.00	0.000
314.67	95.91	0.018	0.002	0.000	0.000	0.00	0.000
314.70	95.92	0.020	0.002	0.000	0.000	0.00	0.000
314.73	95.93	0.023	0.002	0.000	0.000	0.01	0.000
314.76	95.94	0.026	0.002	0.000	0.000	0.01	0.000
314.80	95.95	0.029	0.003	0.000	0.000	0.01	0.000
314.83	95.96	0.032	0.003	0.000	0.000	0.01	0.000
314.86	95.97	0.035	0.003	0.000	0.000	0.01	0.000
314.90	95.98	0.039	0.004	0.000	0.000	0.01	0.000
314.93	95.99	0.043	0.004	0.000	0.000	0.01	0.000
314.96	96	0.048	0.004	0.000	0.000	0.01	0.000
314.99	96.01	0.052	0.005	0.000	0.000	0.01	0.000
315.03	96.02	0.059	0.005	0.000	0.000	0.02	0.000
315.06	96.03	0.066	0.006	0.000	0.000	0.02	0.001
315.09	96.04	0.074	0.007	0.000	0.000	0.02	0.001
315.12	96.05	0.082	0.008	0.000	0.000	0.02	0.001
315.16	96.06	0.088	0.008	0.000	0.000	0.03	0.001
315.19	96.07	0.094	0.009	0.000	0.000	0.03	0.001
315.22	96.08	0.101	0.009	0.000	0.000	0.03	0.001
315.26	96.09	0.108	0.010	0.000	0.000	0.04	0.001
315.29	96.1	0.115	0.011	0.000	0.000	0.04	0.001
315.32	96.11	0.122	0.011	0.000	0.000	0.04	0.001
315.35	96.12	0.129	0.012	0.000	0.000	0.05	0.001
315.39	96.13	0.137	0.013	0.000	0.000	0.05	0.001
315.42	96.14	0.144	0.013	0.000	0.000	0.06	0.002
315.45	96.15	0.152	0.014	0.000	0.000	0.06	0.002
315.49	96.16	0.161	0.015	0.000	0.000	0.07	0.002
315.52	96.17	0.170	0.016	0.000	0.000	0.07	0.002
315.55	96.18	0.180	0.017	0.000	0.000	0.08	0.002
315.58	96.19	0.190	0.018	0.000	0.000	0.08	0.002
315.62	96.2	0.200	0.019	0.000	0.000	0.09	0.003
315.65	96.21	0.211	0.020	0.000	0.000	0.10	0.003
315.68	96.22	0.221	0.021	0.000	0.000	0.10	0.003
315.72	96.23	0.231	0.021	0.000	0.000	0.11	0.003
315.75	96.24	0.241	0.022	0.000	0.000	0.12	0.003

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
315.78	96.25	0.251	0.023	0.000	0.000	0.13	0.004
315.81	96.26	0.261	0.024	0.000	0.000	0.14	0.004
315.85	96.27	0.271	0.025	0.000	0.000	0.14	0.004
315.88	96.28	0.281	0.026	0.000	0.000	0.15	0.004
315.91	96.29	0.290	0.027	0.000	0.000	0.16	0.005
315.94	96.3	0.300	0.028	0.000	0.000	0.17	0.005
315.98	96.31	0.311	0.029	0.000	0.000	0.18	0.005
316.01	96.32	0.321	0.030	0.000	0.000	0.19	0.005
316.04	96.33	0.330	0.031	0.000	0.000	0.20	0.006
316.08	96.34	0.339	0.032	0.000	0.000	0.21	0.006
316.11	96.35	0.349	0.032	0.000	0.000	0.23	0.006
316.14	96.36	0.358	0.033	0.000	0.000	0.24	0.007
316.17	96.37	0.368	0.034	0.000	0.000	0.25	0.007
316.21	96.38	0.377	0.035	0.000	0.000	0.26	0.007
316.24	96.39	0.386	0.036	0.000	0.000	0.27	0.008
316.27	96.4	0.395	0.037	0.000	0.000	0.29	0.008
316.31	96.41	0.404	0.037	0.000	0.000	0.30	0.008
316.34	96.42	0.413	0.038	0.000	0.000	0.31	0.009
316.37	96.43	0.422	0.039	0.000	0.000	0.33	0.009
316.40	96.44	0.431	0.040	0.000	0.000	0.34	0.010
316.44	96.45	0.441	0.041	0.000	0.000	0.36	0.010
316.47	96.46	0.450	0.042	0.000	0.000	0.37	0.010
316.50	96.47	0.460	0.043	0.000	0.000	0.38	0.011
316.54	96.48	0.470	0.044	0.000	0.000	0.40	0.011
316.57	96.49	0.479	0.045	0.000	0.000	0.42	0.012
316.60	96.5	0.489	0.045	0.000	0.000	0.43	0.012
316.63	96.51	0.499	0.046	0.000	0.000	0.45	0.013
316.67	96.52	0.509	0.047	0.000	0.000	0.46	0.013
316.70	96.53	0.518	0.048	0.000	0.000	0.48	0.014
316.73	96.54	0.528	0.049	0.000	0.000	0.50	0.014
316.77	96.55	0.538	0.050	0.000	0.000	0.52	0.015
316.80	96.56	0.548	0.051	0.000	0.000	0.53	0.015
316.83	96.57	0.558	0.052	0.000	0.000	0.55	0.016
316.86	96.58	0.568	0.053	0.000	0.000	0.57	0.016
316.90	96.59	0.578	0.054	0.000	0.000	0.59	0.017
316.93	96.6	0.589	0.055	0.000	0.000	0.61	0.017
316.96	96.61	0.600	0.056	0.000	0.000	0.63	0.018
316.99	96.62	0.611	0.057	0.000	0.000	0.65	0.018
317.03	96.63	0.623	0.058	0.000	0.000	0.67	0.019
317.06	96.64	0.634	0.059	0.000	0.000	0.69	0.019
317.09	96.65	0.646	0.060	0.000	0.000	0.71	0.020
317.13	96.66	0.658	0.061	0.000	0.000	0.73	0.021
317.16	96.67	0.672	0.062	0.000	0.000	0.75	0.021

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
317.19	96.68	0.687	0.064	0.000	0.000	0.77	0.022
317.22	96.69	0.702	0.065	0.000	0.000	0.80	0.023
317.26	96.7	0.717	0.067	0.000	0.000	0.82	0.023
317.29	96.71	0.734	0.068	0.000	0.000	0.84	0.024
317.32	96.72	0.751	0.070	0.000	0.000	0.87	0.025
317.36	96.73	0.769	0.071	0.000	0.000	0.89	0.025
317.39	96.74	0.788	0.073	0.000	0.000	0.92	0.026
317.42	96.75	0.808	0.075	0.000	0.000	0.95	0.027
317.45	96.76	0.829	0.077	0.000	0.000	0.97	0.028
317.49	96.77	0.850	0.079	0.000	0.000	1.00	0.028
317.52	96.78	0.870	0.081	0.000	0.000	1.03	0.029
317.55	96.79	0.892	0.083	0.000	0.000	1.06	0.030
317.59	96.8	0.914	0.085	0.000	0.000	1.09	0.031
317.62	96.81	0.937	0.087	0.000	0.000	1.12	0.032
317.65	96.82	0.961	0.089	0.000	0.000	1.15	0.033
317.68	96.83	0.986	0.092	0.000	0.000	1.18	0.033
317.72	96.84	1.013	0.094	0.000	0.000	1.21	0.034
317.75	96.85	1.043	0.097	0.000	0.000	1.25	0.035
317.78	96.86	1.076	0.100	0.000	0.000	1.28	0.036
317.81	96.87	1.107	0.103	0.000	0.000	1.32	0.037
317.85	96.88	1.137	0.106	0.000	0.000	1.35	0.038
317.88	96.89	1.167	0.108	0.000	0.000	1.39	0.039
317.91	96.9	1.198	0.111	0.000	0.000	1.43	0.041
317.95	96.91	1.231	0.114	0.000	0.000	1.47	0.042
317.98	96.92	1.263	0.117	0.000	0.000	1.51	0.043
318.01	96.93	1.294	0.120	0.000	0.000	1.55	0.044
318.04	96.94	1.326	0.123	0.000	0.000	1.60	0.045
318.08	96.95	1.358	0.126	0.000	0.000	1.64	0.046
318.11	96.96	1.390	0.129	0.000	0.000	1.69	0.048
318.14	96.97	1.424	0.132	0.000	0.000	1.73	0.049
318.18	96.98	1.460	0.136	0.000	0.000	1.78	0.050
318.21	96.99	1.496	0.139	0.000	0.000	1.83	0.052
318.24	97	1.534	0.143	0.000	0.000	1.88	0.053
318.27	97.01	1.572	0.146	0.000	0.000	1.93	0.055
318.31	97.02	1.610	0.150	0.000	0.000	1.98	0.056
318.34	97.03	1.649	0.153	0.000	0.000	2.03	0.058
318.37	97.04	1.689	0.157	0.000	0.000	2.09	0.059
318.41	97.05	1.733	0.161	0.000	0.000	2.14	0.061
318.44	97.06	1.780	0.165	0.000	0.000	2.20	0.062
318.47	97.07	1.828	0.170	0.000	0.000	2.26	0.064
318.50	97.08	1.879	0.175	0.000	0.000	2.32	0.066
318.54	97.09	1.931	0.179	0.000	0.000	2.38	0.068
318.57	97.1	1.985	0.184	0.000	0.000	2.45	0.069

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
318.60	97.11	2.042	0.190	0.000	0.000	2.51	0.071
318.64	97.12	2.101	0.195	0.000	0.000	2.58	0.073
318.67	97.13	2.162	0.201	0.000	0.000	2.65	0.075
318.70	97.14	2.223	0.207	0.000	0.000	2.72	0.077
318.73	97.15	2.286	0.212	0.000	0.000	2.80	0.079
318.77	97.16	2.349	0.218	0.000	0.000	2.87	0.081
318.80	97.17	2.412	0.224	0.000	0.000	2.95	0.084
318.83	97.18	2.478	0.230	0.000	0.000	3.03	0.086
318.86	97.19	2.544	0.236	0.000	0.000	3.12	0.088
318.90	97.2	2.611	0.243	0.000	0.000	3.20	0.091
318.93	97.21	2.681	0.249	0.000	0.000	3.29	0.093
318.96	97.22	2.754	0.256	0.000	0.000	3.38	0.096
319.00	97.23	2.831	0.263	0.000	0.000	3.47	0.098
319.03	97.24	2.914	0.271	0.000	0.000	3.56	0.101
319.06	97.25	3.002	0.279	0.000	0.000	3.66	0.104
319.09	97.26	3.097	0.288	0.000	0.000	3.76	0.106
319.13	97.27	3.196	0.297	0.000	0.000	3.86	0.109
319.16	97.28	3.295	0.306	0.000	0.000	3.97	0.112
319.19	97.29	3.396	0.315	0.000	0.000	4.08	0.115
319.23	97.3	3.498	0.325	0.000	0.000	4.19	0.119
319.26	97.31	3.601	0.335	0.000	0.000	4.31	0.122
319.29	97.32	3.710	0.345	0.000	0.000	4.43	0.125
319.32	97.33	3.826	0.355	0.000	0.000	4.55	0.129
319.36	97.34	3.945	0.367	0.000	0.000	4.68	0.132
319.39	97.35	4.074	0.378	0.000	0.000	4.81	0.136
319.42	97.36	4.215	0.392	0.000	0.000	4.95	0.140
319.46	97.37	4.362	0.405	0.000	0.000	5.09	0.144
319.49	97.38	4.516	0.420	0.000	0.000	5.23	0.148
319.52	97.39	4.677	0.435	0.000	0.000	5.38	0.152
319.55	97.4	4.846	0.450	0.000	0.000	5.54	0.157
319.59	97.41	5.018	0.466	0.000	0.000	5.70	0.161
319.62	97.42	5.194	0.483	0.000	0.000	5.87	0.166
319.65	97.43	5.376	0.499	0.000	0.000	6.04	0.171
319.69	97.44	5.561	0.517	0.000	0.000	6.22	0.176
319.72	97.45	5.745	0.534	0.000	0.000	6.41	0.181
319.75	97.46	5.933	0.551	0.000	0.000	6.60	0.187
319.78	97.47	6.124	0.569	0.000	0.000	6.80	0.192
319.82	97.48	6.318	0.587	0.000	0.000	7.00	0.198
319.85	97.49	6.527	0.606	0.000	0.000	7.21	0.204
319.88	97.5	6.732	0.625	0.000	0.000	7.43	0.210
319.91	97.51	6.941	0.645	0.000	0.000	7.65	0.217
319.95	97.52	7.154	0.665	0.000	0.000	7.88	0.223
319.98	97.53	7.368	0.685	0.000	0.000	8.12	0.230



Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)		DSL
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)	
320.01	97.54	7.587	0.705	0.000	0.000	8.37	0.237	
320.05	97.55	7.809	0.725	0.253	0.007	8.62	0.244	
320.08	97.56	8.025	0.746	0.512	0.015	8.88	0.251	
320.11	97.57	8.241	0.766	0.779	0.022	9.15	0.259	
320.14	97.58	8.469	0.787	1.053	0.030	9.42	0.267	
320.18	97.59	8.697	0.808	1.335	0.038	9.70	0.275	
320.21	97.6	8.937	0.830	1.624	0.046	9.99	0.283	
320.24	97.61	9.194	0.854	1.921	0.054	10.29	0.291	
320.28	97.62	9.443	0.877	2.227	0.063	10.59	0.300	
320.31	97.63	9.701	0.901	2.541	0.072	10.91	0.309	
320.34	97.64	9.959	0.925	2.864	0.081	11.23	0.318	
320.37	97.65	10.213	0.949	3.195	0.090	11.56	0.327	
320.41	97.66	10.453	0.971	3.534	0.100	11.90	0.337	
320.44	97.67	10.698	0.994	3.881	0.110	12.25	0.347	
320.47	97.68	10.945	1.017	4.236	0.120	12.60	0.357	
320.51	97.69	11.191	1.040	4.599	0.130	12.97	0.367	
320.54	97.7	11.436	1.062	4.970	0.141	13.34	0.378	
320.57	97.71	11.693	1.086	5.349	0.151	13.72	0.388	
320.60	97.72	11.953	1.110	5.737	0.162	14.10	0.399	
320.64	97.73	12.221	1.135	6.134	0.174	14.50	0.411	
320.67	97.74	12.484	1.160	6.539	0.185	14.91	0.422	
320.70	97.75	12.751	1.185	6.953	0.197	15.32	0.434	
320.73	97.76	13.028	1.210	7.376	0.209	15.74	0.446	
320.77	97.77	13.301	1.236	7.808	0.221	16.18	0.458	
320.80	97.78	13.596	1.263	8.249	0.234	16.62	0.471	
320.83	97.79	13.908	1.292	8.700	0.246	17.07	0.483	
320.87	97.8	14.253	1.324	9.162	0.259	17.53	0.496	
320.90	97.81	14.617	1.358	9.635	0.273	18.00	0.510	
320.93	97.82	14.975	1.391	10.121	0.287	18.49	0.524	
320.96	97.83	15.320	1.423	10.618	0.301	18.99	0.538	
321.00	97.84	15.654	1.454	11.126	0.315	19.49	0.552	
321.03	97.85	15.983	1.485	11.645	0.330	20.01	0.567	
321.06	97.86	16.306	1.515	12.174	0.345	20.54	0.582	
321.10	97.87	16.642	1.546	12.715	0.360	21.08	0.597	
321.13	97.88	16.992	1.579	13.266	0.376	21.63	0.613	
321.16	97.89	17.358	1.613	13.830	0.392	22.20	0.629	
321.19	97.9	17.720	1.646	14.405	0.408	22.77	0.645	
321.23	97.91	18.107	1.682	14.993	0.425	23.36	0.661	
321.26	97.92	18.539	1.722	15.594	0.442	23.96	0.679	
321.29	97.93	18.986	1.764	16.209	0.459	24.58	0.696	
321.33	97.94	19.444	1.806	16.839	0.477	25.21	0.714	
321.36	97.95	19.900	1.849	17.485	0.495	25.85	0.732	
321.39	97.96	20.366	1.892	18.145	0.514	26.51	0.751	

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
321.42	97.97	20.833	1.935	18.821	0.533	27.19	0.770
321.46	97.98	21.372	1.986	19.513	0.553	27.88	0.789
321.49	97.99	21.943	2.039	20.223	0.573	28.59	0.810
321.52	98	22.460	2.087	20.952	0.593	29.32	0.830
321.56	98.01	22.943	2.131	21.697	0.614	30.06	0.851
321.59	98.02	23.438	2.177	22.457	0.636	30.83	0.873
321.62	98.03	23.956	2.226	23.235	0.658	31.60	0.895
321.65	98.04	24.492	2.275	24.029	0.680	32.40	0.917
321.69	98.05	25.010	2.323	24.841	0.703	33.21	0.940
321.72	98.06	25.542	2.373	25.671	0.727	34.04	0.964
321.75	98.07	26.058	2.421	26.517	0.751	34.88	0.988
321.78	98.08	26.560	2.468	27.380	0.775	35.75	1.012
321.82	98.09	27.050	2.513	28.260	0.800	36.63	1.037
321.85	98.1	27.529	2.558	29.155	0.826	37.52	1.063
321.88	98.11	27.985	2.600	30.066	0.851	38.43	1.088
321.92	98.12	28.435	2.642	30.991	0.878	39.36	1.115
321.95	98.13	28.884	2.683	31.931	0.904	40.30	1.141
321.98	98.14	29.319	2.724	32.886	0.931	41.25	1.168
322.01	98.15	29.723	2.761	33.855	0.959	42.22	1.196
322.05	98.16	30.119	2.798	34.836	0.986	43.20	1.223
322.08	98.17	30.527	2.836	35.831	1.015	44.20	1.252
322.11	98.18	30.909	2.872	36.839	1.043	45.21	1.280
322.15	98.19	31.273	2.905	37.859	1.072	46.23	1.309
322.18	98.2	31.637	2.939	38.891	1.101	47.26	1.338
322.21	98.21	32.010	2.974	39.935	1.131	48.30	1.368
322.24	98.22	32.373	3.008	40.991	1.161	49.36	1.398
322.28	98.23	32.726	3.040	42.059	1.191	50.43	1.428
322.31	98.24	33.067	3.072	43.138	1.222	51.51	1.458
322.34	98.25	33.407	3.104	44.229	1.252	52.60	1.489
322.38	98.26	33.735	3.134	45.330	1.284	53.70	1.521
322.41	98.27	34.067	3.165	46.442	1.315	54.81	1.552
322.44	98.28	34.413	3.197	47.565	1.347	55.93	1.584
322.47	98.29	34.763	3.230	48.700	1.379	57.07	1.616
322.51	98.3	35.113	3.262	49.846	1.411	58.21	1.648
322.54	98.31	35.449	3.293	51.004	1.444	59.37	1.681
322.57	98.32	35.787	3.325	52.172	1.477	60.54	1.714
322.60	98.33	36.136	3.357	53.352	1.511	61.72	1.748
322.64	98.34	36.488	3.390	54.543	1.544	62.91	1.781
322.67	98.35	36.830	3.422	55.746	1.579	64.11	1.815
322.70	98.36	37.168	3.453	56.960	1.613	65.33	1.850
322.74	98.37	37.520	3.486	58.185	1.648	66.55	1.885
322.77	98.38	37.881	3.519	59.422	1.683	67.79	1.920
322.80	98.39	38.233	3.552	60.671	1.718	69.04	1.955

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
322.83	98.4	38.591	3.585	61.931	1.754	70.30	1.991
322.87	98.41	38.937	3.617	63.203	1.790	71.57	2.027
322.90	98.42	39.265	3.648	64.485	1.826	72.85	2.063
322.93	98.43	39.593	3.678	65.779	1.863	74.15	2.100
322.97	98.44	39.920	3.709	67.083	1.900	75.45	2.137
323.00	98.45	40.257	3.740	68.399	1.937	76.77	2.174
323.03	98.46	40.603	3.772	69.725	1.974	78.09	2.211
323.06	98.47	40.945	3.804	71.063	2.012	79.43	2.249
323.10	98.48	41.293	3.836	72.412	2.050	80.78	2.287
323.13	98.49	41.641	3.869	73.772	2.089	82.14	2.326
323.16	98.5	41.985	3.901	75.144	2.128	83.51	2.365
323.20	98.51	42.328	3.932	76.527	2.167	84.89	2.404
323.23	98.52	42.659	3.963	77.921	2.206	86.29	2.443
323.26	98.53	42.983	3.993	79.326	2.246	87.69	2.483
323.29	98.54	43.290	4.022	80.741	2.286	89.11	2.523
323.33	98.55	43.592	4.050	82.166	2.327	90.53	2.564
323.36	98.56	43.895	4.078	83.602	2.367	91.97	2.604
323.39	98.57	44.200	4.106	85.047	2.408	93.41	2.645
323.43	98.58	44.500	4.134	86.502	2.449	94.87	2.686
323.46	98.59	44.796	4.162	87.967	2.491	96.33	2.728
323.49	98.6	45.074	4.188	89.441	2.533	97.81	2.770
323.52	98.61	45.356	4.214	90.924	2.575	99.29	2.812
323.56	98.62	45.634	4.240	92.417	2.617	100.78	2.854
323.59	98.63	45.921	4.266	93.919	2.659	102.29	2.896
323.62	98.64	46.208	4.293	95.430	2.702	103.80	2.939
323.65	98.65	46.511	4.321	96.951	2.745	105.32	2.982
323.69	98.66	46.818	4.350	98.482	2.789	106.85	3.026
323.72	98.67	47.118	4.377	100.023	2.832	108.39	3.069
323.75	98.68	47.419	4.405	101.574	2.876	109.94	3.113
323.79	98.69	47.707	4.432	103.134	2.920	111.50	3.157
323.82	98.7	47.993	4.459	104.704	2.965	113.07	3.202
323.85	98.71	48.274	4.485	106.283	3.010	114.65	3.247
323.88	98.72	48.550	4.510	107.871	3.055	116.24	3.292
323.92	98.73	48.829	4.536	109.469	3.100	117.84	3.337
323.95	98.74	49.108	4.562	111.075	3.145	119.44	3.382
323.98	98.75	49.388	4.588	112.691	3.191	121.06	3.428
324.02	98.76	49.675	4.615	114.316	3.237	122.68	3.474
324.05	98.77	49.968	4.642	115.951	3.283	124.32	3.520
324.08	98.78	50.278	4.671	117.595	3.330	125.96	3.567
324.11	98.79	50.599	4.701	119.250	3.377	127.62	3.614
324.15	98.8	50.907	4.729	120.915	3.424	129.28	3.661
324.18	98.81	51.208	4.757	122.590	3.471	130.96	3.708
324.21	98.82	51.514	4.786	124.275	3.519	132.64	3.756

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
324.25	98.83	51.806	4.813	125.970	3.567	134.34	3.804
324.28	98.84	52.100	4.840	127.675	3.615	136.04	3.852
324.31	98.85	52.390	4.867	129.389	3.664	137.76	3.901
324.34	98.86	52.686	4.895	131.112	3.713	139.48	3.950
324.38	98.87	52.976	4.922	132.846	3.762	141.21	3.999
324.41	98.88	53.252	4.947	134.588	3.811	142.96	4.048
324.44	98.89	53.525	4.973	136.340	3.861	144.71	4.098
324.48	98.9	53.810	4.999	138.101	3.911	146.47	4.148
324.51	98.91	54.122	5.028	139.871	3.961	148.24	4.198
324.54	98.92	54.445	5.058	141.652	4.011	150.02	4.248
324.57	98.93	54.745	5.086	143.443	4.062	151.81	4.299
324.61	98.94	55.040	5.113	145.244	4.113	153.61	4.350
324.64	98.95	55.338	5.141	147.055	4.164	155.42	4.401
324.67	98.96	55.637	5.169	148.875	4.216	157.24	4.453
324.70	98.97	55.934	5.196	150.705	4.267	159.07	4.504
324.74	98.98	56.240	5.225	152.545	4.320	160.91	4.557
324.77	98.99	56.521	5.251	154.395	4.372	162.76	4.609
324.80	99	56.789	5.276	156.254	4.425	164.62	4.662
324.84	99.01	57.053	5.300	158.121	4.477	166.49	4.714
324.87	99.02	57.305	5.324	159.997	4.531	168.37	4.768
324.90	99.03	57.563	5.348	161.882	4.584	170.25	4.821
324.93	99.04	57.839	5.373	163.775	4.638	172.14	4.875
324.97	99.05	58.102	5.398	165.677	4.691	174.04	4.928
325.00	99.06	58.347	5.421	167.587	4.746	175.95	4.982
325.03	99.07	58.586	5.443	169.505	4.800	177.87	5.037
325.07	99.08	58.820	5.465	171.431	4.854	179.80	5.091
325.10	99.09	59.061	5.487	173.365	4.909	181.73	5.146
325.13	99.1	59.307	5.510	175.306	4.964	183.67	5.201
325.16	99.11	59.567	5.534	177.256	5.019	185.62	5.256
325.20	99.12	59.809	5.556	179.215	5.075	187.58	5.312
325.23	99.13	60.040	5.578	181.181	5.130	189.55	5.367
325.26	99.14	60.271	5.599	183.154	5.186	191.52	5.423
325.30	99.15	60.510	5.622	185.136	5.242	193.50	5.479
325.33	99.16	60.755	5.644	187.125	5.299	195.49	5.536
325.36	99.17	60.999	5.667	189.122	5.355	197.49	5.592
325.39	99.18	61.234	5.689	191.127	5.412	199.49	5.649
325.43	99.19	61.463	5.710	193.140	5.469	201.51	5.706
325.46	99.2	61.695	5.732	195.160	5.526	203.53	5.763
325.49	99.21	61.929	5.753	197.188	5.584	205.56	5.821
325.52	99.22	62.166	5.775	199.224	5.641	207.59	5.878
325.56	99.23	62.404	5.798	201.267	5.699	209.64	5.936
325.59	99.24	62.638	5.819	203.319	5.757	211.69	5.994
325.62	99.25	62.875	5.841	205.378	5.816	213.75	6.053

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
325.66	99.26	63.120	5.864	207.444	5.874	215.81	6.111
325.69	99.27	63.364	5.887	209.519	5.933	217.89	6.170
325.72	99.28	63.605	5.909	211.602	5.992	219.97	6.229
325.75	99.29	63.855	5.932	213.693	6.051	222.06	6.288
325.79	99.3	64.109	5.956	215.792	6.111	224.16	6.347
325.82	99.31	64.379	5.981	217.900	6.170	226.27	6.407
325.85	99.32	64.659	6.007	220.017	6.230	228.38	6.467
325.89	99.33	64.931	6.032	222.142	6.290	230.51	6.527
325.92	99.34	65.208	6.058	224.277	6.351	232.64	6.588
325.95	99.35	65.491	6.084	226.421	6.412	234.79	6.648
325.98	99.36	65.769	6.110	228.574	6.472	236.94	6.709
326.02	99.37	66.046	6.136	230.737	6.534	239.10	6.771
326.05	99.38	66.325	6.162	232.908	6.595	241.28	6.832
326.08	99.39	66.604	6.188	235.089	6.657	243.46	6.894
326.12	99.4	66.875	6.213	237.278	6.719	245.65	6.956
326.15	99.41	67.155	6.239	239.477	6.781	247.84	7.018
326.18	99.42	67.434	6.265	241.685	6.844	250.05	7.081
326.21	99.43	67.715	6.291	243.902	6.907	252.27	7.143
326.25	99.44	67.983	6.316	246.128	6.970	254.50	7.206
326.28	99.45	68.257	6.341	248.363	7.033	256.73	7.270
326.31	99.46	68.529	6.367	250.606	7.096	258.97	7.333
326.35	99.47	68.811	6.393	252.859	7.160	261.23	7.397
326.38	99.48	69.078	6.418	255.121	7.224	263.49	7.461
326.41	99.49	69.352	6.443	257.392	7.289	265.76	7.525
326.44	99.5	69.619	6.468	259.672	7.353	268.04	7.590
326.48	99.51	69.892	6.493	261.960	7.418	270.33	7.655
326.51	99.52	70.174	6.519	264.258	7.483	272.63	7.720
326.54	99.53	70.454	6.545	266.565	7.548	274.93	7.785
326.57	99.54	70.732	6.571	268.881	7.614	277.25	7.851
326.61	99.55	71.021	6.598	271.206	7.680	279.57	7.917
326.64	99.56	71.328	6.627	273.541	7.746	281.91	7.983
326.67	99.57	71.643	6.656	275.887	7.812	284.25	8.049
326.71	99.58	71.963	6.686	278.242	7.879	286.61	8.116
326.74	99.59	72.276	6.715	280.608	7.946	288.98	8.183
326.77	99.6	72.575	6.742	282.984	8.013	291.35	8.250
326.80	99.61	72.871	6.770	285.370	8.081	293.74	8.318
326.84	99.62	73.161	6.797	287.766	8.149	296.13	8.386
326.87	99.63	73.453	6.824	290.171	8.217	298.54	8.454
326.90	99.64	73.746	6.851	292.586	8.285	300.95	8.522
326.94	99.65	74.051	6.880	295.010	8.354	303.38	8.591
326.97	99.66	74.354	6.908	297.445	8.423	305.81	8.660
327.00	99.67	74.658	6.936	299.889	8.492	308.26	8.729
327.03	99.68	74.973	6.965	302.344	8.561	310.71	8.798

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
327.07	99.69	75.289	6.995	304.808	8.631	313.18	8.868
327.10	99.7	75.608	7.024	307.284	8.701	315.65	8.938
327.13	99.71	75.927	7.054	309.769	8.772	318.14	9.009
327.17	99.72	76.246	7.084	312.266	8.842	320.63	9.079
327.20	99.73	76.564	7.113	314.772	8.913	323.14	9.150
327.23	99.74	76.870	7.141	317.289	8.985	325.66	9.222
327.26	99.75	77.165	7.169	319.816	9.056	328.18	9.293
327.30	99.76	77.460	7.196	322.353	9.128	330.72	9.365
327.33	99.77	77.748	7.223	324.899	9.200	333.27	9.437
327.36	99.78	78.047	7.251	327.454	9.272	335.82	9.509
327.40	99.79	78.345	7.278	330.020	9.345	338.39	9.582
327.43	99.8	78.645	7.306	332.595	9.418	340.96	9.655
327.46	99.81	78.941	7.334	335.180	9.491	343.55	9.728
327.49	99.82	79.245	7.362	337.775	9.565	346.14	9.802
327.53	99.83	79.556	7.391	340.380	9.638	348.75	9.875
327.56	99.84	79.880	7.421	342.995	9.713	351.36	9.949
327.59	99.85	80.211	7.452	345.622	9.787	353.99	10.024
327.62	99.86	80.559	7.484	348.259	9.862	356.63	10.099
327.66	99.87	80.919	7.518	350.908	9.937	359.28	10.174
327.69	99.88	81.276	7.551	353.568	10.012	361.94	10.249
327.72	99.89	81.636	7.584	356.241	10.088	364.61	10.325
327.76	99.9	81.999	7.618	358.925	10.164	367.29	10.401
327.79	99.91	82.355	7.651	361.621	10.240	369.99	10.477
327.82	99.92	82.716	7.685	364.329	10.317	372.70	10.554
327.85	99.93	83.070	7.717	367.049	10.394	375.42	10.631
327.89	99.94	83.420	7.750	369.780	10.471	378.15	10.708
327.92	99.95	83.769	7.782	372.522	10.549	380.89	10.786
327.95	99.96	84.111	7.814	375.276	10.627	383.64	10.864
327.99	99.97	84.460	7.847	378.042	10.705	386.41	10.942
328.02	99.98	84.795	7.878	380.818	10.784	389.19	11.020
328.05	99.99	85.129	7.909	383.605	10.862	391.97	11.099
328.08	100	85.466	7.940	386.404	10.942	394.77	11.179
328.12	100.01	85.800	7.971	389.213	11.021	397.58	11.258
328.15	100.02	86.149	8.004	392.034	11.101	400.40	11.338
328.18	100.03	86.491	8.035	394.866	11.181	403.23	11.418
328.22	100.04	86.826	8.066	397.709	11.262	406.08	11.499
328.25	100.05	87.163	8.098	400.563	11.343	408.93	11.580
328.28	100.06	87.500	8.129	403.429	11.424	411.80	11.661
328.31	100.07	87.829	8.160	406.305	11.505	414.67	11.742
328.35	100.08	88.157	8.190	409.192	11.587	417.56	11.824
328.38	100.09	88.487	8.221	412.089	11.669	420.46	11.906
328.41	100.1	88.818	8.251	414.998	11.751	423.37	11.988
328.44	100.11	89.151	8.282	417.917	11.834	426.28	12.071

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
328.48	100.12	89.489	8.314	420.848	11.917	429.22	12.154
328.51	100.13	89.824	8.345	423.789	12.000	432.16	12.237
328.54	100.14	90.153	8.376	426.741	12.084	435.11	12.321
328.58	100.15	90.484	8.406	429.705	12.168	438.07	12.405
328.61	100.16	90.807	8.436	432.678	12.252	441.05	12.489
328.64	100.17	91.126	8.466	435.663	12.337	444.03	12.574
328.67	100.18	91.442	8.495	438.658	12.421	447.03	12.658
328.71	100.19	91.755	8.524	441.663	12.506	450.03	12.743
328.74	100.2	92.070	8.554	444.678	12.592	453.05	12.829
328.77	100.21	92.391	8.583	447.704	12.678	456.07	12.915
328.81	100.22	92.715	8.613	450.741	12.764	459.11	13.000
328.84	100.23	93.049	8.645	453.788	12.850	462.16	13.087
328.87	100.24	93.387	8.676	456.846	12.936	465.21	13.173
328.90	100.25	93.728	8.708	459.916	13.023	468.28	13.260
328.94	100.26	94.060	8.738	462.996	13.111	471.36	13.348
328.97	100.27	94.382	8.768	466.088	13.198	474.46	13.435
329.00	100.28	94.707	8.799	469.189	13.286	477.56	13.523
329.04	100.29	95.031	8.829	472.302	13.374	480.67	13.611
329.07	100.3	95.362	8.859	475.425	13.463	483.79	13.699
329.10	100.31	95.686	8.890	478.559	13.551	486.93	13.788
329.13	100.32	96.013	8.920	481.704	13.640	490.07	13.877
329.17	100.33	96.336	8.950	484.859	13.730	493.23	13.967
329.20	100.34	96.654	8.979	488.025	13.819	496.39	14.056
329.23	100.35	96.970	9.009	491.201	13.909	499.57	14.146
329.27	100.36	97.279	9.038	494.388	13.999	502.76	14.236
329.30	100.37	97.591	9.067	497.584	14.090	505.95	14.327
329.33	100.38	97.896	9.095	500.791	14.181	509.16	14.418
329.36	100.39	98.190	9.122	504.008	14.272	512.38	14.509
329.40	100.4	98.484	9.149	507.234	14.363	515.60	14.600
329.43	100.41	98.784	9.177	510.470	14.455	518.84	14.692
329.46	100.42	99.090	9.206	513.716	14.547	522.08	14.784
329.49	100.43	99.395	9.234	516.972	14.639	525.34	14.876
329.53	100.44	99.707	9.263	520.238	14.731	528.61	14.968
329.56	100.45	100.029	9.293	523.515	14.824	531.88	15.061
329.59	100.46	100.358	9.324	526.802	14.917	535.17	15.154
329.63	100.47	100.696	9.355	530.100	15.011	538.47	15.248
329.66	100.48	101.044	9.387	533.409	15.104	541.78	15.341
329.69	100.49	101.388	9.419	536.730	15.198	545.10	15.435
329.72	100.5	101.743	9.452	540.062	15.293	548.43	15.530
329.76	100.51	102.093	9.485	543.406	15.388	551.77	15.624
329.79	100.52	102.428	9.516	546.761	15.483	555.13	15.719
329.82	100.53	102.769	9.548	550.127	15.578	558.49	15.815
329.86	100.54	103.104	9.579	553.504	15.673	561.87	15.910

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
329.89	100.55	103.437	9.610	556.892	15.769	565.26	16.006
329.92	100.56	103.783	9.642	560.291	15.866	568.66	16.103
329.95	100.57	104.135	9.674	563.702	15.962	572.07	16.199
329.99	100.58	104.477	9.706	567.124	16.059	575.49	16.296
330.02	100.59	104.836	9.740	570.558	16.156	578.93	16.393
330.05	100.6	105.195	9.773	574.003	16.254	582.37	16.491
330.09	100.61	105.567	9.807	577.460	16.352	585.83	16.589
330.12	100.62	105.926	9.841	580.930	16.450	589.30	16.687
330.15	100.63	106.282	9.874	584.411	16.549	592.78	16.786
330.18	100.64	106.635	9.907	587.904	16.648	596.27	16.885
330.22	100.65	106.987	9.939	591.408	16.747	599.78	16.984
330.25	100.66	107.335	9.972	594.924	16.846	603.29	17.083
330.28	100.67	107.675	10.003	598.451	16.946	606.82	17.183
330.31	100.68	108.016	10.035	601.989	17.046	610.36	17.283
330.35	100.69	108.378	10.069	605.539	17.147	613.91	17.384
330.38	100.7	108.748	10.103	609.100	17.248	617.47	17.485
330.41	100.71	109.120	10.138	612.674	17.349	621.04	17.586
330.45	100.72	109.476	10.171	616.260	17.451	624.63	17.687
330.48	100.73	109.838	10.204	619.858	17.552	628.23	17.789
330.51	100.74	110.210	10.239	623.468	17.655	631.84	17.892
330.54	100.75	110.574	10.273	627.089	17.757	635.46	17.994
330.58	100.76	110.955	10.308	630.723	17.860	639.09	18.097
330.61	100.77	111.341	10.344	634.370	17.963	642.74	18.200
330.64	100.78	111.714	10.379	638.029	18.067	646.40	18.304
330.68	100.79	112.083	10.413	641.700	18.171	650.07	18.408
330.71	100.8	112.448	10.447	645.383	18.275	653.75	18.512
330.74	100.81	112.816	10.481	649.079	18.380	657.45	18.617
330.77	100.82	113.179	10.515	652.786	18.485	661.15	18.722
330.81	100.83	113.545	10.549	656.505	18.590	664.87	18.827
330.84	100.84	113.911	10.583	660.236	18.696	668.60	18.933
330.87	100.85	114.271	10.616	663.980	18.802	672.35	19.039
330.91	100.86	114.618	10.648	667.734	18.908	676.10	19.145
330.94	100.87	114.966	10.681	671.500	19.015	679.87	19.252
330.97	100.88	115.309	10.713	675.278	19.122	683.65	19.359
331.00	100.89	115.654	10.745	679.067	19.229	687.43	19.466
331.04	100.9	115.999	10.777	682.867	19.337	691.23	19.574
331.07	100.91	116.349	10.809	686.678	19.445	695.05	19.681
331.10	100.92	116.706	10.842	690.501	19.553	698.87	19.790
331.14	100.93	117.064	10.876	694.336	19.661	702.70	19.898
331.17	100.94	117.430	10.910	698.183	19.770	706.55	20.007
331.20	100.95	117.810	10.945	702.041	19.880	710.41	20.117
331.23	100.96	118.178	10.979	705.913	19.989	714.28	20.226
331.27	100.97	118.537	11.012	709.796	20.099	718.16	20.336



Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
331.30	100.98	118.901	11.046	713.691	20.209	722.06	20.446
331.33	100.99	119.270	11.081	717.598	20.320	725.97	20.557
331.36	101	119.637	11.115	721.517	20.431	729.88	20.668
331.40	101.01	120.007	11.149	725.448	20.542	733.82	20.779
331.43	101.02	120.365	11.182	729.391	20.654	737.76	20.891
331.46	101.03	120.736	11.217	733.346	20.766	741.71	21.003
331.50	101.04	121.112	11.252	737.313	20.878	745.68	21.115
331.53	101.05	121.479	11.286	741.293	20.991	749.66	21.228
331.56	101.06	121.846	11.320	745.284	21.104	753.65	21.341
331.59	101.07	122.226	11.355	749.288	21.217	757.66	21.454
331.63	101.08	122.599	11.390	753.304	21.331	761.67	21.568
331.66	101.09	122.982	11.425	757.333	21.445	765.70	21.682
331.69	101.1	123.357	11.460	761.374	21.560	769.74	21.797
331.73	101.11	123.733	11.495	765.427	21.674	773.79	21.911
331.76	101.12	124.091	11.528	769.492	21.790	777.86	22.027
331.79	101.13	124.422	11.559	773.569	21.905	781.94	22.142
331.82	101.14	124.750	11.590	777.657	22.021	786.02	22.258
331.86	101.15	125.078	11.620	781.755	22.137	790.12	22.374
331.89	101.16	125.412	11.651	785.864	22.253	794.23	22.490
331.92	101.17	125.739	11.682	789.984	22.370	798.35	22.607
331.96	101.18	126.069	11.712	794.115	22.487	802.48	22.724
331.99	101.19	126.412	11.744	798.256	22.604	806.62	22.841
332.02	101.2	126.745	11.775	802.409	22.722	810.78	22.959
332.05	101.21	127.072	11.805	806.573	22.840	814.94	23.077
332.09	101.22	127.403	11.836	810.747	22.958	819.11	23.195
332.12	101.23	127.735	11.867	814.933	23.076	823.30	23.313
332.15	101.24	128.063	11.897	819.129	23.195	827.50	23.432
332.19	101.25	128.386	11.927	823.336	23.314	831.70	23.551
332.22	101.26	128.711	11.958	827.553	23.434	835.92	23.671
332.25	101.27	129.042	11.988	831.781	23.553	840.15	23.790
332.28	101.28	129.371	12.019	836.020	23.673	844.39	23.910
332.32	101.29	129.699	12.049	840.270	23.794	848.64	24.031
332.35	101.3	130.024	12.080	844.531	23.914	852.90	24.151
332.38	101.31	130.357	12.111	848.802	24.035	857.17	24.272
332.41	101.32	130.697	12.142	853.084	24.157	861.45	24.394
332.45	101.33	131.033	12.173	857.378	24.278	865.75	24.515
332.48	101.34	131.354	12.203	861.682	24.400	870.05	24.637
332.51	101.35	131.682	12.234	865.997	24.522	874.36	24.759
332.55	101.36	132.025	12.266	870.323	24.645	878.69	24.882
332.58	101.37	132.385	12.299	874.660	24.768	883.03	25.005
332.61	101.38	132.745	12.332	879.009	24.891	887.38	25.128
332.64	101.39	133.091	12.365	883.370	25.014	891.74	25.251
332.68	101.4	133.450	12.398	887.743	25.138	896.11	25.375

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
332.71	101.41	133.815	12.432	892.127	25.262	900.49	25.499
332.74	101.42	134.177	12.465	896.523	25.387	904.89	25.624
332.78	101.43	134.548	12.500	900.931	25.512	909.30	25.748
332.81	101.44	134.945	12.537	905.352	25.637	913.72	25.874
332.84	101.45	135.339	12.573	909.786	25.762	918.15	25.999
332.87	101.46	135.724	12.609	914.232	25.888	922.60	26.125
332.91	101.47	136.120	12.646	918.692	26.014	927.06	26.251
332.94	101.48	136.511	12.682	923.164	26.141	931.53	26.378
332.97	101.49	136.898	12.718	927.649	26.268	936.02	26.505
333.01	101.5	137.272	12.753	932.147	26.395	940.51	26.632
333.04	101.51	137.652	12.788	936.656	26.523	945.02	26.760
333.07	101.52	138.041	12.824	941.179	26.651	949.55	26.888
333.10	101.53	138.416	12.859	945.714	26.780	954.08	27.017
333.14	101.54	138.807	12.896	950.262	26.908	958.63	27.145
333.17	101.55	139.217	12.934	954.822	27.038	963.19	27.274
333.20	101.56	139.640	12.973	959.397	27.167	967.76	27.404
333.23	101.57	140.066	13.013	963.985	27.297	972.35	27.534
333.27	101.58	140.490	13.052	968.587	27.427	976.96	27.664
333.30	101.59	140.910	13.091	973.203	27.558	981.57	27.795
333.33	101.6	141.343	13.131	977.834	27.689	986.20	27.926
333.37	101.61	141.805	13.174	982.478	27.821	990.85	28.058
333.40	101.62	142.279	13.218	987.138	27.953	995.51	28.190
333.43	101.63	142.732	13.260	991.814	28.085	1000.18	28.322
333.46	101.64	143.185	13.302	996.504	28.218	1004.87	28.455
333.50	101.65	143.628	13.344	1001.209	28.351	1009.58	28.588
333.53	101.66	144.084	13.386	1005.929	28.485	1014.30	28.722
333.56	101.67	144.571	13.431	1010.664	28.619	1019.03	28.856
333.60	101.68	145.062	13.477	1015.415	28.753	1023.78	28.990
333.63	101.69	145.549	13.522	1020.182	28.888	1028.55	29.125
333.66	101.7	146.060	13.569	1024.965	29.024	1033.33	29.261
333.69	101.71	146.600	13.620	1029.766	29.160	1038.13	29.397
333.73	101.72	147.120	13.668	1034.584	29.296	1042.95	29.533
333.76	101.73	147.632	13.715	1039.420	29.433	1047.79	29.670
333.79	101.74	148.144	13.763	1044.272	29.570	1052.64	29.807
333.83	101.75	148.631	13.808	1049.140	29.708	1057.51	29.945
333.86	101.76	149.125	13.854	1054.024	29.847	1062.39	30.084
333.89	101.77	149.616	13.900	1058.925	29.985	1067.29	30.222
333.92	101.78	150.120	13.947	1063.842	30.125	1072.21	30.362
333.96	101.79	150.636	13.995	1068.775	30.264	1077.14	30.501
333.99	101.8	151.152	14.043	1073.726	30.404	1082.09	30.641
334.02	101.81	151.697	14.093	1078.694	30.545	1087.06	30.782
334.06	101.82	152.267	14.146	1083.680	30.686	1092.05	30.923
334.09	101.83	152.819	14.197	1088.684	30.828	1097.05	31.065

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
334.12	101.84	153.330	14.245	1093.707	30.970	1102.07	31.207
334.15	101.85	153.826	14.291	1098.745	31.113	1107.11	31.350
334.19	101.86	154.299	14.335	1103.800	31.256	1112.17	31.493
334.22	101.87	154.760	14.378	1108.870	31.400	1117.24	31.637
334.25	101.88	155.214	14.420	1113.955	31.544	1122.32	31.781
334.28	101.89	155.656	14.461	1119.054	31.688	1127.42	31.925
334.32	101.9	156.094	14.502	1124.168	31.833	1132.54	32.070
334.35	101.91	156.523	14.542	1129.296	31.978	1137.66	32.215
334.38	101.92	156.957	14.582	1134.439	32.124	1142.81	32.361
334.42	101.93	157.404	14.623	1139.596	32.270	1147.96	32.507
334.45	101.94	157.844	14.664	1144.767	32.416	1153.13	32.653
334.48	101.95	158.273	14.704	1149.953	32.563	1158.32	32.800
334.51	101.96	158.702	14.744	1155.152	32.710	1163.52	32.947
334.55	101.97	159.136	14.784	1160.366	32.858	1168.73	33.095
334.58	101.98	159.566	14.824	1165.594	33.006	1173.96	33.243
334.61	101.99	159.997	14.864	1170.836	33.154	1179.20	33.391
334.65	102	160.422	14.904	1176.093	33.303	1184.46	33.540
334.68	102.01	160.848	14.943	1181.363	33.452	1189.73	33.689
334.71	102.02	161.293	14.985	1186.647	33.602	1195.01	33.839
334.74	102.03	161.743	15.026	1191.946	33.752	1200.31	33.989
334.78	102.04	162.188	15.068	1197.260	33.903	1205.63	34.140
334.81	102.05	162.625	15.108	1202.589	34.053	1210.96	34.290
334.84	102.06	163.066	15.149	1207.931	34.205	1216.30	34.442
334.88	102.07	163.498	15.190	1213.288	34.356	1221.66	34.593
334.91	102.08	163.931	15.230	1218.660	34.509	1227.03	34.746
334.94	102.09	164.369	15.270	1224.045	34.661	1232.41	34.898
334.97	102.1	164.806	15.311	1229.445	34.814	1237.81	35.051
335.01	102.11	165.256	15.353	1234.859	34.967	1243.23	35.204
335.04	102.12	165.709	15.395	1240.288	35.121	1248.66	35.358
335.07	102.13	166.158	15.437	1245.733	35.275	1254.10	35.512
335.10	102.14	166.598	15.477	1251.191	35.430	1259.56	35.667
335.14	102.15	167.047	15.519	1256.664	35.585	1265.03	35.822
335.17	102.16	167.495	15.561	1262.152	35.740	1270.52	35.977
335.20	102.17	167.942	15.602	1267.655	35.896	1276.02	36.133
335.24	102.18	168.388	15.644	1273.172	36.052	1281.54	36.289
335.27	102.19	168.840	15.686	1278.704	36.209	1287.07	36.446
335.30	102.2	169.299	15.728	1284.251	36.366	1292.62	36.603
335.33	102.21	169.765	15.772	1289.813	36.523	1298.18	36.760
335.37	102.22	170.221	15.814	1295.390	36.681	1303.76	36.918
335.40	102.23	170.679	15.857	1300.982	36.840	1309.35	37.077
335.43	102.24	171.131	15.899	1306.589	36.998	1314.96	37.235
335.47	102.25	171.563	15.939	1312.211	37.158	1320.58	37.395
335.50	102.26	171.987	15.978	1317.847	37.317	1326.21	37.554

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
335.53	102.27	172.418	16.018	1323.496	37.477	1331.86	37.714
335.56	102.28	172.857	16.059	1329.160	37.638	1337.53	37.875
335.60	102.29	173.312	16.101	1334.839	37.798	1343.21	38.035
335.63	102.3	173.779	16.145	1340.532	37.960	1348.90	38.197
335.66	102.31	174.233	16.187	1346.241	38.121	1354.61	38.358
335.70	102.32	174.703	16.230	1351.965	38.283	1360.33	38.520
335.73	102.33	175.202	16.277	1357.705	38.446	1366.07	38.683
335.76	102.34	175.685	16.322	1363.461	38.609	1371.83	38.846
335.79	102.35	176.163	16.366	1369.233	38.772	1377.60	39.009
335.83	102.36	176.646	16.411	1375.020	38.936	1383.39	39.173
335.86	102.37	177.120	16.455	1380.824	39.101	1389.19	39.337
335.89	102.38	177.608	16.500	1386.643	39.265	1395.01	39.502
335.93	102.39	178.110	16.547	1392.478	39.431	1400.85	39.667
335.96	102.4	178.637	16.596	1398.330	39.596	1406.70	39.833
335.99	102.41	179.186	16.647	1404.200	39.762	1412.57	39.999
336.02	102.42	179.754	16.700	1410.088	39.929	1418.46	40.166
336.06	102.43	180.318	16.752	1415.994	40.096	1424.36	40.333
336.09	102.44	180.858	16.802	1421.919	40.264	1430.29	40.501
336.12	102.45	181.392	16.852	1427.861	40.432	1436.23	40.669
336.15	102.46	181.923	16.901	1433.821	40.601	1442.19	40.838
336.19	102.47	182.442	16.949	1439.798	40.771	1448.17	41.007
336.22	102.48	182.950	16.997	1445.792	40.940	1454.16	41.177
336.25	102.49	183.449	17.043	1451.803	41.110	1460.17	41.347
336.29	102.5	183.963	17.091	1457.830	41.281	1466.20	41.518
336.32	102.51	184.485	17.139	1463.874	41.452	1472.24	41.689
336.35	102.52	185.003	17.187	1469.935	41.624	1478.30	41.861
336.38	102.53	185.524	17.236	1476.013	41.796	1484.38	42.033
336.42	102.54	186.060	17.286	1482.109	41.969	1490.48	42.206
336.45	102.55	186.604	17.336	1488.222	42.142	1496.59	42.379
336.48	102.56	187.137	17.386	1494.353	42.315	1502.72	42.552
336.52	102.57	187.646	17.433	1500.501	42.489	1508.87	42.726
336.55	102.58	188.146	17.479	1506.665	42.664	1515.03	42.901
336.58	102.59	188.638	17.525	1512.846	42.839	1521.21	43.076
336.61	102.6	189.133	17.571	1519.043	43.014	1527.41	43.251
336.65	102.61	189.653	17.619	1525.257	43.190	1533.62	43.427
336.68	102.62	190.188	17.669	1531.487	43.367	1539.86	43.604
336.71	102.63	190.727	17.719	1537.736	43.544	1546.10	43.781
336.75	102.64	191.254	17.768	1544.002	43.721	1552.37	43.958
336.78	102.65	191.806	17.819	1550.286	43.899	1558.65	44.136
336.81	102.66	192.371	17.872	1556.588	44.078	1564.96	44.315
336.84	102.67	192.938	17.925	1562.908	44.257	1571.28	44.494
336.88	102.68	193.538	17.980	1569.248	44.436	1577.62	44.673
336.91	102.69	194.198	18.042	1575.608	44.616	1583.98	44.853

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
336.94	102.7	194.827	18.100	1581.990	44.797	1590.36	45.034
336.98	102.71	195.441	18.157	1588.392	44.978	1596.76	45.215
337.01	102.72	196.024	18.211	1594.814	45.160	1603.18	45.397
337.04	102.73	196.585	18.263	1601.254	45.342	1609.62	45.579
337.07	102.74	197.130	18.314	1607.713	45.525	1616.08	45.762
337.11	102.75	197.674	18.365	1614.189	45.709	1622.56	45.946
337.14	102.76	198.207	18.414	1620.683	45.893	1629.05	46.130
337.17	102.77	198.744	18.464	1627.195	46.077	1635.56	46.314
337.20	102.78	199.274	18.513	1633.724	46.262	1642.09	46.499
337.24	102.79	199.796	18.562	1640.270	46.447	1648.64	46.684
337.27	102.8	200.306	18.609	1646.834	46.633	1655.20	46.870
337.30	102.81	200.804	18.655	1653.414	46.819	1661.78	47.056
337.34	102.82	201.305	18.702	1660.010	47.006	1668.38	47.243
337.37	102.83	201.824	18.750	1666.623	47.193	1674.99	47.430
337.40	102.84	202.345	18.799	1673.253	47.381	1681.62	47.618
337.43	102.85	202.876	18.848	1679.900	47.569	1688.27	47.806
337.47	102.86	203.407	18.897	1686.565	47.758	1694.93	47.995
337.50	102.87	203.951	18.948	1693.247	47.947	1701.61	48.184
337.53	102.88	204.502	18.999	1699.948	48.137	1708.32	48.374
337.57	102.89	205.057	19.050	1706.666	48.327	1715.03	48.564
337.60	102.9	205.617	19.102	1713.403	48.518	1721.77	48.755
337.63	102.91	206.168	19.154	1720.158	48.709	1728.53	48.946
337.66	102.92	206.725	19.205	1726.931	48.901	1735.30	49.138
337.70	102.93	207.284	19.257	1733.722	49.094	1742.09	49.330
337.73	102.94	207.841	19.309	1740.532	49.286	1748.90	49.523
337.76	102.95	208.395	19.361	1747.360	49.480	1755.73	49.717
337.80	102.96	208.947	19.412	1754.206	49.674	1762.57	49.910
337.83	102.97	209.492	19.462	1761.070	49.868	1769.44	50.105
337.86	102.98	210.033	19.513	1767.952	50.063	1776.32	50.300
337.89	102.99	210.586	19.564	1774.852	50.258	1783.22	50.495
337.93	103	211.144	19.616	1781.770	50.454	1790.14	50.691
337.96	103.01	211.690	19.667	1788.707	50.650	1797.07	50.887
337.99	103.02	212.239	19.718	1795.661	50.847	1804.03	51.084
338.02	103.03	212.805	19.770	1802.633	51.045	1811.00	51.282
338.06	103.04	213.373	19.823	1809.624	51.243	1817.99	51.480
338.09	103.05	213.943	19.876	1816.634	51.441	1825.00	51.678
338.12	103.06	214.519	19.929	1823.663	51.640	1832.03	51.877
338.16	103.07	215.106	19.984	1830.710	51.840	1839.08	52.077
338.19	103.08	215.692	20.038	1837.777	52.040	1846.14	52.277
338.22	103.09	216.277	20.093	1844.863	52.241	1853.23	52.478
338.25	103.1	216.871	20.148	1851.969	52.442	1860.34	52.679
338.29	103.11	217.477	20.204	1859.094	52.644	1867.46	52.881
338.32	103.12	218.070	20.259	1866.239	52.846	1874.61	53.083

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
338.35	103.13	218.679	20.316	1873.403	53.049	1881.77	53.286
338.39	103.14	219.278	20.372	1880.587	53.252	1888.96	53.489
338.42	103.15	219.876	20.427	1887.791	53.456	1896.16	53.693
338.45	103.16	220.472	20.483	1895.015	53.661	1903.38	53.898
338.48	103.17	221.055	20.537	1902.258	53.866	1910.63	54.103
338.52	103.18	221.625	20.590	1909.520	54.072	1917.89	54.308
338.55	103.19	222.198	20.643	1916.800	54.278	1925.17	54.515
338.58	103.2	222.766	20.696	1924.100	54.484	1932.47	54.721
338.62	103.21	223.324	20.747	1931.417	54.692	1939.79	54.929
338.65	103.22	223.867	20.798	1938.753	54.899	1947.12	55.136
338.68	103.23	224.418	20.849	1946.107	55.108	1954.47	55.345
338.71	103.24	224.972	20.901	1953.479	55.316	1961.85	55.553
338.75	103.25	225.517	20.951	1960.869	55.526	1969.24	55.763
338.78	103.26	226.068	21.002	1968.277	55.735	1976.64	55.972
338.81	103.27	226.623	21.054	1975.703	55.946	1984.07	56.183
338.85	103.28	227.179	21.106	1983.147	56.156	1991.51	56.393
338.88	103.29	227.735	21.157	1990.609	56.368	1998.98	56.605
338.91	103.3	228.294	21.209	1998.090	56.580	2006.46	56.817
338.94	103.31	228.852	21.261	2005.589	56.792	2013.96	57.029
338.98	103.32	229.414	21.313	2013.107	57.005	2021.47	57.242
339.01	103.33	229.969	21.365	2020.642	57.218	2029.01	57.455
339.04	103.34	230.510	21.415	2028.196	57.432	2036.56	57.669
339.07	103.35	231.047	21.465	2035.768	57.646	2044.14	57.883
339.11	103.36	231.575	21.514	2043.357	57.861	2051.72	58.098
339.14	103.37	232.092	21.562	2050.963	58.077	2059.33	58.314
339.17	103.38	232.608	21.610	2058.586	58.293	2066.95	58.530
339.21	103.39	233.140	21.659	2066.226	58.509	2074.59	58.746
339.24	103.4	233.674	21.709	2073.884	58.726	2082.25	58.963
339.27	103.41	234.213	21.759	2081.559	58.943	2089.93	59.180
339.30	103.42	234.775	21.811	2089.252	59.161	2097.62	59.398
339.34	103.43	235.344	21.864	2096.964	59.379	2105.33	59.616
339.37	103.44	235.888	21.915	2104.694	59.598	2113.06	59.835
339.40	103.45	236.428	21.965	2112.442	59.818	2120.81	60.055
339.44	103.46	236.969	22.015	2120.208	60.038	2128.58	60.274
339.47	103.47	237.510	22.065	2127.992	60.258	2136.36	60.495
339.50	103.48	238.050	22.116	2135.793	60.479	2144.16	60.716
339.53	103.49	238.590	22.166	2143.612	60.700	2151.98	60.937
339.57	103.5	239.132	22.216	2151.448	60.922	2159.82	61.159
339.60	103.51	239.682	22.267	2159.303	61.145	2167.67	61.382
339.63	103.52	240.241	22.319	2167.176	61.368	2175.54	61.604
339.67	103.53	240.795	22.371	2175.067	61.591	2183.43	61.828
339.70	103.54	241.348	22.422	2182.976	61.815	2191.34	62.052
339.73	103.55	241.901	22.473	2190.903	62.039	2199.27	62.276

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
339.76	103.56	242.466	22.526	2198.849	62.264	2207.22	62.501
339.80	103.57	243.028	22.578	2206.813	62.490	2215.18	62.727
339.83	103.58	243.595	22.631	2214.795	62.716	2223.16	62.953
339.86	103.59	244.180	22.685	2222.797	62.943	2231.16	63.179
339.90	103.6	244.787	22.741	2230.818	63.170	2239.19	63.407
339.93	103.61	245.397	22.798	2238.859	63.397	2247.23	63.634
339.96	103.62	246.010	22.855	2246.920	63.626	2255.29	63.863
339.99	103.63	246.628	22.913	2255.001	63.854	2263.37	64.091
340.03	103.64	247.236	22.969	2263.103	64.084	2271.47	64.321
340.06	103.65	247.836	23.025	2271.224	64.314	2279.59	64.551
340.09	103.66	248.444	23.081	2279.365	64.544	2287.73	64.781
340.12	103.67	249.073	23.140	2287.526	64.775	2295.89	65.012
340.16	103.68	249.691	23.197	2295.708	65.007	2304.08	65.244
340.19	103.69	250.302	23.254	2303.910	65.239	2312.28	65.476
340.22	103.7	250.913	23.311	2312.132	65.472	2320.50	65.709
340.26	103.71	251.516	23.367	2320.374	65.706	2328.74	65.943
340.29	103.72	252.124	23.423	2328.636	65.940	2337.00	66.177
340.32	103.73	252.749	23.481	2336.918	66.174	2345.29	66.411
340.35	103.74	253.365	23.538	2345.220	66.409	2353.59	66.646
340.39	103.75	253.991	23.597	2353.543	66.645	2361.91	66.882
340.42	103.76	254.621	23.655	2361.886	66.881	2370.25	67.118
340.45	103.77	255.254	23.714	2370.250	67.118	2378.62	67.355
340.49	103.78	255.883	23.772	2378.635	67.355	2387.00	67.592
340.52	103.79	256.522	23.832	2387.041	67.593	2395.41	67.830
340.55	103.8	257.174	23.892	2395.467	67.832	2403.84	68.069
340.58	103.81	257.826	23.953	2403.916	68.071	2412.28	68.308
340.62	103.82	258.474	24.013	2412.385	68.311	2420.75	68.548
340.65	103.83	259.110	24.072	2420.876	68.551	2429.24	68.788
340.68	103.84	259.724	24.129	2429.387	68.793	2437.75	69.029
340.72	103.85	260.310	24.184	2437.917	69.034	2446.29	69.271
340.75	103.86	260.889	24.237	2446.467	69.276	2454.83	69.513
340.78	103.87	261.465	24.291	2455.036	69.519	2463.40	69.756
340.81	103.88	262.014	24.342	2463.623	69.762	2471.99	69.999
340.85	103.89	262.545	24.391	2472.228	70.006	2480.60	70.243
340.88	103.9	263.078	24.441	2480.851	70.250	2489.22	70.487
340.91	103.91	263.611	24.490	2489.491	70.494	2497.86	70.731
340.94	103.92	264.128	24.538	2498.148	70.740	2506.52	70.977
340.98	103.93	264.641	24.586	2506.822	70.985	2515.19	71.222
341.01	103.94	265.151	24.633	2515.513	71.231	2523.88	71.468
341.04	103.95	265.668	24.681	2524.220	71.478	2532.59	71.715
341.08	103.96	266.190	24.730	2532.945	71.725	2541.31	71.962
341.11	103.97	266.717	24.779	2541.687	71.972	2550.05	72.209
341.14	103.98	267.240	24.827	2550.446	72.221	2558.81	72.457

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
341.17	103.99	267.762	24.876	2559.222	72.469	2567.59	72.706
341.21	104	268.266	24.923	2568.016	72.718	2576.38	72.955
341.24	104.01	268.764	24.969	2576.825	72.967	2585.19	73.204
341.27	104.02	269.259	25.015	2585.651	73.217	2594.02	73.454
341.31	104.03	269.760	25.062	2594.493	73.468	2602.86	73.705
341.34	104.04	270.270	25.109	2603.352	73.719	2611.72	73.956
341.37	104.05	270.770	25.155	2612.227	73.970	2620.59	74.207
341.40	104.06	271.274	25.202	2621.119	74.222	2629.49	74.459
341.44	104.07	271.778	25.249	2630.027	74.474	2638.40	74.711
341.47	104.08	272.284	25.296	2638.952	74.727	2647.32	74.964
341.50	104.09	272.798	25.344	2647.894	74.980	2656.26	75.217
341.54	104.1	273.328	25.393	2656.853	75.234	2665.22	75.471
341.57	104.11	273.850	25.442	2665.829	75.488	2674.20	75.725
341.60	104.12	274.373	25.490	2674.822	75.742	2683.19	75.979
341.63	104.13	274.904	25.539	2683.832	75.998	2692.20	76.235
341.67	104.14	275.444	25.590	2692.860	76.253	2701.23	76.490
341.70	104.15	275.982	25.640	2701.906	76.509	2710.27	76.746
341.73	104.16	276.518	25.689	2710.969	76.766	2719.34	77.003
341.77	104.17	277.058	25.740	2720.050	77.023	2728.42	77.260
341.80	104.18	277.608	25.791	2729.149	77.281	2737.52	77.518
341.83	104.19	278.165	25.842	2738.266	77.539	2746.63	77.776
341.86	104.2	278.726	25.895	2747.401	77.798	2755.77	78.035
341.90	104.21	279.272	25.945	2756.555	78.057	2764.92	78.294
341.93	104.22	279.826	25.997	2765.727	78.317	2774.09	78.554
341.96	104.23	280.383	26.048	2774.916	78.577	2783.28	78.814
341.99	104.24	280.941	26.100	2784.124	78.838	2792.49	79.074
342.03	104.25	281.488	26.151	2793.351	79.099	2801.72	79.336
342.06	104.26	282.017	26.200	2802.595	79.361	2810.96	79.598
342.09	104.27	282.542	26.249	2811.856	79.623	2820.22	79.860
342.13	104.28	283.070	26.298	2821.134	79.886	2829.50	80.122
342.16	104.29	283.607	26.348	2830.430	80.149	2838.80	80.386
342.19	104.3	284.155	26.399	2839.744	80.413	2848.11	80.649
342.22	104.31	284.686	26.448	2849.075	80.677	2857.44	80.914
342.26	104.32	285.210	26.497	2858.424	80.941	2866.79	81.178
342.29	104.33	285.734	26.546	2867.790	81.207	2876.16	81.444
342.32	104.34	286.261	26.595	2877.173	81.472	2885.54	81.709
342.36	104.35	286.788	26.644	2886.573	81.739	2894.94	81.976
342.39	104.36	287.314	26.692	2895.991	82.005	2904.36	82.242
342.42	104.37	287.837	26.741	2905.426	82.272	2913.79	82.509
342.45	104.38	288.364	26.790	2914.878	82.540	2923.25	82.777
342.49	104.39	288.893	26.839	2924.347	82.808	2932.71	83.045
342.52	104.4	289.427	26.889	2933.834	83.077	2942.20	83.314
342.55	104.41	289.969	26.939	2943.339	83.346	2951.71	83.583



Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
342.59	104.42	290.504	26.989	2952.861	83.616	2961.23	83.853
342.62	104.43	291.044	27.039	2962.401	83.886	2970.77	84.123
342.65	104.44	291.583	27.089	2971.958	84.156	2980.33	84.393
342.68	104.45	292.123	27.139	2981.533	84.428	2989.90	84.664
342.72	104.46	292.654	27.188	2991.126	84.699	2999.49	84.936
342.75	104.47	293.178	27.237	3000.736	84.971	3009.10	85.208
342.78	104.48	293.709	27.286	3010.364	85.244	3018.73	85.481
342.81	104.49	294.240	27.336	3020.009	85.517	3028.38	85.754
342.85	104.5	294.768	27.385	3029.671	85.791	3038.04	86.028
342.88	104.51	295.298	27.434	3039.350	86.065	3047.72	86.302
342.91	104.52	295.831	27.484	3049.047	86.339	3057.42	86.576
342.95	104.53	296.360	27.533	3058.762	86.614	3067.13	86.851
342.98	104.54	296.894	27.582	3068.494	86.890	3076.86	87.127
343.01	104.55	297.428	27.632	3078.243	87.166	3086.61	87.403
343.04	104.56	297.961	27.681	3088.010	87.443	3096.38	87.680
343.08	104.57	298.497	27.731	3097.794	87.720	3106.16	87.957
343.11	104.58	299.038	27.782	3107.596	87.997	3115.96	88.234
343.14	104.59	299.582	27.832	3117.416	88.275	3125.78	88.512
343.18	104.6	300.133	27.883	3127.254	88.554	3135.62	88.791
343.21	104.61	300.683	27.934	3137.110	88.833	3145.48	89.070
343.24	104.62	301.230	27.985	3146.984	89.113	3155.35	89.350
343.27	104.63	301.769	28.035	3156.876	89.393	3165.24	89.630
343.31	104.64	302.307	28.085	3166.785	89.673	3175.15	89.910
343.34	104.65	302.851	28.136	3176.712	89.954	3185.08	90.191
343.37	104.66	303.398	28.187	3186.657	90.236	3195.02	90.473
343.41	104.67	303.949	28.238	3196.620	90.518	3204.99	90.755
343.44	104.68	304.502	28.289	3206.601	90.801	3214.97	91.038
343.47	104.69	305.059	28.341	3216.601	91.084	3224.97	91.321
343.50	104.7	305.624	28.393	3226.619	91.368	3234.99	91.605
343.54	104.71	306.188	28.446	3236.655	91.652	3245.02	91.889
343.57	104.72	306.756	28.499	3246.710	91.936	3255.08	92.173
343.60	104.73	307.313	28.550	3256.783	92.222	3265.15	92.459
343.64	104.74	307.872	28.602	3266.875	92.508	3275.24	92.744
343.67	104.75	308.427	28.654	3276.985	92.794	3285.35	93.031
343.70	104.76	308.984	28.706	3287.113	93.081	3295.48	93.318
343.73	104.77	309.528	28.756	3297.259	93.368	3305.63	93.605
343.77	104.78	310.075	28.807	3307.423	93.656	3315.79	93.893
343.80	104.79	310.639	28.859	3317.605	93.944	3325.97	94.181
343.83	104.8	311.214	28.913	3327.806	94.233	3336.17	94.470
343.86	104.81	311.794	28.967	3338.026	94.522	3346.39	94.759
343.90	104.82	312.382	29.021	3348.265	94.812	3356.63	95.049
343.93	104.83	312.973	29.076	3358.524	95.103	3366.89	95.340
343.96	104.84	313.564	29.131	3368.802	95.394	3377.17	95.631

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
344.00	104.85	314.152	29.186	3379.099	95.685	3387.47	95.922
344.03	104.86	314.740	29.240	3389.415	95.977	3397.78	96.214
344.06	104.87	315.329	29.295	3399.751	96.270	3408.12	96.507
344.09	104.88	315.927	29.351	3410.106	96.563	3418.47	96.800
344.13	104.89	316.525	29.406	3420.481	96.857	3428.85	97.094
344.16	104.9	317.133	29.463	3430.876	97.151	3439.24	97.388
344.19	104.91	317.738	29.519	3441.290	97.446	3449.66	97.683
344.23	104.92	318.347	29.575	3451.725	97.742	3460.09	97.979
344.26	104.93	318.966	29.633	3462.180	98.038	3470.55	98.275
344.29	104.94	319.584	29.690	3472.654	98.335	3481.02	98.571
344.32	104.95	320.197	29.747	3483.149	98.632	3491.52	98.869
344.36	104.96	320.810	29.804	3493.665	98.929	3502.03	99.166
344.39	104.97	321.420	29.861	3504.200	99.228	3512.57	99.465
344.42	104.98	322.026	29.917	3514.755	99.527	3523.12	99.764
344.46	104.99	322.632	29.974	3525.330	99.826	3533.70	100.063
344.49	105	323.237	30.030	3535.925	100.126	3544.29	100.363
344.52	105.01	323.846	30.086	3546.540	100.427	3554.91	100.664
344.55	105.02	324.455	30.143	3557.175	100.728	3565.54	100.965
344.59	105.03	325.075	30.201	3567.830	101.030	3576.20	101.267
344.62	105.04	325.692	30.258	3578.505	101.332	3586.87	101.569
344.65	105.05	326.308	30.315	3589.201	101.635	3597.57	101.872
344.69	105.06	326.932	30.373	3599.917	101.938	3608.28	102.175
344.72	105.07	327.555	30.431	3610.653	102.242	3619.02	102.479
344.75	105.08	328.176	30.489	3621.410	102.547	3629.78	102.784
344.78	105.09	328.793	30.546	3632.187	102.852	3640.55	103.089
344.82	105.1	329.405	30.603	3642.984	103.158	3651.35	103.395
344.85	105.11	330.011	30.659	3653.801	103.464	3662.17	103.701
344.88	105.12	330.606	30.714	3664.638	103.771	3673.01	104.008
344.91	105.13	331.199	30.769	3675.495	104.078	3683.86	104.315
344.95	105.14	331.800	30.825	3686.370	104.386	3694.74	104.623
344.98	105.15	332.410	30.882	3697.266	104.695	3705.63	104.932
345.01	105.16	333.021	30.939	3708.182	105.004	3716.55	105.241
345.05	105.17	333.635	30.996	3719.118	105.314	3727.49	105.551
345.08	105.18	334.234	31.051	3730.074	105.624	3738.44	105.861
345.11	105.19	334.834	31.107	3741.050	105.935	3749.42	106.172
345.14	105.2	335.443	31.164	3752.045	106.246	3760.41	106.483
345.18	105.21	336.069	31.222	3763.060	106.558	3771.43	106.795
345.21	105.22	336.700	31.280	3774.097	106.870	3782.46	107.107
345.24	105.23	337.337	31.340	3785.154	107.184	3793.52	107.420
345.28	105.24	337.973	31.399	3796.232	107.497	3804.60	107.734
345.31	105.25	338.610	31.458	3807.330	107.811	3815.70	108.048
345.34	105.26	339.250	31.517	3818.450	108.126	3826.82	108.363
345.37	105.27	339.892	31.577	3829.591	108.442	3837.96	108.679

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
345.41	105.28	340.545	31.638	3840.753	108.758	3849.12	108.995
345.44	105.29	341.205	31.699	3851.936	109.075	3860.30	109.312
345.47	105.3	341.870	31.761	3863.142	109.392	3871.51	109.629
345.51	105.31	342.550	31.824	3874.369	109.710	3882.74	109.947
345.54	105.32	343.249	31.889	3885.619	110.028	3893.99	110.265
345.57	105.33	343.946	31.954	3896.892	110.348	3905.26	110.585
345.60	105.34	344.649	32.019	3908.188	110.667	3916.56	110.904
345.64	105.35	345.356	32.085	3919.507	110.988	3927.87	111.225
345.67	105.36	346.051	32.149	3930.849	111.309	3939.22	111.546
345.70	105.37	346.744	32.214	3942.214	111.631	3950.58	111.868
345.73	105.38	347.432	32.278	3953.601	111.953	3961.97	112.190
345.77	105.39	348.123	32.342	3965.011	112.277	3973.38	112.513
345.80	105.4	348.832	32.408	3976.444	112.600	3984.81	112.837
345.83	105.41	349.562	32.475	3987.900	112.925	3996.27	113.162
345.87	105.42	350.287	32.543	3999.381	113.250	4007.75	113.487
345.90	105.43	351.024	32.611	4010.885	113.576	4019.25	113.812
345.93	105.44	351.769	32.680	4022.414	113.902	4030.78	114.139
345.96	105.45	352.519	32.750	4033.967	114.229	4042.33	114.466
346.00	105.46	353.265	32.819	4045.545	114.557	4053.91	114.794
346.03	105.47	354.016	32.889	4057.147	114.886	4065.52	115.122
346.06	105.48	354.747	32.957	4068.774	115.215	4077.14	115.452
346.10	105.49	355.466	33.024	4080.425	115.545	4088.79	115.782
346.13	105.5	356.194	33.092	4092.099	115.875	4100.47	116.112
346.16	105.51	356.920	33.159	4103.797	116.206	4112.16	116.443
346.19	105.52	357.627	33.225	4115.519	116.538	4123.89	116.775
346.23	105.53	358.326	33.290	4127.263	116.871	4135.63	117.108
346.26	105.54	359.030	33.355	4139.031	117.204	4147.40	117.441
346.29	105.55	359.737	33.421	4150.822	117.538	4159.19	117.775
346.33	105.56	360.439	33.486	4162.636	117.873	4171.00	118.110
346.36	105.57	361.135	33.551	4174.473	118.208	4182.84	118.445
346.39	105.58	361.830	33.615	4186.332	118.544	4194.70	118.781
346.42	105.59	362.526	33.680	4198.215	118.880	4206.58	119.117
346.46	105.6	363.210	33.743	4210.120	119.217	4218.49	119.454
346.49	105.61	363.898	33.807	4222.047	119.555	4230.42	119.792
346.52	105.62	364.587	33.871	4233.998	119.893	4242.37	120.130
346.56	105.63	365.272	33.935	4245.971	120.232	4254.34	120.469
346.59	105.64	365.952	33.998	4257.966	120.572	4266.33	120.809
346.62	105.65	366.634	34.061	4269.983	120.912	4278.35	121.149
346.65	105.66	367.313	34.125	4282.023	121.253	4290.39	121.490
346.69	105.67	367.975	34.186	4294.085	121.595	4302.45	121.832
346.72	105.68	368.644	34.248	4306.169	121.937	4314.54	122.174
346.75	105.69	369.315	34.311	4318.274	122.280	4326.64	122.517
346.78	105.7	369.997	34.374	4330.402	122.623	4338.77	122.860

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
346.82	105.71	370.677	34.437	4342.552	122.967	4350.92	123.204
346.85	105.72	371.360	34.501	4354.725	123.312	4363.09	123.549
346.88	105.73	372.050	34.565	4366.920	123.657	4375.29	123.894
346.92	105.74	372.745	34.629	4379.138	124.003	4387.51	124.240
346.95	105.75	373.465	34.696	4391.378	124.350	4399.75	124.587
346.98	105.76	374.168	34.761	4403.643	124.697	4412.01	124.934
347.01	105.77	374.856	34.825	4415.930	125.045	4424.30	125.282
347.05	105.78	375.542	34.889	4428.240	125.394	4436.61	125.631
347.08	105.79	376.234	34.953	4440.572	125.743	4448.94	125.980
347.11	105.8	376.929	35.018	4452.927	126.093	4461.29	126.330
347.15	105.81	377.626	35.083	4465.305	126.443	4473.67	126.680
347.18	105.82	378.331	35.148	4477.706	126.794	4486.07	127.031
347.21	105.83	379.039	35.214	4490.130	127.146	4498.50	127.383
347.24	105.84	379.747	35.280	4502.577	127.499	4510.94	127.736
347.28	105.85	380.463	35.346	4515.048	127.852	4523.42	128.089
347.31	105.86	381.170	35.412	4527.542	128.206	4535.91	128.443
347.34	105.87	381.873	35.477	4540.059	128.560	4548.43	128.797
347.38	105.88	382.573	35.542	4552.599	128.915	4560.97	129.152
347.41	105.89	383.273	35.607	4565.162	129.271	4573.53	129.508
347.44	105.9	383.983	35.673	4577.748	129.627	4586.12	129.864
347.47	105.91	384.686	35.739	4590.358	129.984	4598.73	130.221
347.51	105.92	385.392	35.804	4602.990	130.342	4611.36	130.579
347.54	105.93	386.101	35.870	4615.646	130.700	4624.01	130.937
347.57	105.94	386.822	35.937	4628.325	131.059	4636.69	131.296
347.60	105.95	387.553	36.005	4641.028	131.419	4649.40	131.656
347.64	105.96	388.301	36.074	4653.755	131.780	4662.12	132.016
347.67	105.97	389.062	36.145	4666.507	132.141	4674.88	132.378
347.70	105.98	389.809	36.214	4679.284	132.502	4687.65	132.739
347.74	105.99	390.544	36.283	4692.085	132.865	4700.45	133.102
347.77	106	391.258	36.349	4704.910	133.228	4713.28	133.465
347.80	106.01	391.973	36.415	4717.758	133.592	4726.13	133.829
347.83	106.02	392.686	36.482	4730.630	133.956	4739.00	134.193
347.87	106.03	393.394	36.548	4743.525	134.322	4751.89	134.558
347.90	106.04	394.104	36.614	4756.443	134.687	4764.81	134.924
347.93	106.05	394.819	36.680	4769.385	135.054	4777.75	135.291
347.97	106.06	395.563	36.749	4782.351	135.421	4790.72	135.658
348.00	106.07	396.323	36.820	4795.341	135.789	4803.71	136.026
348.03	106.08	397.069	36.889	4808.356	136.157	4816.72	136.394
348.06	106.09	397.829	36.960	4821.396	136.527	4829.76	136.764
348.10	106.1	398.593	37.031	4834.460	136.897	4842.83	137.133
348.13	106.11	399.361	37.102	4847.550	137.267	4855.92	137.504
348.16	106.12	400.158	37.176	4860.665	137.639	4869.03	137.876
348.20	106.13	400.990	37.253	4873.808	138.011	4882.18	138.248

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
348.23	106.14	401.794	37.328	4886.977	138.384	4895.34	138.621
348.26	106.15	402.582	37.401	4900.172	138.757	4908.54	138.994
348.29	106.16	403.296	37.467	4913.392	139.132	4921.76	139.369
348.33	106.17	403.992	37.532	4926.635	139.507	4935.00	139.744
348.36	106.18	404.683	37.596	4939.900	139.882	4948.27	140.119
348.39	106.19	405.379	37.661	4953.189	140.259	4961.56	140.495
348.43	106.2	406.078	37.726	4966.500	140.635	4974.87	140.872
348.46	106.21	406.772	37.790	4979.834	141.013	4988.20	141.250
348.49	106.22	407.464	37.855	4993.191	141.391	5001.56	141.628
348.52	106.23	408.153	37.919	5006.571	141.770	5014.94	142.007
348.56	106.24	408.846	37.983	5019.973	142.150	5028.34	142.387
348.59	106.25	409.540	38.048	5033.398	142.530	5041.77	142.767
348.62	106.26	410.240	38.113	5046.846	142.911	5055.21	143.148
348.65	106.27	410.935	38.177	5060.316	143.292	5068.68	143.529
348.69	106.28	411.637	38.242	5073.810	143.674	5082.18	143.911
348.72	106.29	412.361	38.310	5087.327	144.057	5095.69	144.294
348.75	106.3	413.057	38.374	5100.868	144.440	5109.24	144.677
348.79	106.31	413.754	38.439	5114.431	144.824	5122.80	145.061
348.82	106.32	414.449	38.504	5128.017	145.209	5136.38	145.446
348.85	106.33	415.147	38.568	5141.626	145.594	5149.99	145.831
348.88	106.34	415.842	38.633	5155.257	145.980	5163.63	146.217
348.92	106.35	416.553	38.699	5168.912	146.367	5177.28	146.604
348.95	106.36	417.269	38.766	5182.590	146.754	5190.96	146.991
348.98	106.37	417.980	38.832	5196.292	147.142	5204.66	147.379
349.02	106.38	418.696	38.898	5210.017	147.531	5218.38	147.768
349.05	106.39	419.445	38.968	5223.766	147.920	5232.13	148.157
349.08	106.4	420.171	39.035	5237.539	148.310	5245.91	148.547
349.11	106.41	420.887	39.102	5251.336	148.701	5259.70	148.938
349.15	106.42	421.581	39.166	5265.156	149.092	5273.52	149.329
349.18	106.43	422.275	39.231	5278.999	149.484	5287.37	149.721
349.21	106.44	422.953	39.294	5292.864	149.877	5301.23	150.114
349.25	106.45	423.624	39.356	5306.752	150.270	5315.12	150.507
349.28	106.46	424.293	39.418	5320.661	150.664	5329.03	150.901
349.31	106.47	424.960	39.480	5334.592	151.059	5342.96	151.296
349.34	106.48	425.619	39.541	5348.546	151.454	5356.91	151.691
349.38	106.49	426.265	39.601	5362.520	151.850	5370.89	152.086
349.41	106.5	426.906	39.661	5376.516	152.246	5384.88	152.483
349.44	106.51	427.535	39.719	5390.532	152.643	5398.90	152.880
349.48	106.52	428.153	39.777	5404.569	153.040	5412.94	153.277
349.51	106.53	428.762	39.833	5418.626	153.438	5426.99	153.675
349.54	106.54	429.364	39.889	5432.703	153.837	5441.07	154.074
349.57	106.55	429.962	39.945	5446.800	154.236	5455.17	154.473
349.61	106.56	430.551	40.000	5460.916	154.636	5469.28	154.873

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
349.64	106.57	431.140	40.054	5475.051	155.036	5483.42	155.273
349.67	106.58	431.732	40.109	5489.206	155.437	5497.57	155.674
349.70	106.59	432.326	40.164	5503.380	155.838	5511.75	156.075
349.74	106.6	432.918	40.219	5517.574	156.240	5525.94	156.477
349.77	106.61	433.503	40.274	5531.787	156.643	5540.15	156.880
349.80	106.62	434.081	40.327	5546.019	157.046	5554.39	157.283
349.84	106.63	434.656	40.381	5560.270	157.449	5568.64	157.686
349.87	106.64	435.234	40.435	5574.540	157.853	5582.91	158.090
349.90	106.65	435.816	40.489	5588.828	158.258	5597.20	158.495
349.93	106.66	436.407	40.544	5603.137	158.663	5611.50	158.900
349.97	106.67	437.004	40.599	5617.464	159.069	5625.83	159.306
350.00	106.68	437.599	40.654	5631.811	159.475	5640.18	159.712
350.03	106.69	438.193	40.710	5646.178	159.882	5654.55	160.119
350.07	106.7	438.782	40.764	5660.564	160.289	5668.93	160.526
350.10	106.71	439.362	40.818	5674.970	160.697	5683.34	160.934
350.13	106.72	439.930	40.871	5689.394	161.106	5697.76	161.342
350.16	106.73	440.495	40.923	5703.836	161.515	5712.20	161.751
350.20	106.74	441.057	40.976	5718.298	161.924	5726.67	162.161
350.23	106.75	441.621	41.028	5732.777	162.334	5741.14	162.571
350.26	106.76	442.189	41.081	5747.275	162.745	5755.64	162.982
350.30	106.77	442.763	41.134	5761.792	163.156	5770.16	163.393
350.33	106.78	443.341	41.188	5776.328	163.567	5784.70	163.804
350.36	106.79	443.926	41.242	5790.883	163.979	5799.25	164.216
350.39	106.8	444.517	41.297	5805.457	164.392	5813.82	164.629
350.43	106.81	445.103	41.351	5820.051	164.805	5828.42	165.042
350.46	106.82	445.689	41.406	5834.664	165.219	5843.03	165.456
350.49	106.83	446.270	41.460	5849.296	165.633	5857.66	165.870
350.52	106.84	446.845	41.513	5863.946	166.048	5872.31	166.285
350.56	106.85	447.421	41.567	5878.616	166.464	5886.98	166.701
350.59	106.86	447.993	41.620	5893.305	166.880	5901.67	167.117
350.62	106.87	448.559	41.673	5908.012	167.296	5916.38	167.533
350.66	106.88	449.126	41.725	5922.738	167.713	5931.11	167.950
350.69	106.89	449.699	41.778	5937.482	168.131	5945.85	168.368
350.72	106.9	450.271	41.832	5952.246	168.549	5960.61	168.786
350.75	106.91	450.835	41.884	5967.028	168.967	5975.40	169.204
350.79	106.92	451.400	41.936	5981.828	169.386	5990.20	169.623
350.82	106.93	451.958	41.988	5996.647	169.806	6005.01	170.043
350.85	106.94	452.513	42.040	6011.484	170.226	6019.85	170.463
350.89	106.95	453.067	42.091	6026.340	170.647	6034.71	170.884
350.92	106.96	453.619	42.143	6041.213	171.068	6049.58	171.305
350.95	106.97	454.179	42.195	6056.105	171.490	6064.47	171.727
350.98	106.98	454.744	42.247	6071.015	171.912	6079.38	172.149
351.02	106.99	455.312	42.300	6085.944	172.335	6094.31	172.572

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
351.05	107	455.889	42.353	6100.891	172.758	6109.26	172.995
351.08	107.01	456.471	42.408	6115.858	173.182	6124.23	173.419
351.12	107.02	457.049	42.461	6130.843	173.606	6139.21	173.843
351.15	107.03	457.623	42.515	6145.848	174.031	6154.22	174.268
351.18	107.04	458.194	42.568	6160.871	174.456	6169.24	174.693
351.21	107.05	458.770	42.621	6175.913	174.882	6184.28	175.119
351.25	107.06	459.347	42.675	6190.974	175.309	6199.34	175.546
351.28	107.07	459.912	42.727	6206.054	175.736	6214.42	175.973
351.31	107.08	460.473	42.779	6221.152	176.163	6229.52	176.400
351.35	107.09	461.029	42.831	6236.269	176.591	6244.64	176.828
351.38	107.1	461.586	42.883	6251.403	177.020	6259.77	177.257
351.41	107.11	462.143	42.935	6266.557	177.449	6274.92	177.686
351.44	107.12	462.699	42.986	6281.728	177.879	6290.10	178.116
351.48	107.13	463.249	43.037	6296.917	178.309	6305.29	178.546
351.51	107.14	463.788	43.087	6312.125	178.739	6320.49	178.976
351.54	107.15	464.322	43.137	6327.350	179.170	6335.72	179.407
351.57	107.16	464.850	43.186	6342.592	179.602	6350.96	179.839
351.61	107.17	465.376	43.235	6357.852	180.034	6366.22	180.271
351.64	107.18	465.902	43.284	6373.129	180.467	6381.50	180.704
351.67	107.19	466.426	43.332	6388.423	180.900	6396.79	181.137
351.71	107.2	466.955	43.382	6403.734	181.333	6412.10	181.570
351.74	107.21	467.488	43.431	6419.063	181.767	6427.43	182.004
351.77	107.22	468.026	43.481	6434.409	182.202	6442.78	182.439
351.80	107.23	468.567	43.531	6449.773	182.637	6458.14	182.874
351.84	107.24	469.113	43.582	6465.155	183.073	6473.52	183.310
351.87	107.25	469.677	43.634	6480.555	183.509	6488.92	183.746
351.90	107.26	470.237	43.686	6495.974	183.945	6504.34	184.182
351.94	107.27	470.789	43.738	6511.411	184.382	6519.78	184.619
351.97	107.28	471.338	43.789	6526.866	184.820	6535.23	185.057
352.00	107.29	471.879	43.839	6542.338	185.258	6550.71	185.495
352.03	107.3	472.411	43.888	6557.829	185.697	6566.20	185.934
352.07	107.31	472.938	43.937	6573.337	186.136	6581.70	186.373
352.10	107.32	473.463	43.986	6588.862	186.576	6597.23	186.813
352.13	107.33	473.990	44.035	6604.404	187.016	6612.77	187.253
352.17	107.34	474.515	44.084	6619.963	187.456	6628.33	187.693
352.20	107.35	475.038	44.133	6635.540	187.897	6643.91	188.134
352.23	107.36	475.562	44.181	6651.134	188.339	6659.50	188.576
352.26	107.37	476.091	44.230	6666.745	188.781	6675.11	189.018
352.30	107.38	476.618	44.279	6682.373	189.224	6690.74	189.461
352.33	107.39	477.145	44.328	6698.019	189.667	6706.39	189.904
352.36	107.4	477.667	44.377	6713.682	190.110	6722.05	190.347
352.40	107.41	478.190	44.425	6729.362	190.554	6737.73	190.791
352.43	107.42	478.720	44.475	6745.060	190.999	6753.43	191.236

Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)	
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)
352.46	107.43	479.256	44.524	6760.774	191.444	6769.14	191.681
352.49	107.44	479.791	44.574	6776.507	191.889	6784.87	192.126
352.53	107.45	480.327	44.624	6792.257	192.335	6800.62	192.572
352.56	107.46	480.860	44.673	6808.024	192.782	6816.39	193.019
352.59	107.47	481.387	44.722	6823.809	193.229	6832.18	193.466
352.62	107.48	481.912	44.771	6839.612	193.676	6847.98	193.913
352.66	107.49	482.434	44.820	6855.431	194.124	6863.80	194.361
352.69	107.5	482.959	44.868	6871.267	194.572	6879.64	194.809
352.72	107.51	483.491	44.918	6887.121	195.021	6895.49	195.258
352.76	107.52	484.027	44.968	6902.993	195.471	6911.36	195.708
352.79	107.53	484.569	45.018	6918.882	195.921	6927.25	196.158
352.82	107.54	485.112	45.068	6934.789	196.371	6943.16	196.608
352.85	107.55	485.650	45.118	6950.713	196.822	6959.08	197.059
352.89	107.56	486.187	45.168	6966.655	197.274	6975.02	197.510
352.92	107.57	486.732	45.219	6982.615	197.725	6990.98	197.962
352.95	107.58	487.274	45.269	6998.593	198.178	7006.96	198.415
352.99	107.59	487.819	45.320	7014.589	198.631	7022.96	198.868
353.02	107.6	488.364	45.371	7030.602	199.084	7038.97	199.321
353.05	107.61	488.907	45.421	7046.634	199.538	7055.00	199.775
353.08	107.62	489.441	45.471	7062.683	199.993	7071.05	200.230
353.12	107.63	489.975	45.520	7078.749	200.448	7087.12	200.685
353.15	107.64	490.516	45.570	7094.834	200.903	7103.20	201.140
353.18	107.65	491.061	45.621	7110.936	201.359	7119.30	201.596
353.22	107.66	491.607	45.672	7127.055	201.816	7135.42	202.052
353.25	107.67	492.159	45.723	7143.193	202.273	7151.56	202.509
353.28	107.68	492.718	45.775	7159.349	202.730	7167.72	202.967
353.31	107.69	493.286	45.828	7175.524	203.188	7183.89	203.425
353.35	107.7	493.866	45.882	7191.718	203.647	7200.09	203.884
353.38	107.71	494.465	45.937	7207.930	204.106	7216.30	204.343
353.41	107.72	495.074	45.994	7224.163	204.565	7232.53	204.802
353.44	107.73	495.677	46.050	7240.415	205.026	7248.78	205.262
353.48	107.74	496.275	46.106	7256.688	205.486	7265.06	205.723
353.51	107.75	496.884	46.162	7272.980	205.948	7281.35	206.185
353.54	107.76	497.494	46.219	7289.292	206.410	7297.66	206.647
353.58	107.77	498.098	46.275	7305.624	206.872	7313.99	207.109
353.61	107.78	498.686	46.330	7321.975	207.335	7330.34	207.572
353.64	107.79	499.279	46.385	7338.346	207.799	7346.71	208.036
353.67	107.8	499.879	46.440	7354.736	208.263	7363.10	208.500
353.71	107.81	500.495	46.498	7371.147	208.727	7379.51	208.964
353.74	107.82	501.113	46.555	7387.577	209.193	7395.94	209.430
353.77	107.83	501.734	46.613	7404.028	209.659	7412.40	209.895
353.81	107.84	502.364	46.671	7420.500	210.125	7428.87	210.362
353.84	107.85	502.983	46.729	7436.992	210.592	7445.36	210.829



Elevation (MSL, ft)	Elevation (MSL, m)	Area (M.Sq.ft)	Area (M.Sq.m)	Live Capacity		Gross Capacity (Live + Dead)		
				Volume (M.Cu.ft)	Volume (M.Cu.m)	Volume (M.Cu.ft)	Volume (M.Cu.m)	
353.87	107.86	503.598	46.786	7453.504	211.060	7461.87	211.296	
353.90	107.87	504.211	46.843	7470.036	211.528	7478.40	211.765	
353.94	107.88	504.826	46.900	7486.589	211.996	7494.96	212.233	
353.97	107.89	505.436	46.957	7503.161	212.466	7511.53	212.703	
<b>354.00</b>	<b>107.9</b>	<b>506.045</b>	<b>47.013</b>	<b>7519.754</b>	<b>212.936</b>	<b>7528.12</b>	<b>213.172</b>	<b>FRL</b>
354.04	107.91	506.659	47.070	7536.366	213.406	7544.73	213.643	
354.07	107.92	507.284	47.128	7552.999	213.877	7561.37	214.114	
354.10	107.93	507.911	47.186	7569.653	214.348	7578.02	214.585	
354.13	107.94	508.536	47.245	7586.327	214.821	7594.69	215.058	
354.17	107.95	509.167	47.303	7603.021	215.293	7611.39	215.530	
354.20	107.96	509.802	47.362	7619.737	215.767	7628.10	216.004	
354.23	107.97	510.444	47.422	7636.473	216.241	7644.84	216.478	
354.27	107.98	511.080	47.481	7653.231	216.715	7661.60	216.952	
354.30	107.99	511.705	47.539	7670.009	217.190	7678.38	217.427	
354.33	108	512.322	47.596	7686.807	217.666	7695.17	217.903	

1.1

## **Annexure - 2**

### **Mobilisation and Calibration Report**

## 2 MOBILISATION

### 2.1 Introduction

Ocean Science & Surveying Pvt. Ltd. (OSaS) was contracted by Narmada Water Resources, Water Supply & Kalpsar Department (WRD) to carry out topographic and bathymetric survey of thirteen reservoirs in the Saurashtra region; namely Bhadar-1, Bhadar-2, Brahmani-1, Und-1, Machhu-1, Machhu-2, Khodiyar, Aaji-1, Nara, Tappar, Rudramata, Mitti and Fatehgadh.

This report documents the mobilisation and calibrations carried out by OSaS on board SMB Ocean for bathymetric survey of Bhadar-1 reservoir in Saurashtra region, Gujarat.

The survey team arrived at the survey site on 13<sup>th</sup> January 2021. After necessary meetings and discussions, the survey team started mobilisation of equipment on 15<sup>th</sup> January 2021 while the survey boat SMB Ocean was alongside at Val tower, Bhadar-1 dam. DGPS consistency check was done on 14<sup>th</sup> January through establishing two reference stations (TBM) using RTK systems. The levelling of these TBMs was carried out on the same day with respect to the known level of F.R.L provided by the client. Initial system preparation and equipment checks were completed on 16<sup>th</sup> January 2021. Bar check has been carried out every day before commencing the survey. The bathymetric and topographic survey commenced on 17<sup>th</sup> Jan 2021 at Bhadar-1 reservoir. Bathymetric survey was completed on 24<sup>th</sup> February 2021 and topographic survey was completed on 06<sup>th</sup> March 2021.

### 2.2 HSE Checks

A safety induction was given by the Party Chief prior to survey, detailing personnel responsibilities in the event of an emergency, life jacket locations, safety gear locations and procedures and signals for emergencies.

Back deck procedures were explained and enforced with no single man operations and all non-essential personnel keeping clear of operations. PPE included safety boots, hard hats and cover-alls for all personnel involved in back deck operations.

### 2.3 Survey Equipment list on SMB Ocean

#### 2.3.1 Navigation and Positioning

Item	Quantity
Hemisphere DGPS system with cables	1
Navigation computer with Hypack software	1
Moxa 8-port cable	4
Hemisphere RTK system with all accessories	3

#### 2.3.2 Single beam Echo sounder

Item	Quantity
Odom MK III Single beam echo sounder	2
Dual frequency transducer and mounting pole	2
Bar check	1
MRU-PD	2
TSS HS-50 Heave sensor	1

#### 2.3.3 Auto Level

Item	Quantity
Geomax auto level	1

#### 2.3.4 Power Systems


Item	Quantity
2KVA stabilizer	2
1 KVA generator	3
24V power supply	5
Exide battery 100AH	1

#### 2.3.5 Miscellaneous

Item	Quantity
Monitor	5
Laptop	2
LCD monitors	5
24V power supply	5
Helmets / life jackets	8
Tool box	1
Tripod and Tribrach	4 & 3
Exide battery 100AH	1
Antenna T-section	2 Sets
Echo rolls	52 nos
HP printer	1 nos
UPS	2 Sets
Switch board	9 Sets
Drill machine	1 Set

## 2.4 Vessel Offset Diagram

The equipment offsets in the Survey Motor Boat (SMB) Ocean are shown in the figure below:



### 3 EQUIPMENT CALIBRATIONS





#### 3.1 DGPS Calibrations

The details of the DGPS consistency checks are as follows:





In order to determine the integrity and reliability of the positioning system, the system was checked for its consistency during mobilisation.

Two reference stations were established as temporary control points/temporary benchmarks (TMB). The levelling of these TBMs was completed using an auto level, with respect to the known level of F.R.L which is given as 107.90m above MSL, provided by the client. The base stations of the RTK were set up at these positions and two-hour continuous observations using Hemisphere RTK positioning system was conducted to fix the consistency of the position for horizontal control. The system provides real time correction signals, providing centimetre level accuracy. Additional TBMs were established at various parts of the survey area to keep the rover in range with respect to the base station.

The details of reference stations OSaS-BH-TBM-01 and OSaS-BH-TBM-02 are given in **Table 1** and **Table 2**.

<b>Station Number:</b>	OSaS-BH-TBM-01	<b>Latitude:</b>	21° 48' 35.984" N
<b>Locality:</b>	Gondal, Gujarat	<b>Longitude:</b>	70° 46' 7.761" E
<b>Geodetic Datum:</b>	WGS84	<b>Northing:</b>	2412845.20 m N
<b>Projection:</b>	Universal Transverse Mercator	<b>Easting:</b>	682842.74 m E
<b>Date:</b>	17 <sup>th</sup> January 2021	<b>Elevation:</b>	112.980m above MSL
<b>Station Description:</b>	A circle with text OSaS-BH-TBM-01 is drawn with yellow paint on the walkway to the Val (valve) tower.		
<b>Access:</b>	Road to the top of the reservoir near the spillway. TBM is situated on the walkway to the Val (valve) tower. TBM-1 lies about 28m SW of the Val (valve) tower.		
<b>Sketch:</b>			
<b>Map:</b>			
			

**Table 1: Details of OSaS-BH-TBM-01**


<b>Station Number:</b>	OSaS-BH-TBM-02	<b>Latitude:</b>	21° 48' 36.158"N
<b>Locality:</b>	Gondal, Gujarat	<b>Longitude:</b>	70° 46' 08.048"E
<b>Geodetic Datum:</b>	WGS84	<b>Northing:</b>	2412850.62 m N
<b>Projection:</b>	Universal Transverse Mercator	<b>Easting:</b>	682850.92 m E
<b>Date:</b>	17 <sup>th</sup> January 2021	<b>Elevation:</b>	113.140m above MSL
<b>Station Description:</b>	A circle with text OSaS-BH-TBM-01 is drawn with yellow paint on the walkway to the Val (valve) tower.		
<b>Access:</b>	Road to top of the reservoir near spillway and TBM is situated on the walkway to the Val (valve) tower. TBM-2 lies about 18m SW of the Val (valve) tower.		
<b>Sketch:</b>			
<b>Map:</b>			
			

**Table 2: Details of OSaS-BH-TBM-02**



### 3.2 Single Beam Echo Sounder

The average speed of sound through the water column was input to the single beam echo sounder when a bar-check was performed before the start of survey operations. The following **Figure 2** shows the bar check extracts of the Odom MK III echo sounder used in SMB Ocean.



**Figure 2: Bar check calibration on board SMB Ocean**

## 4 CONCLUSIONS

Mobilisation for this project, including calibration and verification were carried out on board SMB Ocean in a safe and acceptable manner. All systems performed to the specifications throughout the length of the survey.

**Annexure - 3**  
**Previous Data - 1979**  
**Bhadar 1 Reservoir**

BHADAR IRRIGATION SCHEME								
ANNEXURE-X								
Live Storage Capacity O.S.L. R.L. : 320.00 Ft., 97.54 MT. CREST RL : 348.00 FT, 106.07 MT F.S.L., R.L. 354.00 FT, 107.89 MT TOP OF DAM RL : 371.00 FT, 113.08 MT					GATE : 35 X 6 = 29 NOS. Dead Storage : 8.00 MCFT, 0.226 M.Cum Live Storage : 6640.00 MCFT, 187.912 M.CUM HFL RL 362.00 FT 110.33 MT			
R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
318.57			97.1	0.00	0.000	0.00	0.000	
318.60			97.11	0.00	0.000	0.10	0.003	
318.64			97.12	0.00	0.000	0.20	0.006	
318.67			97.13	0.00	0.000	0.30	0.008	
318.70			97.14	0.00	0.000	0.40	0.011	
318.73			97.15	0.00	0.000	0.49	0.014	
318.77			97.16	0.00	0.000	0.59	0.017	
318.80			97.17	0.00	0.000	0.69	0.020	
318.83			97.18	0.00	0.000	0.79	0.022	
318.86			97.19	0.00	0.000	0.89	0.025	
318.90			97.2	0.00	0.000	0.99	0.028	
318.93			97.21	0.00	0.000	1.16	0.033	
318.96			97.22	0.00	0.000	1.33	0.038	
319.00			97.23	0.00	0.000	1.50	0.042	
319.03			97.24	0.00	0.000	1.67	0.047	
319.06			97.25	0.00	0.000	1.84	0.052	
319.09			97.26	0.00	0.000	2.01	0.057	
319.13			97.27	0.00	0.000	2.18	0.062	
319.16			97.28	0.00	0.000	2.34	0.066	
319.19			97.29	0.00	0.000	2.51	0.071	
319.23			97.3	0.00	0.000	2.68	0.076	
319.26			97.31	0.00	0.000	2.93	0.083	
319.29			97.32	0.00	0.000	3.19	0.090	
319.32			97.33	0.00	0.000	3.44	0.097	
319.36			97.34	0.00	0.000	3.69	0.104	
319.39			97.35	0.00	0.000	3.94	0.112	
319.42			97.36	0.00	0.000	4.19	0.119	
319.46			97.37	0.00	0.000	4.44	0.126	
319.49			97.38	0.00	0.000	4.69	0.133	
319.52			97.39	0.00	0.000	4.94	0.140	
319.55			97.4	0.00	0.000	5.19	0.147	
319.59			97.41	0.00	0.000	5.40	0.153	
319.62			97.42	0.00	0.000	5.61	0.159	
319.65			97.43	0.00	0.000	5.82	0.165	
319.69			97.44	0.00	0.000	6.02	0.171	
319.72			97.45	0.00	0.000	6.23	0.177	
319.75			97.46	0.00	0.000	6.44	0.182	
319.78			97.47	0.00	0.000	6.65	0.188	
319.82			97.48	0.00	0.000	6.86	0.194	
319.85			97.49	0.00	0.000	7.07	0.200	
319.88			97.5	0.00	0.000	7.27	0.206	
319.91			97.51	0.00	0.000	7.45	0.211	
319.95			97.52	0.00	0.000	7.63	0.216	
319.98			97.53	0.00	0.000	7.80	0.221	
320.00	320.00	97.54	97.54	0.00	0.000	8.00	0.226	O.S.L.

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
320.04			97.55	0.57	0.016	8.57	0.242	
320.07			97.56	1.13	0.032	9.13	0.258	
320.10	320.10	97.57	97.57	1.70	0.048	9.70	0.274	
320.14			97.58	2.26	0.064	10.26	0.290	
320.17			97.59	2.83	0.080	10.83	0.306	
320.20	320.20	97.60	97.60	3.40	0.096	11.40	0.322	
320.24			97.61	3.96	0.112	11.96	0.338	
320.27			97.62	4.52	0.128	12.52	0.354	
320.30	320.30	97.63	97.63	5.10	0.144	13.10	0.370	
320.34			97.64	5.65	0.160	13.65	0.386	
320.37			97.65	6.22	0.176	14.22	0.402	
320.40	320.40	97.66	97.66	6.80	0.192	14.80	0.418	
320.44			97.67	7.35	0.208	15.35	0.434	
320.47			97.68	7.91	0.224	15.91	0.450	
320.50	320.50	97.69	97.69	8.50	0.240	16.50	0.466	
320.53			97.70	9.04	0.256	17.04	0.482	
320.57			97.71	9.61	0.272	17.61	0.498	
320.60	320.60	97.72	97.72	10.20	0.288	18.20	0.514	
320.63			97.73	10.75	0.304	18.75	0.530	
320.67			97.74	11.32	0.321	19.32	0.547	
320.70	320.70	97.75	97.75	11.90	0.337	19.90	0.563	
320.73			97.76	12.47	0.353	20.47	0.579	
320.76			97.77	13.03	0.369	21.03	0.595	
320.80	320.80	97.78	97.78	13.60	0.385	21.60	0.611	
320.83			97.79	14.13	0.400	22.13	0.626	
320.86			97.80	14.66	0.415	22.66	0.641	
320.90	320.90	97.81	97.81	15.30	0.430	23.30	0.656	
320.93			97.82	15.79	0.447	23.79	0.673	
320.96			97.83	16.39	0.464	24.39	0.690	
321.00	321.00	97.84	97.84	17.00	0.481	25.00	0.707	
321.03			97.85	17.72	0.502	25.72	0.728	
321.06			97.86	18.45	0.522	26.45	0.748	
321.10	321.10	97.87	97.87	19.20	0.543	27.20	0.769	
321.12			97.88	19.91	0.564	27.91	0.790	
321.16			97.89	20.64	0.584	28.64	0.810	
321.20	321.20	97.90	97.90	21.40	0.605	29.40	0.831	
321.22			97.91	23.77	0.673	31.77	0.899	
321.26			97.92	26.17	0.741	34.17	0.967	
321.30	321.30	97.93	97.93	23.60	0.809	31.60	1.035	
321.32			97.94	27.64	0.783	35.64	1.009	
321.35			97.95	26.71	0.756	34.71	0.982	
321.40	321.40	97.96	97.96	25.80	0.730	33.80	0.956	
321.42			97.97	26.51	0.751	34.51	0.977	
321.45			97.98	27.24	0.771	35.24	0.997	
321.50	321.50	97.99	97.99	28.00	0.792	36.00	1.018	
321.52			98.00	28.97	0.820	36.97	1.046	
321.55			98.01	29.97	0.849	37.97	1.075	
321.60	321.60	98.02	98.02	31.00	0.877	39.00	1.103	
321.62			98.03	31.97	0.905	39.97	1.131	
321.65			98.04	32.97	0.934	40.97	1.160	
321.70	321.70	98.05	98.05	34.00	0.962	42.00	1.188	
321.72			98.06	34.97	0.990	42.97	1.216	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
321.75			98.07	35.97	1.019	43.97	1.245	
321.80	321.80	98.08	98.08	37.00	1.047	45.00	1.273	
321.81			98.09	37.98	1.075	45.98	1.301	
321.85			98.10	38.98	1.104	46.98	1.330	
321.90	321.90	98.11	98.11	40.00	1.132	48.00	1.358	
321.91			98.12	40.98	1.160	48.98	1.386	
321.94			98.13	41.98	1.189	49.98	1.415	
322.00	322.00	98.14	98.14	43.00	1.217	51.00	1.443	
322.01			98.15	43.87	1.242	51.87	1.468	
322.04			98.16	44.77	1.268	52.77	1.494	
322.10	322.10	98.17	98.17	45.70	1.293	53.70	1.519	
322.11			98.18	46.57	1.319	54.57	1.545	
322.14			98.19	47.47	1.344	55.47	1.570	
322.20	322.20	98.20	98.20	48.40	1.370	56.40	1.596	
322.21			98.21	49.28	1.395	57.28	1.621	
322.24			98.22	50.17	1.421	58.17	1.647	
322.30	322.30	98.23	98.23	51.10	1.446	59.10	1.672	
322.31			98.24	51.96	1.471	59.96	1.697	
322.34			98.25	52.85	1.497	60.85	1.723	
322.40	322.40	98.26	98.26	53.80	1.522	61.80	1.748	
322.44			98.27	54.66	1.548	62.66	1.774	
322.44			98.28	55.56	1.573	63.56	1.799	
322.50	322.50	98.29	98.29	56.50	1.599	64.50	1.825	
322.50			98.30	57.36	1.624	65.36	1.850	
322.54			98.31	58.26	1.650	66.26	1.876	
322.60	322.60	98.32	98.32	59.20	1.675	67.20	1.901	
322.60			98.33	60.06	1.701	68.06	1.927	
322.63			98.34	60.96	1.726	68.96	1.952	
322.70	322.70	98.35	98.35	61.90	1.752	69.90	1.978	
322.70			98.36	62.77	1.777	70.77	2.003	
322.73			98.37	63.66	1.803	71.66	2.029	
322.80	322.80	98.38	98.38	64.60	1.828	72.60	2.054	
322.80			98.39	65.45	1.853	73.45	2.079	
322.83			98.40	66.34	1.879	74.34	2.105	
322.90	322.90	98.41	98.41	67.30	1.904	75.30	2.130	
322.90			98.42	68.15	1.930	76.15	2.156	
322.93			98.43	69.05	1.955	77.05	2.181	
323.00	323.00	98.44	98.44	70.00	1.981	78.00	2.207	
322.99			98.45	70.65	2.001	78.65	2.227	
323.03			98.46	71.35	2.020	79.35	2.246	
323.06		98.47	98.47	72.04	2.040	80.04	2.266	
323.10	323.10	98.48	98.48	72.80	2.060	80.80	2.286	
323.13			98.49	73.68	2.086	81.68	2.312	
323.16			98.50	74.61	2.113	82.61	2.339	
323.20	323.20	98.51	98.51	75.60	2.139	83.60	2.365	
323.22			98.52	76.48	2.166	84.48	2.392	
323.26			98.53	77.42	2.192	85.42	2.418	
323.30	323.30	98.54	98.54	78.40	2.219	86.40	2.445	
323.32			98.55	79.29	2.245	87.29	2.471	
323.36			98.56	80.22	2.272	88.22	2.498	
323.40	323.40	98.57	98.57	81.20	2.298	89.20	2.524	
323.42			98.58	82.08	2.324	90.08	2.550	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
323.45			98.59	83.01	2.351	91.01	2.577	
323.50	323.50	98.60	98.60	84.00	2.377	92.00	2.603	
323.52			98.61	84.74	2.400	92.74	2.626	
323.55			98.62	85.54	2.422	93.54	2.648	
323.60	323.60	98.63	98.63	86.40	2.445	94.40	2.671	
323.62			98.64	87.34	2.473	95.34	2.699	
323.65			98.65	88.35	2.502	96.35	2.728	
323.70	323.70	98.66	98.66	89.60	2.530	97.60	2.756	
323.72			98.67	90.35	2.558	98.35	2.784	
323.75			98.68	91.35	2.587	99.35	2.813	
323.80	323.80	98.69	98.69	92.40	2.615	100.40	2.841	
323.81			98.70	93.28	2.641	101.28	2.867	
323.85			98.71	94.21	2.668	102.21	2.894	
323.90	323.90	98.72	98.72	95.20	2.694	103.20	2.920	
323.91			98.73	96.07	2.720	104.07	2.946	
323.95			98.74	97.00	2.747	105.00	2.973	
324.00	324.00	98.72	98.75	98.00	2.773	106.00	2.999	
324.01			98.76	99.20	2.809	107.20	3.035	
324.04			98.77	100.47	2.845	108.47	3.071	
324.10	324.10	98.78	98.78	101.80	2.881	109.80	3.107	
324.11			98.79	103.00	2.917	111.00	3.143	
324.14			98.80	104.26	2.952	112.26	3.178	
324.20	324.20	98.81	98.81	105.60	2.988	113.60	3.214	
324.21			98.82	106.79	3.024	114.79	3.250	
324.24			98.83	108.06	3.060	116.06	3.286	
324.30	324.30	98.84	98.84	109.40	3.096	117.40	3.322	
324.31			98.85	110.59	3.132	118.59	3.358	
324.34			98.86	111.85	3.167	119.85	3.393	
324.40	324.40	98.87	98.87	113.20	3.203	121.20	3.429	
324.41			98.88	114.38	3.239	122.38	3.465	
324.44			98.89	115.66	3.275	123.66	3.501	
324.50	324.50	98.90	98.90	117.00	3.311	125.00	3.537	
324.50			98.91	118.46	3.354	126.46	3.580	
324.54			98.92	119.99	3.398	127.99	3.624	
324.60	324.60	98.93	98.93	121.60	3.441	129.60	3.667	
324.60			98.94	123.05	3.484	131.05	3.710	
324.64			98.95	124.58	3.528	132.58	3.754	
324.70	324.70	98.96	98.96	126.20	3.571	134.20	3.797	
324.70			98.97	127.65	3.615	135.65	3.841	
324.73			98.98	129.19	3.658	137.19	3.884	
324.80	324.80	98.99	98.99	130.80	3.702	138.80	3.928	
324.80			99.00	132.27	3.745	140.27	3.971	
324.83			99.01	133.80	3.789	141.80	4.015	
324.90	324.90	99.02	99.02	135.40	3.832	143.40	4.058	
324.90			99.03	136.47	3.864	144.47	4.090	
324.93			99.04	137.61	3.897	145.61	4.123	
324.96		99.05	99.05	138.75	3.929	146.75	4.155	
325.00	325.00	99.06	99.06	140.00	3.962	148.00	4.188	
325.03			99.07	141.68	4.012	149.68	4.238	
325.06			99.08	143.45	4.062	151.45	4.288	
325.10	325.10	99.09	99.09	145.30	4.112	153.30	4.338	
325.13			99.10	146.98	4.162	154.98	4.388	

R.L. in Ft	R.L. as per old Area capacity table		Live				Total (Live+Dead)		Remarks
	Ft	Mt	R.L. in	Capacity	Capacity	Capacity	Capacity		
			Mt	in Mcft	in M.Cum	in Mcft	in M.Cum		
325.16			99.11	148.75	4.212	156.75	4.438		
325.20	325.20	99.12	99.12	150.60	4.262	158.60	4.488		
325.23			99.13	152.28	4.312	160.28	4.538		
325.26			99.14	154.04	4.362	162.04	4.588		
325.30	325.30	99.15	99.15	155.90	4.412	163.90	4.638		
325.32			99.16	157.57	4.462	165.57	4.688		
325.36			99.17	159.34	4.512	167.34	4.738		
325.40	325.40	99.18	99.18	161.20	4.562	169.20	4.788		
325.42			99.19	162.87	4.612	170.87	4.838		
325.46			99.20	164.64	4.662	172.64	4.888		
325.50	325.50	99.21	99.21	166.50	4.712	174.50	4.938		
325.52			99.22	168.17	4.762	176.17	4.988		
325.55			99.23	169.93	4.812	177.93	5.038		
325.60	325.60	99.24	99.24	171.80	4.862	179.80	5.088		
325.62			99.25	174.12	4.931	182.12	5.157		
325.65			99.26	176.55	4.999	184.55	5.225		
325.70	325.70	99.27	99.27	177.10	5.068	185.10	5.294		
325.72			99.28	180.08	5.099	188.08	5.325		
325.75			99.29	181.19	5.131	189.19	5.357		
325.80	325.80	99.30	99.30	182.40	5.162	190.40	5.388		
325.82			99.31	184.06	5.212	192.06	5.438		
325.85			99.32	185.83	5.262	193.83	5.488		
325.90	325.90	99.33	99.33	187.70	5.312	195.70	5.538		
325.91			99.34	189.36	5.362	197.36	5.588		
325.95			99.35	191.12	5.412	199.12	5.638		
326.00	326.00	99.36	99.36	193.00	5.462	201.00	5.688		
326.01			99.37	194.65	5.512	202.65	5.738		
326.05			99.38	196.42	5.562	204.42	5.788		
326.10	326.10	99.39	99.39	198.30	5.612	206.30	5.838		
326.11			99.40	199.95	5.662	207.95	5.888		
326.14			99.41	201.72	5.712	209.72	5.938		
326.20	326.20	99.42	99.42	198.60	5.762	206.60	5.988		
326.21			99.43	205.25	5.812	213.25	6.038		
326.24			99.44	207.01	5.862	215.01	6.088		
326.30	326.30	99.45	99.45	208.90	5.912	216.90	6.138		
326.31			99.46	210.55	5.962	218.55	6.188		
326.34			99.47	212.31	6.012	220.31	6.238		
326.40	326.40	99.48	99.48	214.20	6.062	222.20	6.288		
326.41			99.49	215.41	6.100	223.41	6.326		
326.44			99.50	216.74	6.137	224.74	6.363		
326.47		99.51	99.51	218.07	6.175	226.07	6.401		
326.50	326.50	99.52	99.52	219.50	6.212	227.50	6.438		
326.54			99.53	221.14	6.262	229.14	6.488		
326.57			99.54	222.91	6.312	230.91	6.538		
326.60	326.60	99.55	99.55	224.80	6.362	232.80	6.588		
326.64			99.56	226.44	6.412	234.44	6.638		
326.67			99.57	228.20	6.462	236.20	6.688		
326.70	326.70	99.58	99.58	230.10	6.512	238.10	6.738		
326.70			99.59	231.75	6.587	239.75	6.813		
326.80	326.80	99.60	99.60	235.40	6.662	243.40	6.888		
326.80			99.61	236.57	6.699	244.57	6.925		
326.83			99.62	237.90	6.737	245.90	6.963		

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
326.87			99.63	239.28	6.774	247.28	7.000	
326.90	326.90	99.64	99.64	240.70	6.812	248.70	7.038	
326.93			99.65	242.33	6.862	250.33	7.088	
326.96			99.66	244.09	6.912	252.09	7.138	
327.00	327.00	99.67	99.67	246.00	6.962	254.00	7.188	
327.03			99.68	248.32	7.032	256.32	7.258	
327.06			99.69	250.78	7.101	258.78	7.327	
327.10	327.10	99.70	99.70	253.40	7.171	261.40	7.397	
327.13			99.71	255.71	7.241	263.71	7.467	
327.16			99.72	258.19	7.311	266.19	7.537	
327.20	327.20	99.73	99.73	260.80	7.381	268.80	7.607	
327.23			99.74	263.12	7.451	271.12	7.677	
327.26			99.75	265.58	7.520	273.58	7.746	
327.30	327.30	99.76	99.76	268.20	7.590	276.20	7.816	
327.33			99.77	270.84	7.669	278.84	7.895	
327.36			99.78	273.64	7.749	281.64	7.975	
327.40	327.40	99.79	99.79	275.60	7.828	283.60	8.054	
327.42			99.80	278.57	7.888	286.57	8.114	
327.46			99.81	280.70	7.949	288.70	8.175	
327.50	327.50	99.82	99.82	283.00	8.009	291.00	8.235	
327.52			99.83	285.30	8.079	293.30	8.305	
327.56			99.84	287.76	8.148	295.76	8.374	
327.60	327.60	99.85	99.85	290.40	8.218	298.40	8.444	
327.62			99.86	292.69	8.288	300.69	8.514	
327.65			99.87	295.16	8.358	303.16	8.584	
327.70	327.70	99.88	99.88	297.80	8.428	305.80	8.654	
327.72			99.89	300.09	8.498	308.09	8.724	
327.75			99.90	302.55	8.567	310.55	8.793	
327.80	327.80	99.91	99.91	305.20	8.637	313.20	8.863	
327.82			99.92	307.47	8.707	315.47	8.933	
327.85			99.93	309.93	8.776	317.93	9.002	
327.90	327.90	99.94	99.94	312.60	8.846	320.60	9.072	
327.92			99.95	314.87	8.916	322.87	9.142	
327.95			99.96	317.34	8.986	325.34	9.212	
328.00	328.00	99.97	99.97	329.00	9.056	337.00	9.282	
328.01			99.98	321.81	9.113	329.81	9.339	
328.05			99.99	323.81	9.169	331.81	9.395	
328.10	328.10	100.00	100.00	326.00	9.226	334.00	9.452	
328.11			100.01	327.80	9.282	335.80	9.508	
328.15			100.02	329.79	9.339	337.79	9.565	
328.20	328.20	100.03	100.03	332.00	9.395	340.00	9.621	
328.21			100.04	333.78	9.452	341.78	9.678	
328.24			100.05	335.78	9.508	343.78	9.734	
328.30	328.30	100.06	100.06	338.00	9.565	346.00	9.791	
328.31			100.07	339.79	9.622	347.79	9.848	
328.34			100.08	341.79	9.678	349.79	9.904	
328.40	328.40	100.09	100.09	344.00	9.735	352.00	9.961	
328.41			100.10	345.30	9.778	353.30	10.004	
328.44			100.11	346.80	9.820	354.80	10.046	
328.47		100.12	100.12	348.31	9.863	356.31	10.089	
328.50	328.50	100.13	100.13	350.00	9.905	358.00	10.131	
328.54			100.14	351.79	9.962	359.79	10.188	



R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
328.57			100.15	353.79	10.018	361.79	10.244	
328.60	328.60	100.16	100.16	356.00	10.075	364.00	10.301	
328.64			100.17	357.80	10.132	365.80	10.358	
328.67			100.18	359.80	10.188	367.80	10.414	
328.70	328.70	100.19	100.19	362.00	10.245	370.00	10.471	
328.74			100.20	363.79	10.301	371.79	10.527	
328.77			100.21	365.78	10.358	373.78	10.584	
328.80	328.80	100.22	100.22	368.00	10.414	376.00	10.640	
328.83			100.23	369.77	10.471	377.77	10.697	
328.87			100.24	371.77	10.527	379.77	10.753	
328.90	328.90	100.25	100.25	374.00	10.584	382.00	10.810	
328.93			100.26	375.77	10.641	383.77	10.867	
328.97			100.27	377.77	10.697	385.77	10.923	
329.00	329.00	100.28	100.28	380.00	10.754	388.00	10.980	
329.03			100.29	382.01	10.817	390.01	11.043	
329.06			100.30	384.25	10.881	392.25	11.107	
329.10	329.10	100.31	100.31	386.70	10.944	394.70	11.170	
329.13			100.32	388.71	11.007	396.71	11.233	
329.16			100.33	390.93	11.070	398.93	11.296	
329.20	329.20	100.34	100.34	393.40	11.133	401.40	11.359	
329.23			100.35	395.39	11.196	403.39	11.422	
329.26			100.36	397.63	11.260	405.63	11.486	
329.30	329.30	100.37	100.37	400.10	11.323	408.10	11.549	
329.33			100.38	402.09	11.386	410.09	11.612	
329.36			100.39	404.32	11.449	412.32	11.675	
329.40	329.40	100.40	100.40	406.80	11.512	414.80	11.738	
329.43			100.41	408.81	11.576	416.81	11.802	
329.46			100.42	411.09	11.641	419.09	11.867	
329.50	329.50	100.43	100.43	413.50	11.705	421.50	11.931	
329.52			100.44	415.56	11.767	423.56	11.993	
329.56			100.45	417.76	11.830	425.76	12.056	
329.60	329.60	100.46	100.46	420.20	11.892	428.20	12.118	
329.62			100.47	422.19	11.955	430.19	12.181	
329.65			100.48	424.41	12.018	432.41	12.244	
329.70	329.70	100.49	100.49	426.90	12.081	434.90	12.307	
329.72			100.50	428.86	12.144	436.86	12.370	
329.75			100.51	431.09	12.207	439.09	12.433	
329.80	329.80	100.52	100.52	433.60	12.270	441.60	12.496	
329.82			100.53	435.55	12.333	443.55	12.559	
329.85			100.54	437.78	12.397	445.78	12.623	
329.90	329.90	100.55	100.55	440.30	12.460	448.30	12.686	
329.92			100.56	442.26	12.523	450.26	12.749	
329.95			100.57	444.49	12.587	452.49	12.813	
330.00	330.00	100.58	100.58	447.00	12.650	455.00	12.876	
330.02			100.59	449.50	12.728	457.50	12.954	
330.05			100.60	452.26	12.807	460.26	13.033	
330.10	330.10	100.61	100.61	453.30	12.885	461.30	13.111	
330.11			100.62	457.80	12.963	465.80	13.189	
330.15			100.63	460.56	13.042	468.56	13.268	
330.20	330.20	100.64	100.64	463.60	13.120	471.60	13.346	
330.21			100.65	466.09	13.198	474.09	13.424	
330.25			100.66	468.86	13.277	476.86	13.503	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
330.30	330.30	100.67	100.67	471.90	13.355	479.90	13.581	
330.31			100.68	474.39	13.433	482.39	13.659	
330.34			100.69	477.16	13.512	485.16	13.738	
330.40	330.40	100.70	100.70	480.20	13.590	488.20	13.816	
330.41			100.71	482.00	13.649	490.00	13.875	
330.44			100.72	484.07	13.707	492.07	13.933	
330.47		100.73	100.73	486.15	13.766	494.15	13.992	
330.50	330.50	100.74	100.74	488.50	13.824	496.50	14.050	
330.54			100.75	490.96	13.902	498.96	14.128	
330.57			100.76	493.72	13.981	501.72	14.207	
330.60	330.60	100.77	100.77	496.80	14.059	504.80	14.285	
330.64			100.78	499.26	14.137	507.26	14.363	
330.67			100.79	502.02	14.216	510.02	14.442	
330.70	330.70	100.80	100.80	505.10	14.294	513.10	14.520	
330.74			100.81	507.55	14.372	515.55	14.598	
330.77			100.82	510.32	14.451	518.32	14.677	
330.80	330.80	100.83	100.83	513.40	14.529	521.40	14.755	
330.84			100.84	515.85	14.607	523.85	14.833	
330.87			100.85	518.62	14.686	526.62	14.912	
330.90	330.90	100.86	100.86	521.70	14.764	529.70	14.990	
330.93			100.87	524.15	14.842	532.15	15.068	
330.97			100.88	526.92	14.921	534.92	15.147	
331.00	331.00	100.89	100.89	530.00	14.999	538.00	15.225	
331.03			100.90	532.62	15.082	540.62	15.308	
331.07			100.91	535.55	15.165	543.55	15.391	
331.10	331.10	100.92	100.92	538.30	15.248	546.30	15.474	
331.13			100.93	541.08	15.322	549.08	15.548	
331.16			100.94	543.68	15.395	551.68	15.621	
331.20	331.20	100.95	100.95	546.60	15.469	554.60	15.695	
331.23			100.96	549.05	15.547	557.05	15.773	
331.26			100.97	551.82	15.626	559.82	15.852	
331.30	331.30	100.98	100.98	554.90	15.704	562.90	15.930	
331.33			100.99	557.34	15.782	565.34	16.008	
331.36			101.00	560.09	15.860	568.09	16.086	
331.40	331.40	101.01	101.01	563.20	15.938	571.20	16.164	
331.43			101.02	565.65	16.017	573.65	16.243	
331.46			101.03	568.45	16.097	576.45	16.323	
331.50	331.50	101.04	101.04	571.50	16.176	579.50	16.402	
331.52			101.05	574.85	16.278	582.85	16.504	
331.56			101.06	578.45	16.380	586.45	16.606	
331.60	331.60	101.07	101.07	582.40	16.482	590.40	16.708	
331.62			101.08	585.68	16.585	593.68	16.811	
331.66			101.09	589.31	16.687	597.31	16.913	
331.70	331.70	101.10	101.10	593.30	16.790	601.30	17.016	
331.72			101.11	596.57	16.893	604.57	17.119	
331.75			101.12	600.21	16.996	608.21	17.222	
331.80	331.80	101.13	101.13	604.20	17.099	612.20	17.325	
331.82			101.14	610.97	17.301	618.97	17.527	
331.85			101.15	618.09	17.502	626.09	17.728	
331.90	331.90	101.16	101.16	615.10	17.704	623.10	17.930	
331.92			101.17	625.35	17.708	633.35	17.934	
331.95			101.18	625.49	17.712	633.49	17.938	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
332.00	332.00	101.19	101.19	626.00	17.716	634.00	17.942	
332.02			101.20	629.30	17.820	637.30	18.046	
332.05			101.21	632.96	17.923	640.96	18.149	
332.10	332.10	101.22	101.22	637.60	18.027	645.60	18.253	
332.12			101.23	640.68	18.142	648.68	18.368	
332.15			101.24	644.74	18.257	652.74	18.483	
332.20	332.20	101.25	101.25	649.20	18.372	657.20	18.598	
332.21			101.26	652.67	18.482	660.67	18.708	
332.25			101.27	656.55	18.591	664.55	18.817	
332.30	332.30	101.28	101.28	660.80	18.701	668.80	18.927	
332.31			101.29	664.28	18.810	672.28	19.036	
332.35			101.30	668.14	18.920	676.14	19.146	
332.40	332.40	101.31	101.31	672.40	19.029	680.40	19.255	
332.41			101.32	674.90	19.111	682.90	19.337	
332.44			101.33	677.79	19.193	685.79	19.419	
332.48		101.34	101.34	680.70	19.275	688.70	19.501	
332.50	332.50	101.35	101.35	684.00	19.357	692.00	19.583	
332.54			101.36	687.52	19.468	695.52	19.694	
332.57			101.37	691.45	19.580	699.45	19.806	
332.60	332.60	101.38	101.38	695.80	19.691	703.80	19.917	
332.64			101.39	699.31	19.802	707.31	20.028	
332.67			101.40	703.24	19.914	711.24	20.140	
332.70	332.70	101.41	101.41	707.60	20.025	715.60	20.251	
332.74			101.42	711.11	20.136	719.11	20.362	
332.77			101.43	715.04	20.248	723.04	20.474	
332.80	332.80	101.44	101.44	719.40	20.359	727.40	20.585	
332.84			101.45	722.90	20.470	730.90	20.696	
332.87			101.46	726.83	20.582	734.83	20.808	
332.90	332.90	101.47	101.47	731.20	20.693	739.20	20.919	
332.94			101.48	734.70	20.804	742.70	21.030	
332.97			101.49	738.63	20.916	746.63	21.142	
333.00	333.00	101.50	101.50	743.00	21.027	751.00	21.253	
333.03			101.51	747.46	21.166	755.46	21.392	
333.07			101.52	752.36	21.304	760.36	21.530	
333.10	333.10	101.53	101.53	757.70	21.443	765.70	21.669	
333.13			101.54	762.15	21.582	770.15	21.808	
333.17			101.55	767.05	21.720	775.05	21.946	
333.20	333.20	101.56	101.56	772.40	21.859	780.40	22.085	
333.23			101.57	776.84	21.998	784.84	22.224	
333.26			101.58	781.74	22.136	789.74	22.362	
333.30	333.30	101.59	101.59	787.10	22.275	795.10	22.501	
333.33			101.60	791.53	22.414	799.53	22.640	
333.36			101.61	796.43	22.552	804.43	22.778	
333.40	333.40	101.62	101.62	801.80	22.691	809.80	22.917	
333.43			101.63	806.22	22.830	814.22	23.056	
333.46			101.64	811.12	22.968	819.12	23.194	
333.50	333.50	101.65	101.65	816.50	23.107	824.50	23.333	
333.53			101.66	820.91	23.246	828.91	23.472	
333.56			101.67	825.81	23.384	833.81	23.610	
333.60	333.60	101.68	101.68	831.20	23.523	839.20	23.749	
333.62			101.69	835.93	23.671	843.93	23.897	
333.66			101.70	841.16	23.819	849.16	24.045	

R.L. as per old Area capacity table		Live				Total (Live+Dead)		Remarks
R.L. in		R.L. in	Capacity	Capacity	Capacity	Capacity		
Ft	Ft	Mt	in Mcft	in M.Cum	in Mcft	in M.Cum		
333.70	333.70	101.71	101.71	845.90	23.967	853.90	24.193	
333.72			101.72	850.95	24.096	858.95	24.322	
333.76			101.73	855.52	24.226	863.52	24.452	
333.80	333.80	101.74	101.74	860.60	24.355	868.60	24.581	
333.82			101.75	864.99	24.494	872.99	24.720	
333.85			101.76	869.88	24.632	877.88	24.858	
333.90	333.90	101.77	101.77	875.30	24.771	883.30	24.997	
333.92			101.78	879.68	24.910	887.68	25.136	
333.95			101.79	884.57	25.048	892.57	25.274	
334.00	334.00	101.80	101.80	890.00	25.187	898.00	25.413	
334.02			101.81	894.20	25.321	902.20	25.547	
334.05			101.82	898.93	25.455	906.93	25.681	
334.10	334.10	101.83	101.83	904.20	25.589	912.20	25.815	
334.12			101.84	908.40	25.723	916.40	25.949	
334.15			101.85	913.13	25.857	921.13	26.083	
334.20	334.20	101.86	101.86	918.40	25.991	926.40	26.217	
334.22			101.87	922.58	26.125	930.58	26.351	
334.25			101.88	927.30	26.258	935.30	26.484	
334.30	334.30	101.89	101.89	932.60	26.392	940.60	26.618	
334.31			101.90	936.76	26.526	944.76	26.752	
334.35			101.91	941.49	26.660	949.49	26.886	
334.40	334.40	101.92	101.92	946.80	26.794	954.80	27.020	
334.41			101.93	949.78	26.895	957.78	27.121	
334.44			101.94	953.33	26.995	961.33	27.221	
334.48		101.95	101.95	956.90	27.096	964.90	27.322	
334.50	334.50	101.96	101.96	961.00	27.196	969.00	27.422	
334.54			101.97	965.15	27.330	973.15	27.556	
334.58			101.98	969.88	27.464	977.88	27.690	
334.60	334.60	101.99	101.99	975.20	27.598	983.20	27.824	
334.64			102.00	979.35	27.732	987.35	27.958	
334.67			102.01	984.08	27.866	992.08	28.092	
334.70	334.70	102.02	102.02	989.40	28.000	997.40	28.226	
334.74			102.03	993.54	28.134	1001.54	28.360	
334.77			102.04	998.27	28.268	1006.27	28.494	
334.80	334.80	102.05	102.05	1003.60	28.402	1011.60	28.628	
334.84			102.06	1007.74	28.536	1015.74	28.762	
334.87			102.07	1012.47	28.670	1020.47	28.896	
334.90	334.90	102.08	102.08	1017.80	28.804	1025.80	29.030	
334.94			102.09	1021.92	28.938	1029.92	29.164	
334.97			102.10	1026.64	29.071	1034.64	29.297	
335.00	335.00	102.11	102.11	1032.00	29.205	1040.00	29.431	
335.04			102.12	1035.84	29.332	1043.84	29.558	
335.07			102.13	1040.31	29.458	1048.31	29.684	
335.10	335.10	102.14	102.14	1045.40	29.585	1053.40	29.811	
335.13			102.15	1049.25	29.711	1057.25	29.937	
335.17			102.16	1053.71	29.838	1061.71	30.064	
335.20	335.20	102.17	102.17	1058.80	29.964	1066.80	30.190	
335.23			102.18	1062.63	30.090	1070.63	30.316	
335.26			102.19	1067.09	30.217	1075.09	30.443	
335.30	335.30	102.20	102.20	1072.20	30.343	1080.20	30.569	
335.33			102.21	1076.01	30.469	1084.01	30.695	
335.36			102.22	1080.48	30.596	1088.48	30.822	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
335.40	335.40	102.23	102.23	1085.60	30.722	1093.60	30.948	
335.43			102.24	1089.41	30.849	1097.41	31.075	
335.46			102.25	1093.88	30.975	1101.88	31.201	
335.50	335.50	102.26	102.26	1099.00	31.102	1107.00	31.328	
335.53			102.27	1102.82	31.228	1110.82	31.454	
335.56			102.28	1107.28	31.355	1115.28	31.581	
335.60	335.60	102.29	102.29	1112.40	31.481	1120.40	31.707	
335.63			102.30	1116.20	31.607	1124.20	31.833	
335.66			102.31	1120.66	31.734	1128.66	31.960	
335.70	335.70	102.32	102.32	1125.80	31.860	1133.80	32.086	
335.72			102.33	1129.59	31.986	1137.59	32.212	
335.76			102.34	1134.05	32.113	1142.05	32.339	
335.80	335.80	102.35	102.35	1139.20	32.239	1147.20	32.465	
335.82			102.36	1142.97	32.365	1150.97	32.591	
335.86			102.37	1147.43	32.492	1155.43	32.718	
335.90	335.90	102.38	102.38	1152.60	32.618	1160.60	32.844	
335.92			102.39	1156.37	32.745	1164.37	32.971	
335.95			102.40	1160.84	32.871	1168.84	33.097	
336.00	336.00	102.41	102.41	1166.00	32.998	1174.00	33.224	
336.02			102.42	1170.27	33.138	1178.27	33.364	
336.05			102.43	1175.23	33.279	1183.23	33.505	
336.10	336.10	102.44	102.44	1180.90	33.419	1188.90	33.645	
336.12			102.45	1185.15	33.560	1193.15	33.786	
336.15			102.46	1190.12	33.700	1198.12	33.926	
336.20	336.20	102.47	102.47	1195.80	33.841	1203.80	34.067	
336.22			102.48	1200.05	33.982	1208.05	34.208	
336.25			102.49	1205.02	34.122	1213.02	34.348	
336.30	336.30	102.50	102.50	1210.70	34.263	1218.70	34.489	
336.31			102.51	1214.94	34.403	1222.94	34.629	
336.35			102.52	1219.90	34.544	1227.90	34.770	
336.40	336.40	102.53	102.53	1225.60	34.684	1233.60	34.910	
336.41			102.54	1229.82	34.825	1237.82	35.051	
336.45			102.55	1234.79	34.965	1242.79	35.191	
336.50	336.50	102.56	102.56	1240.50	35.106	1248.50	35.332	
336.51			102.57	1244.72	35.247	1252.72	35.473	
336.54			102.58	1249.69	35.387	1257.69	35.613	
336.60	336.60	102.59	102.59	1255.40	35.528	1263.40	35.754	
336.61			102.60	1258.38	35.633	1266.38	35.859	
336.64			102.61	1262.10	35.739	1270.10	35.965	
336.68		102.62	102.62	1265.83	35.844	1273.83	36.070	
336.70	336.70	102.63	102.63	1270.30	35.949	1278.30	36.175	
336.74			102.64	1274.49	36.090	1282.49	36.316	
336.77			102.65	1279.46	36.230	1287.46	36.456	
336.80	336.80	102.66	102.66	1285.20	36.371	1293.20	36.597	
336.84			102.67	1289.40	36.512	1297.40	36.738	
336.87			102.68	1294.36	36.652	1302.36	36.878	
336.90	336.90	102.69	102.69	1300.10	36.793	1308.10	37.019	
336.94			102.70	1304.29	36.933	1312.29	37.159	
336.97			102.71	1309.24	37.074	1317.24	37.300	
337.00	337.00	102.72	102.72	1315.00	37.214	1323.00	37.440	
337.04			102.73	1319.20	37.356	1327.20	37.582	
337.07			102.74	1324.21	37.497	1332.21	37.723	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
337.10	337.10	102.75	102.75	1330.00	37.639	1338.00	37.865	
337.14			102.76	1334.20	37.780	1342.20	38.006	
337.17			102.77	1339.19	37.922	1347.19	38.148	
337.20	337.20	102.78	102.78	1345.00	38.063	1353.00	38.289	
337.23			102.79	1349.19	38.205	1357.19	38.431	
337.27			102.80	1354.19	38.346	1362.19	38.572	
337.30	337.30	102.81	102.81	1360.00	38.488	1368.00	38.714	
337.33			102.82	1364.18	38.629	1372.18	38.855	
337.36			102.83	1369.17	38.771	1377.17	38.997	
337.40	337.40	102.84	102.84	1375.00	38.912	1383.00	39.138	
337.43			102.85	1379.17	39.054	1387.17	39.280	
337.46			102.86	1384.17	39.195	1392.17	39.421	
337.50	337.50	102.87	102.87	1390.00	39.337	1398.00	39.563	
337.53			102.88	1394.71	39.494	1402.71	39.720	
337.56			102.89	1400.24	39.650	1408.24	39.876	
337.60	337.60	102.90	102.90	1406.00	39.807	1414.00	40.033	
337.63			102.91	1411.29	39.963	1419.29	40.189	
337.66			102.92	1416.81	40.120	1424.81	40.346	
337.70	337.70	102.93	102.93	1423.00	40.276	1431.00	40.502	
337.73			102.94	1427.87	40.433	1435.87	40.659	
337.76			102.95	1433.40	40.589	1441.40	40.815	
337.80	337.80	102.96	102.96	1439.00	40.746	1447.00	40.972	
337.82			102.97	1444.46	40.903	1452.46	41.129	
337.86			102.98	1450.00	41.059	1458.00	41.285	
337.90	337.90	102.99	102.99	1456.00	41.216	1464.00	41.442	
337.92			103.00	1461.06	41.373	1469.06	41.599	
337.96			103.01	1466.59	41.529	1474.59	41.755	
338.00	338.00	103.02	103.02	1473.00	41.686	1481.00	41.912	
338.02			103.03	1479.03	41.881	1487.03	42.107	
338.05			103.04	1485.92	42.077	1493.92	42.303	
338.10	338.10	103.05	103.05	1493.70	42.272	1501.70	42.498	
338.12			103.06	1499.71	42.467	1507.71	42.693	
338.15			103.07	1506.59	42.662	1514.59	42.888	
338.20	338.20	103.08	103.08	1513.18	42.857	1521.18	43.083	
338.22			103.09	1520.38	43.052	1528.38	43.278	
338.25			103.10	1527.28	43.248	1535.28	43.474	
338.30	338.30	103.11	103.11	1535.10	43.443	1543.10	43.669	
338.32			103.12	1541.07	43.638	1549.07	43.864	
338.35			103.13	1547.97	43.834	1555.97	44.060	
338.40	338.40	103.14	103.14	1555.80	44.029	1563.80	44.255	
338.41			103.15	1561.77	44.224	1569.77	44.450	
338.45			103.16	1568.67	44.420	1576.67	44.646	
338.50	338.50	103.17	103.17	1576.50	44.615	1584.50	44.841	
338.51			103.18	1582.46	44.810	1590.46	45.036	
338.55			103.19	1589.36	45.006	1597.36	45.232	
338.60	338.60	103.20	103.20	1597.20	45.201	1605.20	45.427	
338.61			103.21	1603.14	45.396	1611.14	45.622	
338.64			103.22	1610.03	45.591	1618.03	45.817	
338.70	338.70	103.23	103.23	1617.90	45.786	1625.90	46.012	
338.71			103.24	1623.82	45.981	1631.82	46.207	
338.74			103.25	1630.71	46.177	1638.71	46.403	
338.80	338.80	103.26	103.26	1638.60	46.372	1646.60	46.598	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
338.81			103.27	1642.79	46.519	1650.79	46.745	
338.84			103.28	1647.97	46.665	1655.97	46.891	
338.87		103.29	103.29	1653.17	46.812	1661.17	47.038	
338.90	338.90	103.30	103.30	1659.30	46.958	1667.30	47.184	
338.94			103.31	1665.20	47.153	1673.20	47.379	
338.97			103.32	1672.10	47.349	1680.10	47.575	
339.00	339.00	103.33	103.33	1680.00	47.544	1688.00	47.770	
339.04			103.34	1685.99	47.742	1693.99	47.968	
339.07			103.35	1692.99	47.940	1700.99	48.166	
339.10	339.10	103.36	103.36	1701.00	48.138	1709.00	48.364	
339.14			103.37	1706.98	48.336	1714.98	48.562	
339.17			103.38	1713.99	48.535	1721.99	48.761	
339.20	339.20	103.39	103.39	1722.00	48.733	1730.00	48.959	
339.23			103.40	1727.98	48.931	1735.98	49.157	
339.27			103.41	1734.97	49.129	1742.97	49.355	
339.30	339.30	103.42	103.42	1743.00	49.327	1751.00	49.553	
339.33			103.43	1748.96	49.525	1756.96	49.751	
339.37			103.44	1755.95	49.723	1763.95	49.949	
339.40	339.40	103.45	103.45	1764.00	49.921	1772.00	50.147	
339.43			103.46	1769.94	50.119	1777.94	50.345	
339.46			103.47	1776.93	50.317	1784.93	50.543	
339.50	339.50	103.48	103.48	1785.00	50.515	1793.00	50.741	
339.53			103.49	1792.05	50.745	1800.05	50.971	
339.56			103.50	1800.19	50.976	1808.19	51.202	
339.60	339.60	103.51	103.51	1809.40	51.206	1817.40	51.432	
339.63			103.52	1816.45	51.436	1824.45	51.662	
339.66			103.53	1824.57	51.666	1832.57	51.892	
339.70	339.70	103.54	103.54	1833.80	51.896	1841.80	52.122	
339.73			103.55	1840.82	52.126	1848.82	52.352	
339.76			103.56	1848.96	52.357	1856.96	52.583	
339.80	339.80	103.57	103.57	1858.20	52.587	1866.20	52.813	
339.83			103.58	1865.21	52.817	1873.21	53.043	
339.86			103.59	1873.34	53.047	1881.34	53.273	
339.90	339.90	103.60	103.60	1882.60	53.277	1890.60	53.503	
339.92			103.61	1889.59	53.507	1897.59	53.733	
339.96			103.62	1897.73	53.738	1905.73	53.964	
340.00	340.00	103.63	103.63	1907.00	53.968	1915.00	54.194	
340.02			103.64	1914.38	54.209	1922.38	54.435	
340.05			103.65	1922.91	54.451	1930.91	54.677	
340.10	340.10	103.66	103.66	1932.50	54.692	1940.50	54.918	
340.12			103.67	1939.89	54.932	1947.89	55.158	
340.15			103.68	1948.36	55.171	1956.36	55.397	
340.20	340.20	103.69	103.69	1958.00	55.411	1966.00	55.637	
340.22			103.70	1965.34	55.652	1973.34	55.878	
340.25			103.71	1973.87	55.894	1981.87	56.120	
340.30	340.30	103.72	103.72	1985.50	56.135	1993.50	56.361	
340.32			103.73	1990.86	56.375	1998.86	56.601	
340.35			103.74	1999.34	56.615	2007.34	56.841	
340.40	340.40	103.75	103.75	2009.00	56.855	2017.00	57.081	
340.42			103.76	2016.30	57.095	2024.30	57.321	
340.45			103.77	2024.79	57.336	2032.79	57.562	
340.50	340.50	103.78	103.78	2034.50	57.576	2042.50	57.802	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
340.51			103.79	2041.78	57.817	2049.78	58.043	
340.55			103.80	2050.28	58.057	2058.28	58.283	
340.60	340.60	103.81	103.81	2060.00	58.298	2068.00	58.524	
340.61			103.82	2067.27	58.539	2075.27	58.765	
340.65			103.83	2075.77	58.779	2083.77	59.005	
340.70	340.70	103.84	103.84	2085.50	59.020	2093.50	59.246	
340.71			103.85	2092.76	59.260	2100.76	59.486	
340.74			103.86	2101.25	59.501	2109.25	59.727	
340.80	340.80	103.87	103.87	2111.00	59.741	2119.00	59.967	
340.81			103.88	2118.23	59.982	2126.23	60.208	
340.84			103.89	2126.73	60.222	2134.73	60.448	
340.90	340.90	103.90	103.90	2136.50	60.463	2144.50	60.689	
340.91			103.91	2141.61	60.644	2149.61	60.870	
340.94			103.92	2147.99	60.824	2155.99	61.050	
340.97		103.93	103.93	2154.39	61.005	2162.39	61.231	
341.00	341.00	103.94	103.94	2162.00	61.185	2170.00	61.411	
341.04			103.95	2168.32	61.400	2176.32	61.626	
341.07			103.96	2175.91	61.615	2183.91	61.841	
341.10	341.10	103.97	103.97	2184.80	61.830	2192.80	62.056	
341.14			103.98	2191.10	62.045	2199.10	62.271	
341.17			103.99	2198.69	62.260	2206.69	62.486	
341.20	341.20	104.00	104.00	2207.60	62.475	2215.60	62.701	
341.24			104.01	2213.88	62.690	2221.88	62.916	
341.27			104.02	2221.47	62.905	2229.47	63.131	
341.30	341.30	104.03	104.03	2230.40	63.120	2238.40	63.346	
341.33			104.04	2236.65	63.335	2244.65	63.561	
341.37			104.05	2244.25	63.550	2252.25	63.776	
341.40	341.40	104.06	104.06	2253.20	63.765	2261.20	63.991	
341.43			104.07	2259.44	63.980	2267.44	64.206	
341.47			104.08	2267.05	64.196	2275.05	64.422	
341.50	341.50	104.09	104.09	2276.00	64.411	2284.00	64.637	
341.53			104.10	2282.25	64.626	2290.25	64.852	
341.56			104.11	2289.84	64.841	2297.84	65.067	
341.60	341.60	104.12	104.12	2298.80	65.056	2306.80	65.282	
341.63			104.13	2305.02	65.271	2313.02	65.497	
341.66			104.14	2312.62	65.486	2320.62	65.712	
341.70	341.70	104.15	104.15	2321.60	65.701	2329.60	65.927	
341.73			104.16	2327.80	65.916	2335.80	66.142	
341.76			104.17	2335.39	66.131	2343.39	66.357	
341.80	341.80	104.18	104.18	2344.40	66.346	2352.40	66.572	
341.83			104.19	2350.59	66.561	2358.59	66.787	
341.86			104.20	2358.20	66.777	2366.20	67.003	
341.90	341.90	104.21	104.21	2367.20	66.992	2375.20	67.218	
341.92			104.22	2373.39	67.207	2381.39	67.433	
341.96			104.23	2380.99	67.422	2388.99	67.648	
342.00	342.00	104.24	104.24	2390.00	67.637	2398.00	67.863	
342.02			104.25	2396.41	67.859	2404.41	68.085	
342.06			104.26	2404.23	68.080	2412.23	68.306	
342.10	342.10	104.27	104.27	2413.50	68.302	2421.50	68.528	
342.12			104.28	2419.89	68.524	2427.89	68.750	
342.15			104.29	2427.72	68.745	2435.72	68.971	
342.20	342.20	104.30	104.30	2437.00	68.967	2445.00	69.193	



R.L. as per old Area capacity table			Live			Total (Live+Dead)		Remarks
R.L. in		R.L. in	Capacity	Capacity	Capacity	Capacity		
Ft	Ft	Mt	in Mcft	in M.Cum	in Mcft	in M.Cum		
342.22			104.31	2443.21	69.184	2451.21	69.410	
342.25			104.32	2450.87	69.401	2458.87	69.627	
342.30	342.30	104.33	104.33	2460.50	69.618	2468.50	69.844	
342.32			104.34	2466.53	69.844	2474.53	70.070	
342.35			104.35	2474.52	70.071	2482.52	70.297	
342.40	342.40	104.36	104.36	2484.00	70.297	2492.00	70.523	
342.42			104.37	2490.34	70.519	2498.34	70.745	
342.45			104.38	2498.17	70.740	2506.17	70.966	
342.50	342.50	104.39	104.39	2507.50	70.962	2515.50	71.188	
342.52			104.40	2513.83	71.184	2521.83	71.410	
342.55			104.41	2521.66	71.405	2529.66	71.631	
342.60	342.60	104.42	104.42	2531.00	71.627	2539.00	71.853	
342.61			104.43	2537.15	71.844	2545.15	72.070	
342.65			104.44	2544.81	72.061	2552.81	72.287	
342.70	342.70	104.45	104.45	2554.50	72.278	2562.50	72.504	
342.71			104.46	2560.47	72.504	2568.47	72.730	
342.75			104.47	2568.46	72.731	2576.46	72.957	
342.80	342.80	104.48	104.48	2578.00	72.957	2586.00	73.183	
342.81			104.49	2584.28	73.179	2592.28	73.405	
342.84			104.50	2592.11	73.400	2600.11	73.626	
342.90	342.90	104.51	104.51	2601.50	73.622	2609.50	73.848	
342.91			104.52	2605.81	73.788	2613.81	74.014	
342.94			104.53	2611.68	73.955	2619.68	74.181	
342.97		104.54	104.54	2617.58	74.121	2625.58	74.347	
343.00	343.00	104.55	104.55	2625.00	74.287	2633.00	74.513	
343.04			104.56	2632.52	74.545	2640.52	74.771	
343.07			104.57	2641.62	74.802	2649.62	75.028	
343.10	343.10	104.58	104.58	2652.30	75.060	2660.30	75.286	
343.14			104.59	2659.82	75.318	2667.82	75.544	
343.17			104.60	2668.92	75.575	2676.92	75.801	
343.20	343.20	104.61	104.61	2679.60	75.833	2687.60	76.059	
343.24			104.62	2687.10	76.090	2695.10	76.316	
343.27			104.63	2696.19	76.348	2704.19	76.574	
343.30	343.30	104.64	104.64	2706.90	76.605	2714.90	76.831	
343.34			104.65	2714.38	76.863	2722.38	77.089	
343.37			104.66	2723.48	77.120	2731.48	77.346	
343.40	343.40	104.67	104.67	2734.20	77.378	2742.20	77.604	
343.43			104.68	2741.67	77.635	2749.67	77.861	
343.47			104.69	2750.75	77.893	2758.75	78.119	
343.50	343.50	104.70	104.70	2761.50	78.150	2769.50	78.376	
343.53			104.71	2768.94	78.408	2776.94	78.634	
343.57			104.72	2778.04	78.665	2786.04	78.891	
343.60	343.60	104.73	104.73	2788.80	78.923	2796.80	79.149	
343.63			104.74	2796.23	79.180	2804.23	79.406	
343.66			104.75	2805.31	79.438	2813.31	79.664	
343.70	343.70	104.76	104.76	2816.10	79.695	2824.10	79.921	
343.73			104.77	2823.50	79.953	2831.50	80.179	
343.76			104.78	2832.60	80.210	2840.60	80.436	
343.80	343.80	104.79	104.79	2843.40	80.468	2851.40	80.694	
343.83			104.80	2850.80	80.726	2858.80	80.952	
343.86			104.81	2859.90	80.983	2867.90	81.209	
343.90	343.90	104.82	104.82	2870.70	81.241	2878.70	81.467	

R.L. in Ft	R.L. as per old Area capacity table		Live			Total (Live+Dead)		Remarks
	Ft	Mt	R.L. in	Capacity	Capacity	Capacity	Capacity	
			Mt	in Mcft	in M.Cum	in Mcft	in M.Cum	
343.93			104.83	2878.11	81.499	2886.11	81.725	
343.96			104.84	2887.22	81.757	2895.22	81.983	
344.00	344.00	104.85	104.85	1898.00	82.015	1906.00	82.241	
344.02			104.86	2905.63	82.278	2913.63	82.504	
344.06			104.87	2914.93	82.542	2922.93	82.768	
344.10	344.10	104.88	104.88	2926.00	82.805	2934.00	83.031	
344.12			104.89	2933.57	83.069	2941.57	83.295	
344.16			104.90	2942.90	83.334	2950.90	83.560	
344.20	344.20	104.91	104.91	2954.00	83.598	2962.00	83.824	
344.22			104.92	2961.56	83.862	2969.56	84.088	
344.25			104.93	2970.88	84.126	2978.88	84.352	
344.30	344.30	104.94	104.94	2982.00	84.390	2990.00	84.616	
344.32			104.95	2989.54	84.654	2997.54	84.880	
344.35			104.96	2998.87	84.919	3006.87	85.145	
344.40	344.40	104.97	104.97	3010.00	85.183	3018.00	85.409	
344.42			104.98	3017.53	85.447	3025.53	85.673	
344.45			104.99	3026.86	85.711	3034.86	85.937	
344.50	344.50	105.00	105.00	3038.00	85.975	3046.00	86.201	
344.52			105.01	3046.64	86.271	3054.64	86.497	
344.55			105.02	3057.11	86.568	3065.11	86.794	
344.60	344.60	105.03	105.03	3069.40	86.864	3077.40	87.090	
344.62			105.04	3078.03	87.160	3086.03	87.386	
344.65			105.05	3088.48	87.456	3096.48	87.682	
344.70	344.70	105.06	105.06	3100.80	87.752	3108.80	87.978	
344.71			105.07	3109.40	88.048	3117.40	88.274	
344.75			105.08	3119.86	88.345	3127.86	88.571	
344.80	344.80	105.09	105.09	3132.20	88.641	3140.20	88.867	
344.81			105.10	3140.78	88.937	3148.78	89.163	
344.84			105.11	3151.23	89.233	3159.23	89.459	
344.90	344.90	105.12	105.12	3163.60	89.529	3171.60	89.755	
344.91			105.13	3169.54	89.751	3177.54	89.977	
344.94			105.14	3177.39	89.974	3185.39	90.200	
344.98		105.15	105.15	3185.27	90.196	3193.27	90.422	
345.00	345.00	105.16	105.16	3195.00	90.418	3203.00	90.644	
345.04			105.17	3203.97	90.726	3211.97	90.952	
345.07			105.18	3214.86	91.035	3222.86	91.261	
345.10	345.10	105.19	105.19	3227.70	91.343	3235.70	91.569	
345.14			105.20	3236.65	91.652	3244.65	91.878	
345.17			105.21	3247.55	91.960	3255.55	92.186	
345.20	345.20	105.22	105.22	3260.40	92.269	3268.40	92.495	
345.24			105.23	3269.34	92.577	3277.34	92.803	
345.27			105.24	3280.23	92.886	3288.23	93.112	
345.30	345.30	105.25	105.25	3293.10	93.194	3301.10	93.420	
345.34			105.26	3302.02	93.503	3310.02	93.729	
345.37			105.27	3312.92	93.811	3320.92	94.037	
345.40	345.40	105.28	105.28	3325.80	94.120	3333.80	94.346	
345.44			105.29	3334.71	94.428	3342.71	94.654	
345.47			105.30	3345.59	94.737	3353.59	94.963	
345.50	345.50	105.31	105.31	3358.50	95.045	3366.50	95.271	
345.53			105.32	3367.37	95.353	3375.37	95.579	
345.57			105.33	3378.26	95.662	3386.26	95.888	
345.60	345.60	105.34	105.34	3391.20	95.970	3399.20	96.196	

R.L. in Ft	R.L. as per old Area capacity table		Live			Total (Live+Dead)		Remarks
	Ft	Mt	R.L. in Mt	Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
345.63			105.35	3400.05	96.279	3408.05	96.505	
345.67			105.36	3410.95	96.587	3418.95	96.813	
345.70	345.70	105.37	105.37	3423.90	96.896	3431.90	97.122	
345.73			105.38	3432.74	97.204	3440.74	97.430	
345.76			105.39	3443.63	97.513	3451.63	97.739	
345.80	345.80	105.40	105.40	3456.60	97.821	3464.60	98.047	
345.83			105.41	3465.42	98.130	3473.42	98.356	
345.86			105.42	3476.32	98.438	3484.32	98.664	
345.90	345.90	105.43	105.43	3489.30	98.747	3497.30	98.973	
345.93			105.44	3498.11	99.055	3506.11	99.281	
345.96			105.45	3508.99	99.364	3516.99	99.590	
346.00	346.00	105.46	105.46	3522.00	99.672	3530.00	99.898	
346.03			105.47	3530.68	99.978	3538.68	100.204	
346.06			105.48	3541.47	100.283	3549.47	100.509	
346.10	346.10	105.49	105.49	3554.40	100.589	3562.40	100.815	
346.12			105.50	3563.06	100.895	3571.06	101.121	
346.16			105.51	3573.86	101.200	3581.86	101.426	
346.20	346.20	105.52	105.52	3586.80	101.506	3594.80	101.732	
346.22			105.53	3595.45	101.812	3603.45	102.038	
346.26			105.54	3606.24	102.117	3614.24	102.343	
346.30	346.30	105.55	105.55	3619.20	102.423	3627.20	102.649	
346.32			105.56	3627.83	102.729	3635.83	102.955	
346.35			105.57	3638.62	103.034	3646.62	103.260	
346.40	346.40	105.58	105.58	3651.60	103.340	3659.60	103.566	
346.42			105.59	3660.21	103.646	3668.21	103.872	
346.45			105.60	3671.01	103.951	3679.01	104.177	
346.50	346.50	105.61	105.61	3684.00	104.257	3692.00	104.483	
346.52			105.62	3692.60	104.563	3700.60	104.789	
346.55			105.63	3703.39	104.868	3711.39	105.094	
346.60	346.60	105.64	105.64	3716.40	105.174	3724.40	105.400	
346.62			105.65	3724.98	105.480	3732.98	105.706	
346.65			105.66	3735.77	105.785	3743.77	106.011	
346.70	346.70	105.67	105.67	3748.80	106.091	3756.80	106.317	
346.71			105.68	3757.37	106.397	3765.37	106.623	
346.75			105.69	3768.18	106.703	3776.18	106.929	
346.80	346.80	105.70	105.70	3781.20	107.009	3789.20	107.235	
346.81			105.71	3789.76	107.314	3797.76	107.540	
346.85			105.72	3800.53	107.619	3808.53	107.845	
346.90	346.90	105.73	105.73	3813.60	107.924	3821.60	108.150	
346.91			105.74	3822.09	108.230	3830.09	108.456	
346.94			105.75	3832.89	108.535	3840.89	108.761	
347.00	347.00	105.76	105.76	3846.00	108.841	3854.00	109.067	
347.01			105.77	3854.64	109.151	3862.64	109.377	
347.04			105.78	3865.60	109.462	3873.60	109.688	
347.10	347.10	105.79	105.79	3878.90	109.772	3886.90	109.998	
347.11			105.80	3884.78	110.005	3892.78	110.231	
347.14			105.81	3892.99	110.237	3900.99	110.463	
347.17		105.82	105.82	3901.25	110.470	3909.25	110.696	
347.20	347.20	105.83	105.83	3911.80	110.703	3919.80	110.929	
347.24			105.84	3920.41	111.014	3928.41	111.240	
347.27			105.85	3931.38	111.324	3939.38	111.550	
347.30	347.30	105.86	105.86	3944.70	111.635	3952.70	111.861	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
347.34			105.87	3953.31	111.945	3961.31	112.171	
347.37			105.88	3964.27	112.256	3972.27	112.482	
347.40	347.40	105.89	105.89	3977.60	112.566	3985.60	112.792	
347.44			105.90	3986.19	112.876	3994.19	113.102	
347.47			105.91	3997.15	113.187	4005.15	113.413	
347.50	347.50	105.92	105.92	4010.50	113.497	4018.50	113.723	
347.54			105.93	4019.07	113.807	4027.07	114.033	
347.57			105.94	4030.03	114.118	4038.03	114.344	
347.60	347.60	105.95	105.95	4043.40	114.428	4051.40	114.654	
347.63			105.96	4051.95	114.738	4059.95	114.964	
347.67			105.97	4062.91	115.049	4070.91	115.275	
347.70	347.70	105.98	105.98	4076.30	115.359	4084.30	115.585	
347.73			105.99	4084.82	115.669	4092.82	115.895	
347.76			106.00	4095.78	115.980	4103.78	116.206	
347.80	347.80	106.01	106.01	4109.20	116.290	4117.20	116.516	
347.83			106.02	4117.70	116.600	4125.70	116.826	
347.86			106.03	4128.66	116.911	4136.66	117.137	
347.90	347.90	106.04	106.04	4142.10	117.221	4150.10	117.447	
347.93			106.05	4150.58	117.531	4158.58	117.757	
347.96			106.06	4161.54	117.842	4169.54	118.068	
348.00	348.00	106.07	106.07	4175.00	118.152	4183.00	118.378	Crest R.L.
348.03			106.08	4173.22	118.172	4181.22	118.398	
348.06			106.09	4173.93	118.193	4181.93	118.419	
348.10	348.10	106.10	106.10	4212.50	118.213	4220.50	118.439	
348.13			106.11	4198.93	118.900	4206.93	119.126	
348.16			106.12	4223.20	119.588	4231.20	119.814	
348.20	348.20	106.13	106.13	4250.00	120.275	4258.00	120.501	
348.22			106.14	4259.96	120.629	4267.96	120.855	
348.26			106.15	4272.45	120.982	4280.45	121.208	
348.30	348.30	106.16	106.16	4287.50	121.336	4295.50	121.562	
348.32			106.17	4297.43	121.690	4305.43	121.916	
348.36			106.18	4309.92	122.043	4317.92	122.269	
348.40	348.40	106.19	106.19	4325.00	122.397	4333.00	122.623	
348.42			106.20	4334.90	122.751	4342.90	122.977	
348.45			106.21	4347.39	123.104	4355.39	123.330	
348.50	348.50	106.22	106.22	4362.50	123.458	4370.50	123.684	
348.52			106.23	4372.38	123.812	4380.38	124.038	
348.55			106.24	4384.88	124.166	4392.88	124.392	
348.60	348.60	106.25	106.25	4400.00	124.520	4408.00	124.746	
348.62			106.26	4409.87	124.874	4417.87	125.100	
348.65			106.27	4422.36	125.227	4430.36	125.453	
348.70	348.70	106.28	106.28	4437.50	125.581	4445.50	125.807	
348.72			106.29	4447.34	125.935	4455.34	126.161	
348.75			106.30	4459.83	126.288	4467.83	126.514	
348.80	348.80	106.31	106.31	4475.00	126.642	4483.00	126.868	
348.81			106.32	4484.81	126.996	4492.81	127.222	
348.85			106.33	4497.30	127.349	4505.30	127.575	
348.90	348.90	106.34	106.34	4512.50	127.703	4520.50	127.929	
348.91			106.35	4519.16	127.968	4527.16	128.194	
348.95			106.36	4528.53	128.234	4536.53	128.460	
348.98		106.37	106.37	4537.94	128.499	4545.94	128.725	
349.00	349.00	106.38	106.38	4550.00	128.765	4558.00	128.991	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
349.04			106.39	4559.11	129.100	4567.11	129.326	
349.08			106.40	4570.93	129.434	4578.93	129.660	
349.10	349.10	106.41	106.41	4585.50	129.769	4593.50	129.995	
349.14			106.42	4594.58	130.104	4602.58	130.330	
349.18			106.43	4606.41	130.439	4614.41	130.665	
349.20	349.20	106.44	106.44	4621.00	130.774	4629.00	131.000	
349.24			106.45	4630.06	131.109	4638.06	131.335	
349.27			106.46	4641.88	131.443	4649.88	131.669	
349.30	349.30	106.47	106.47	4656.50	131.778	4664.50	132.004	
349.34			106.48	4665.53	132.113	4673.53	132.339	
349.37			106.49	4677.36	132.448	4685.36	132.674	
349.40	349.40	106.50	106.50	4692.00	132.783	4700.00	133.009	
349.44			106.51	4701.02	133.118	4709.02	133.344	
349.47			106.52	4712.85	133.453	4720.85	133.679	
349.50	349.50	106.53	106.53	4727.50	133.788	4735.50	134.014	
349.54			106.54	4736.50	134.123	4744.50	134.349	
349.57			106.55	4748.32	134.457	4756.32	134.683	
349.60	349.60	106.56	106.56	4763.00	134.792	4771.00	135.018	
349.63			106.57	4771.96	135.127	4779.96	135.353	
349.67			106.58	4783.80	135.462	4791.80	135.688	
349.70	349.70	106.59	106.59	4798.50	135.797	4806.50	136.023	
349.73			106.60	4807.46	136.132	4815.46	136.358	
349.77			106.61	4819.29	136.467	4827.29	136.693	
349.80	349.80	106.62	106.62	4834.00	136.802	4842.00	137.028	
349.83			106.63	4842.24	137.117	4850.24	137.343	
349.86			106.64	4853.37	137.432	4861.37	137.658	
349.90	349.90	106.65	106.65	4864.50	137.747	4872.50	137.973	
349.93			106.66	4873.68	138.007	4881.68	138.233	
349.96			106.67	4882.88	138.268	4890.88	138.494	
350.00	350.00	106.68	106.68	4895.00	138.528	4903.00	138.754	
350.03			106.69	4903.57	138.854	4911.57	139.080	
350.06			106.70	4915.07	139.179	4923.07	139.405	
350.10	350.10	106.71	106.71	4929.50	139.505	4937.50	139.731	
350.13			106.72	4938.06	139.830	4946.06	140.056	
350.16			106.73	4949.55	140.156	4957.55	140.382	
350.20	350.20	106.74	106.74	4964.00	140.481	4972.00	140.707	
350.23			106.75	4972.53	140.806	4980.53	141.032	
350.26			106.76	4984.02	141.132	4992.02	141.358	
350.30	350.30	106.77	106.77	4998.50	141.457	5006.50	141.683	
350.32			106.78	5007.00	141.782	5015.00	142.008	
350.36			106.79	5018.48	142.108	5026.48	142.334	
350.40	350.40	106.80	106.80	5033.00	142.433	5041.00	142.659	
350.42			106.81	5041.47	142.759	5049.47	142.985	
350.46			106.82	5052.98	143.084	5060.98	143.310	
350.50	350.50	106.83	106.83	5067.50	143.410	5075.50	143.636	
350.52			106.84	5075.98	143.736	5083.98	143.962	
350.55			106.85	5087.48	144.061	5095.48	144.287	
350.60	350.60	106.86	106.86	5102.00	144.387	5110.00	144.613	
350.62			106.87	5110.47	144.712	5118.47	144.938	
350.65			106.88	5121.96	145.038	5129.96	145.264	
350.70	350.70	106.89	106.89	5136.50	145.363	5144.50	145.589	
350.72			106.90	5144.93	145.688	5152.93	145.914	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
350.75			106.91	5156.42	146.014	5164.42	146.240	
350.80	350.80	106.92	106.92	5171.00	146.339	5179.00	146.565	
350.82			106.93	5179.41	146.665	5187.41	146.891	
350.85			106.94	5190.91	146.990	5198.91	147.216	
350.90	350.90	106.95	106.95	5205.50	147.316	5213.50	147.542	
350.91			106.96	5213.90	147.641	5221.90	147.867	
350.95			106.97	5225.39	147.967	5233.39	148.193	
351.00	351.00	106.98	106.98	5240.00	148.292	5248.00	148.518	
351.01			106.99	5251.63	148.710	5259.63	148.936	
351.05			107.00	5266.38	149.127	5274.38	149.353	
351.10	351.10	107.01	107.01	5284.80	149.545	5292.80	149.771	
351.11			107.02	5296.22	149.972	5304.22	150.198	
351.14			107.03	5311.31	150.400	5319.31	150.626	
351.20	351.20	107.04	107.04	5329.60	150.827	5337.60	151.053	
351.21			107.05	5341.33	151.250	5349.33	151.476	
351.24			107.06	5356.26	151.672	5364.26	151.898	
351.30	351.30	107.07	107.07	5374.40	152.095	5382.40	152.321	
351.31			107.08	5386.11	152.518	5394.11	152.744	
351.34			107.09	5401.04	152.940	5409.04	153.166	
351.40	351.40	107.10	107.10	5419.20	153.363	5427.20	153.589	
351.41			107.11	5430.89	153.786	5438.89	154.012	
351.44			107.12	5445.82	154.208	5453.82	154.434	
351.50	351.50	107.13	107.13	5464.00	154.631	5472.00	154.857	
351.50			107.14	5476.93	155.089	5484.93	155.315	
351.54			107.15	5493.11	155.548	5501.11	155.774	
351.60	351.60	107.16	107.16	5512.60	156.006	5520.60	156.232	
351.60			107.17	5525.50	156.465	5533.50	156.691	
351.64			107.18	5541.70	156.923	5549.70	157.149	
351.70	351.70	107.19	107.19	5561.20	157.382	5569.20	157.608	
351.70			107.20	5574.08	157.840	5582.08	158.066	
351.73			107.21	5590.26	158.299	5598.26	158.525	
351.80	351.80	107.22	107.22	5609.80	158.757	5617.80	158.983	
351.80			107.23	5622.65	159.216	5630.65	159.442	
351.83			107.24	5638.85	159.674	5646.85	159.900	
351.90	351.90	107.25	107.25	5658.40	160.133	5666.40	160.359	
351.90			107.26	5667.18	160.477	5675.18	160.703	
351.93			107.27	5679.32	160.820	5687.32	161.046	
351.96		107.28	107.28	5691.51	161.164	5699.51	161.390	
352.00	352.00	107.29	107.29	5707.00	161.508	5715.00	161.734	
352.03			107.30	5719.02	161.945	5727.02	162.171	
352.06			107.31	5734.44	162.381	5742.44	162.607	
352.10	352.10	107.32	107.32	5753.30	162.818	5761.30	163.044	
352.13			107.33	5765.28	163.255	5773.28	163.481	
352.16			107.34	5780.70	163.691	5788.70	163.917	
352.20	352.20	107.35	107.35	5799.60	164.128	5807.60	164.354	
352.23			107.36	5811.55	164.565	5819.55	164.791	
352.26			107.37	5826.97	165.001	5834.97	165.227	
352.30	352.30	107.38	107.38	5845.90	165.438	5853.90	165.664	
352.33			107.39	5857.82	165.875	5865.82	166.101	
352.36			107.40	5873.25	166.312	5881.25	166.538	
352.40	352.40	107.41	107.41	5892.20	166.749	5900.20	166.975	
352.42			107.42	5904.11	167.186	5912.11	167.412	

R.L. in Ft	R.L. as per old Area capacity table		R.L. in Mt	Live		Total (Live+Dead)		Remarks
	Ft	Mt		Capacity in Mcft	Capacity in M.Cum	Capacity in Mcft	Capacity in M.Cum	
352.46			107.43	5919.53	167.622	5927.53	167.848	
352.50	352.50	107.44	107.44	5938.50	168.059	5946.50	168.285	
352.52			107.45	5950.38	168.496	5958.38	168.722	
352.55			107.46	5965.81	168.933	5973.81	169.159	
352.60	352.60	107.47	107.47	5984.80	169.370	5992.80	169.596	
352.62			107.48	5996.67	169.807	6004.67	170.033	
352.65			107.49	6012.09	170.243	6020.09	170.469	
352.70	352.70	107.50	107.50	6031.10	170.680	6039.10	170.906	
352.72			107.51	6040.57	171.050	6048.57	171.276	
352.75			107.52	6053.64	171.420	6061.64	171.646	
352.80	352.80	107.53	107.53	6077.40	171.790	6085.40	172.016	
352.82			107.54	6084.48	172.293	6092.48	172.519	
352.85			107.55	6102.26	172.797	6110.26	173.023	
352.90	352.90	107.56	107.56	6123.70	173.300	6131.70	173.526	
352.92			107.57	6135.46	173.737	6143.46	173.963	
352.95			107.58	6150.90	174.174	6158.90	174.400	
353.00	353.00	107.59	107.59	6170.00	174.611	6178.00	174.837	
353.01			107.60	6181.99	175.054	6189.99	175.280	
353.05			107.61	6197.64	175.498	6205.64	175.724	
353.10	353.10	107.62	107.62	6217.00	175.941	6225.00	176.167	
353.11			107.63	6228.95	176.384	6236.95	176.610	
353.15			107.64	6244.61	176.828	6252.61	177.054	
353.20	353.20	107.65	107.65	6264.00	177.271	6272.00	177.497	
353.21			107.66	6275.92	177.714	6283.92	177.940	
353.24			107.67	6291.58	178.158	6299.58	178.384	
353.30	353.30	107.68	107.68	6311.00	178.601	6319.00	178.827	
353.31			107.69	6322.89	179.044	6330.89	179.270	
353.34			107.70	6338.55	179.488	6346.55	179.714	
353.40	353.40	107.71	107.71	6358.00	179.931	6366.00	180.157	
353.41			107.72	6369.86	180.374	6377.86	180.600	
353.44			107.73	6385.52	180.818	6393.52	181.044	
353.50	353.50	107.74	107.74	6405.00	181.261	6413.00	181.487	
353.51			107.75	6416.83	181.704	6424.83	181.930	
353.54			107.76	6432.48	182.148	6440.48	182.374	
353.60	353.60	107.77	107.77	6452.00	182.591	6460.00	182.817	
353.60			107.78	6463.81	183.035	6471.81	183.261	
353.64			107.79	6479.48	183.478	6487.48	183.704	
353.70	353.70	107.80	107.80	6499.00	183.922	6507.00	184.148	
353.70			107.81	6510.80	184.365	6518.80	184.591	
353.74			107.82	6526.46	184.809	6534.46	185.035	
353.80	353.80	107.83	107.83	6546.00	185.252	6554.00	185.478	
353.80			107.84	6557.77	185.695	6565.77	185.921	
353.83			107.85	6573.42	186.139	6581.42	186.365	
353.90	353.90	107.86	107.86	6593.00	186.582	6601.00	186.808	
353.90			107.87	6604.74	187.025	6612.74	187.251	
353.93			107.88	6620.39	187.469	6628.39	187.695	
354.00	354.00	107.89	107.89	6640.00	187.912	6648.00	188.138	F.R.L.


## **Annexure - 4**

### **Daily Progress Reports**




 <b>DAILY PROGRESS REPORT</b>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 001

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34420	
Vessel:	OSaS SMB		Date:	13-01-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav			Client Rep.		
<b>Survey Personnel:</b>					
1. Salman		2. Samson		3. Gaurav	
4. Amit		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
	1115	Transport with survey equipment arrived at guest house.			
1115	1315	Survey team Salman, Samson, Gaurav and Amit arrived at site.			
1330	1345	Lunch.			
1345	1410	Survey equipment shifted from tempo to store.			
1410	1515	Meeting attended by Party Chief with Deputy Eng. Mukesh Joshi and Section Officer Hiren Joshi at guest house.			
1515	1610	Site visit by survey team accompanied by Section Officer Hiren Joshi.			
1610	1700	Location selection and marking of reference station. Boat trial.			
1700	1730	Team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.00 sq.km	Line km: 0.0	Bathymetry 0.00 sq.km	Line km: 0.0
		Topo: 0.00 sq.km	Line km: 0.0	Topo: 0.00 sq.km	Line km: 0.0
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Survey preparations.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 002

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34420	
Vessel:	OSaS SMB		Date:	14-01-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav			Client Rep.		
<b>Survey Personnel:</b>					
1. Salman		2. Samson		3. Gaurav	
4. Amit		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0700	0730	Survey team arrived at site.			
0810	1230	Established two reference stations near Val Tower by static DGPS observation.			
1230	1310	Lunch.			
1310	1515	Vertical control established by level transfer from existing reference shown by section officer to the newly established reference station (Temporary Benchmark).			
1515	1700	Installation of digital water level gauge and level transfer from TBM.			
1700	1730	Team returned to guest house.			
0700	0730	Survey team arrived at site.			
		Today's coverage		Cumulative coverage	
		Bathymetry: <b>0.00 sq.km</b>	Line km: <b>0.0</b>	Bathymetry <b>0.00 sq.km</b>	Line km: <b>0.0</b>
		Topo: <b>0.00 sq.km</b>	Line km: <b>0.0</b>	Topo: <b>0.00 sq.km</b>	Line km: <b>0.0</b>
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Survey preparations.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 003

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34420	
Vessel:	OSaS SMB		Date:	15-01-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav			Client Rep.		
<b>Survey Personnel:</b>					
1. Salman		2. Samson		3. Gaurav	
4. Amit		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0815	0930	Reached site and boat trial taken.			
0930		Meeting with section officer and discussed survey task. He provided the hard copy of old survey records and assured all possible help.			
0930	1530	Boat furniture installed by a local carpenter.			
1530	1715	Equipment shifted to boat.			
	1800	Team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: <b>0.00 sq.km</b>	Line km: <b>0.0</b>	Bathymetry <b>0.00 sq.km</b>	Line km: <b>0.0</b>
		Topo: <b>0.00 sq.km</b>	Line km: <b>0.0</b>	Topo: <b>0.00 sq.km</b>	Line km: <b>0.0</b>
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Project kick start meeting with client representatives and survey preparations.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <b>DAILY PROGRESS REPORT</b>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 004

Client:		Narmada Water Resources, Water Supply & Kalpsar Department		Project No:		P34420	
Vessel:		OSaS SMB		Date:		16-01-2021	
Location:		BHADAR DAM		Sheet No:		1 of 1	
Party Chief: Sunil Kumar Yadav				Client Rep.			
<b>Survey Personnel:</b>							
1. Salman		2. Samson		3. Gaurav			
4. Amit		5.		6.			
7.		8.		9.			
10.							
<b>Equipment</b>		RTK System	SBES System	Auto Level		Heave sensor	
		Water Level Meter	Bar Check	Generator		Hypack	
		Computer					
<b>Time (hrs)</b>		<b>Activities</b>					
0815		1100 Reached site and set up RTK reference station and survey boat for display to Client.					
1100		1300 Attended project kick-off meeting with senior officers from client side in presence of Project Manager Mr Santokh Chand and Mr. Narpal Singh Rathore.					
1300		1415 Site visit and briefing conducted by survey team for Client representatives regarding conduct of survey and various equipment to be used.					
1415		1540 Lunch break.					
1540		1730 System preparation and check for survey. Water level data checked.					
1730		1800 Team returned to guest house.					
		Today's coverage		Cumulative coverage			
		Bathymetry: <b>0.00 sq.km</b>		Line km: <b>0.0</b>		Bathymetry <b>0.00 sq.km</b>	
		Topo: <b>0.00 sq.km</b>		Line km: <b>0.0</b>		Topo: <b>0.00 sq.km</b>	
		Line km: <b>0.0</b>		Line km: <b>0.0</b>		Line km: <b>0.0</b>	
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours			
<b>Plan for next 24 hours:</b> Project kick start meeting with client representatives and survey preparations.							
<b>Remarks:</b>							
 <b>Party Chief</b>				<b>Client Representative</b>			


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 005

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34420
Vessel:	OSaS SMB			Date:	17-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson		3. Gaurav	
4. Amit		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0835	Reached site and set up RTK reference station for bathymetric and land survey.			
0835	0900	Bar check carried out. Rover RTK system check carried out using known station.			
0900		Bathymetric and land survey started.			
1250	1330	Lunch break.			
1330		Bathymetric and land survey resumed.			
	1710	Bathymetry survey terminated.			
	1750	Land survey terminated. Team returned at Val Tower and secured reference station.			
1750	1830	Team returned to guest house			
		Today's coverage		Cumulative coverage	
		Bathymetry: <b>1.07 sq.km</b>	Line km: <b>47</b>	Bathymetry: <b>1.07 sq.km</b>	Line km: <b>47</b>
		Topo: <b>0.33 sq.km</b>	Line km: <b>13.2</b>	Topo: <b>0.33 sq.km</b>	Line km: <b>13.2</b>
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 006

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34420
Vessel:	OSaS SMB			Date:	18-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson		3. Gaurav	
4. Amit		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0730	0815	Reached site and set up RTK reference station for bathymetric and land survey.			
0815	0845	Bar check carried out. Rover RTK system check carried out using known station.			
0900		Bathymetric and land survey started.			
1230	1300	Lunch break.			
1300		Bathymetric and land survey resumed.			
	1740	Bathymetry survey terminated.			
	1730	Land survey terminated. Team returned at Val Tower and secured reference station.			
1800	1815	Team returned to guest house			
		Today's coverage		Cumulative coverage	
		Bathymetry: <b>1.18 sq.km</b>	Line km: <b>55</b>	Bathymetry: <b>2.25 sq.km</b>	Line km: <b>102</b>
		Topo: <b>0.55 sq.km</b>	Line km: <b>22.5</b>	Topo: <b>0.88 sq.km</b>	Line km: <b>35.7</b>
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 007

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	19-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson		3. Gaurav	
4. Amit		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>	<b>Activities</b>				
0730	0810	Reached site and set up RTK reference station at two location for bathymetric and land survey.			
0815	0845	Bar check carried out. RTK system check carried out using known station.			
0900		Bathymetric survey started.			
0915		Land survey started.			
	1730	Bathymetry survey terminated and reference station secured.			
	1740	Land survey terminated and reference station secured.			
1800	1810	Team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.17 sq.km	Line km: 54	Bathymetry: 3.42 sq.km	Line km: 156
		Topo: 0.41 sq.km	Line km: 16.8	Topo: 1.29 sq.km	Line km: 52.5
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		

 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT


DPR No. 008

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	20-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson		3. Gaurav	
4. Amit		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System		SBES System		Auto Level
	Water Level Meter		Bar Check		Generator
	Computer				Heave sensor
				Hypack	
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0815	Reached site and set up RTK reference station at two location for bathymetric and land survey.			
0815	0845	Bar check carried out. RTK system check carried out using known station.			
0900		Bathymetric survey started.			
0915		Land survey started.			
	1715	Bathymetry survey terminated and reference station secured.			
	1730	Land survey terminated and reference station secured.			
1745	1810	Team returned to guest house			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.67 sq.km	Line km: 34.2	Bathymetry: 4.09sq.km	Line km: 190.2
		Topo: 0.54 sq.km	Line km: 22.4	Topo: 1.83 sq.km	Line km: 74.9
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
					
<b>Party Chief</b>			<b>Client Representative</b>		




 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 009

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	21-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson Chacko		3. Gaurav Sharma	
4. Amit Bhardwaj		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System		SBES System		Auto Level
	Water Level Meter		Bar Check		Generator
	Computer				Heave sensor
				Hypack	
<b>Time (hrs)</b>			<b>Activities</b>		
0730	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0730	0830	Land survey team reached site and set up RTK reference station for land survey.			
0815	0830	Bar check carried out.			
0840		Bathymetric survey started.			
0850		Land survey started.			
	1600	Bathymetry survey terminated in view of Executive Engineer visit at guest house. Section officer requested Party Chief to be present at guest house during visit.			
	1815	Land survey terminated and reference station secured.			
1845	1945	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.01 sq.km		Bathymetry: 5.09sq.km	
		Line km: 44.7		Line km: 234.9	
		Topo: 0.4 sq.km		Topo: 2.23 sq.km	
		Line km: 16.4		Line km: 91.3	
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 010

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	22-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson Chacko		3. Gaurav Sharma	
4. Amit Bhardwaj		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System		SBES System		Auto Level
	Water Level Meter		Bar Check		Generator
	Computer				Heave sensor Hypack
<b>Time (hrs)</b>		<b>Activities</b>			
0730	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0730	0830	Land survey team reached at site and set up RTK reference station for land survey.			
0805	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0850		Land survey started.			
	1740	Bathymetry survey terminated and base station secured.			
	1745	Land survey terminated and reference station secured.			
1745	1900	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: <b>1.13 sq.km</b>		Bathymetry: <b>6.22sq.km</b>	
		Line km: <b>49</b>		Line km: <b>283.9</b>	
		Topo: <b>0.42 sq.km</b>		Topo: <b>2.65 sq.km</b>	
		Line km: <b>17.22</b>		Line km: <b>108.6</b>	
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 011

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	23-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson Chacko		3. Gaurav Sharma	
4. Amit Bhardwaj		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>	<b>Activities</b>				
0745	0815	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0745	0830	Land survey team reached site and set up RTK reference station for land survey.			
0815	0830	Bar check carried out.			
0830		Bathymetric survey started.			
0850		Land survey started.			
	1740	Bathymetry survey terminated and base station secured.			
	1750	Land survey terminated and reference station secured.			
1750	1945	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: <b>0.8 sq.km</b>	Line km: <b>33.2</b>	Bathymetry: <b>7.02sq.km</b>	Line km: <b>317.1</b>
		Topo: <b>0.59 sq.km</b>	Line km: <b>23.78</b>	Topo: <b>3.24 sq.km</b>	Line km: <b>132.38</b>
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 012

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320	
Vessel:	OSaS SMB			Date:	24-01-2021	
Location:	BHADAR DAM			Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav				Client Rep.		
<b>Survey Personnel:</b>						
1. Salman		2. Samson Chacko		3. Gaurav Sharma		
4. Amit Bhardwaj		5. Binu Kumar		6.		
7.		8.		9.		
10.						
<b>Equipment</b>	RTK System		SBES System	Auto Level		Heave sensor
	Water Level Meter		Bar Check	Generator		Hypack
	Computer					
<b>Time (hrs)</b>		<b>Activities</b>				
0745	0815	Bathy team reached at site and set up RTK reference station for bathymetric survey.				
0745	0830	Land survey team reached at site and set up RTK reference station for land survey.				
0815	0830	Bar check carried out.				
0830		Bathymetric survey started.				
0850		Land survey started.				
	1730	Bathymetry survey terminated and base station secured.				
	1740	Land survey terminated and reference station secured.				
1750	1945	Land Survey team returned to guest house.				
		Today's coverage			Cumulative coverage	
		Bathymetry: <b>1.27 sq.km</b>		Line km: <b>52.2</b>	Bathymetry: <b>8.29sq.km</b>	
		Topo: <b>0.6 sq.km</b>		Line km: <b>24.6</b>	Topo: <b>3.84 sq.km</b>	
		Weather downtime today: Nil hours			Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.						
<b>Remarks:</b>						
 <b>Party Chief</b>				<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 013

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	25-01-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav			Client Rep.		
<b>Survey Personnel:</b>					
1. Salman		2. Samson Chacko		3. Gaurav Sharma	
4. Amit Bhardwaj		5. Binu Kumar		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>	<b>Activities</b>				
0740	0810	Bathy team reached at site and set up RTK reference station for bathymetric survey.			
0740	0830	Land survey team reached at site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0820		Bathymetric survey started.			
0840		Land survey started.			
	1730	Bathymetry survey terminated and base station secured.			
	1740	Land survey terminated and reference station secured.			
1740	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.14 sq.km	Line km: 47	Bathymetry: 9.43sq.km	Line km: 416.3
		Topo: 0.58 sq.km	Line km: 23.8	Topo: 4.42 sq.km	Line km: 180.7
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p><b>OCEAN</b> Science &amp; Surveying</p> <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 014

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	26-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson Chacko		3. Gaurav Sharma	
4. Amit Bhardwaj		5. Binu Kumar		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0730	0800	Bathy team reached at site and set up RTK reference station for bathymetric survey.			
0740	0830	Land survey team reached at site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0820		Bathymetric survey started.			
0840		Land survey started.			
	1745	Bathymetry survey terminated and base station secured.			
	1740	Land survey terminated and reference station secured.			
1740	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.24 sq.km	Line km: 51.0	Bathymetry: 10.67sq.km	Line km: 467.3
		Topo: 0.64 sq.km	Line km: 26.5	Topo: 5.06 sq.km	Line km: 207.2
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 015

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	27-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson Chacko		3. Gaurav Sharma	
4. Amit Bhardwaj		5. Binu Kumar		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0805	Bathy team reached at site and set up RTK reference station for bathymetric survey.			
0740	0830	Land survey team reached at site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0820		Bathymetric survey started.			
0840		Land survey started.			
	1735	Bathymetry survey terminated and base station secured.			
	1730	Land survey terminated and reference station secured.			
1730	1910	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.05 sq.km	Line km: 43.0	Bathymetry: 11.72sq.km	Line km: 510.3
		Topo: 0.79 sq.km	Line km: 32.3	Topo: 5.85 sq.km	Line km: 239.5
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
					
<b>Party Chief</b>			<b>Client Representative</b>		

 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT


DPR No. 016

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320	
Vessel:	OSaS SMB			Date:	28-01-2021	
Location:	BHADAR DAM			Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav				Client Rep.		
<b>Survey Personnel:</b>						
1. Salman		2. Samson Chacko		3. Gaurav Sharma		
4. Amit Bhardwaj		5. Binu Kumar		6.		
7.		8.		9.		
10.						
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor		
	Water Level Meter	Bar Check	Generator	Hypack		
	Computer					
<b>Time (hrs)</b>		<b>Activities</b>				
0735	0800	Bathy team reached at site and set up RTK reference station for bathymetric survey.				
0740	0830	Land survey team reached at site and set up RTK reference station for land survey.				
0810	0820	Bar check carried out.				
0820		Bathymetric survey started.				
0840		Land survey started.				
	1745	Bathymetry survey terminated and base station secured.				
	1740	Land survey terminated and reference station secured.				
1740	1930	Land Survey team returned to guest house.				
		Today's coverage		Cumulative coverage		
		Bathymetry: 0.87 sq.km	Line km: 36	Bathymetry: 12.59sq.km	Line km: 546.3	
		Topo: 0.60 sq.km	Line km: 24.6	Topo: 6.45 sq.km	Line km: 264.1	
		Weather downtime today: Nil hours		Cumulative weather downtime: Nil hours		
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.						
<b>Remarks:</b>						
 Party Chief				Client Representative		




 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 017

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	29-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson Chacko		3. Gaurav Sharma	
4. Amit Bhardwaj		5. Binu Kumar		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System		SBES System	Auto Level	
	Water Level Meter		Bar Check	Generator	
	Computer			Heave sensor Hypack	
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0810	Bathy team reached at site and set up RTK reference station for bathymetric survey.			
0750	0840	Land survey team reached at site and set up RTK reference station for land survey.			
0815	0830	Bar check carried out.			
0840		Bathymetric survey started.			
0840		Land survey started.			
	1300	Bathymetry survey terminated due to high wind speed and swells.			
	1740	Land survey terminated and reference station secured.			
1740	1915	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.49 sq.km	Line km: 20.2	Bathymetry: 13.08sq.km	Line km: 566.5
		Topo: 0.60 sq.km	Line km: 24.5	Topo: 7.05 sq.km	Line km: 288.6
		Weather downtime today: 4 hours		Cumulative weather downtime: 4 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT


DPR No. 018

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	30-01-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav			Client Rep.		
<b>Survey Personnel:</b>					
1. Salman		2. Samson Chacko		3. Gaurav Sharma	
4. Amit Bhardwaj		5. Binu Kumar		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0810	Bathy team reached at site and set up RTK reference station for bathymetric survey.			
0750	0840	Land survey team reached at site and set up RTK reference station for land survey.			
0810	0825	Bar check carried out.			
0830		Bathymetric survey started.			
0840		Land survey started.			
	1745	Bathymetry survey terminated and reference station secured.			
	1740	Land survey terminated and reference station secured.			
1740	1900	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.38 sq.km	Line km: 56.6	Bathymetry: 14.46 sq.km	Line km: 623.1
		Topo: 0.54 sq.km	Line km: 22.1	Topo: 7.59 sq.km	Line km: 310.7
		Weather downtime today: 0 hours		Cumulative weather downtime: 4 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 019

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	31-01-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Salman		2. Samson Chacko		3. Gaurav Sharma	
4. Amit Bhardwaj		5. Binu Kumar		6.	
7.		8.		9.	
10.					
Equipment	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0815	Bathy team reached at site and set up RTK reference station for bathymetric survey.			
0750	0840	Land survey team reached at site and set up RTK reference station for land survey.			
0815	0830	Bar check carried out.			
0835		Bathymetric survey started.			
0840		Land survey started.			
	1630	Bathymetry survey terminated and reference station secured.			
	1730	Land survey terminated and reference station secured.			
1730	1845	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.0 sq.km	Line km: 42	Bathymetry: 15.46 sq.km	Line km: 665.1
		Topo: 0.56 sq.km	Line km: 22.9	Topo: 8.15 sq.km	Line km: 333.6
		Weather downtime today: 0 hours		Cumulative weather downtime: 4 hours	
Plan for next 24 hours: Continue with bathymetric and topographic survey.					
Remarks:					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 020

Client:	Namada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	01-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Gaurav Sharma		3. Amit Bhardwaj	
4. Binu Kumar		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System		SBES System	Auto Level	Heave sensor
	Water Level Meter		Bar Check	Generator	Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0810	Bathy team reached at site and set up RTK reference station for bathymetric survey.			
0745	0845	Land survey team reached at site and set up RTK reference station for land survey.			
0815	0830	Bar check carried out.			
0835		Bathymetric survey started.			
0850		Land survey started.			
	1745	Bathymetry survey terminated and reference station secured.			
	1740	Land survey terminated and reference station secured.			
1740	1915	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.32 sq.km	Line km: 54.2	Bathymetry: 16.78 sq.km	Line km: 719.3
		Topo: 0.58 sq.km	Line km: 23.8	Topo: 8.73 sq.km	Line km: 357.4
		Weather downtime today: 0 hours		Cumulative weather downtime: 4 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 021

Client:	Narmada Water Resources, Water Supply & Kalpsar Department	Project No:	P34320		
Vessel:	OSaS SMB	Date:	02-02-2021		
Location:	BHADAR DAM	Sheet No:	1 of 1		
Party Chief: Sunil Kumar Yadav		Client Rep.			
<b>Survey Personnel:</b>					
1. Samson Chacko	2. Gaurav Sharma	3. Amit Bhardwaj			
4. Binu Kumar	5.	6.			
7.	8.	9.			
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>	<b>Activities</b>				
0735	0800	Bathy team reached at site and set up RTK reference station for bathymetric survey.			
0740	0845	Land survey team reached at site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0850		Land survey started.			
	1730	Bathymetry survey terminated and reference station secured.			
	1740	Land survey terminated and reference station secured.			
1740	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.26 sq.km	Line km: 51.7	Bathymetry: 18.04 sq.km	Line km: 771
		Topo: 0.60 sq.km	Line km: 24.6	Topo: 9.33 sq.km	Line km: 382
		Weather downtime today: 0 hours		Cumulative weather downtime: 4 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			 <b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 022

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320	
Vessel:	OSaS SMB			Date:	03-02-2021	
Location:	BHADAR DAM			Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav				Client Rep.		
<b>Survey Personnel:</b>						
1. Samson Chacko		2. Gaurav Sharma		3. Amit Bhardwaj		
4. Binu Kumar		5.		6.		
7.		8.		9.		
10.						
<b>Equipment</b>	RTK System		SBES System	Auto Level		Heave sensor
	Water Level Meter		Bar Check	Generator		Hypack
	Computer					
<b>Time (hrs)</b>		<b>Activities</b>				
0740	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.				
0740	0845	Land survey team reached site and set up RTK reference station for land survey.				
0810	0820	Bar check carried out.				
0830		Bathymetric survey started.				
0850		Land survey started.				
	1740	Bathymetry survey terminated and reference station secured.				
	1730	Land survey terminated and reference station secured.				
1730	1915	Land Survey team returned to guest house.				
		Today's coverage		Cumulative coverage		
		Bathymetry: 1.27 sq.km	Line km: 52	Bathymetry: 19.31 sq.km	Line km: 823	
		Topo: 0.59 sq.km	Line km: 24.2	Topo: 9.92 sq.km	Line km: 406.2	
		Weather downtime today: 0 hours		Cumulative weather downtime: 4 hours		
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.						
<b>Remarks:</b>						
 <b>Party Chief</b>				<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 023


Client:	Namada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	04-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Gaurav Sharma		3. Amit Bhardwaj	
4. Binu Kumar		5.		6.	
7.		8.		9.	
10.					
Equipment	RTK System		SBES System	Auto Level	
	Water Level Meter		Bar Check	Generator	
	Computer				
Heave sensor		Hypack			
Time (hrs)		Activities			
0745	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0845	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0850		Land survey started.			
	1800	Bathymetry survey terminated and reference station secured.			
	1800	Land survey terminated and reference station secured.			
1800	2015	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.37 sq.km	Line km: 56.5	Bathymetry: 20.68 sq.km	Line km: 879.5
		Topo: 0.69 sq.km	Line km: 28.3	Topo: 10.61 sq.km	Line km: 434.5
		Weather downtime today: 0 hours		Cumulative weather downtime: 4 hours	
Plan for next 24 hours: Continue with bathymetric and topographic survey.					
Remarks:					
 Party Chief			Client Representative		

 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT


DPR No. 024

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	05-02-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Gaurav Sharma		3. Amit Bhardwaj	
4. Binu Kumar		5.		6.	
7.		8.		9.	
10.					
Equipment	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0845	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0850		Land survey started.			
	1730	Bathymetry survey terminated and reference station secured.			
	1735	Land survey terminated and reference station secured.			
1735	1915	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.22 sq.km	Line km: 50.1	Bathymetry: 21.9 sq.km	Line km: 929.6
		Topo: 0.55 sq.km	Line km: 22.5	Topo: 11.16 sq.km	Line km: 457
		Weather downtime today: 0 hours		Cumulative weather downtime: 4 hours	
Plan for next 24 hours: Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		




 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 025

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	06-02-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Gaurav Sharma		3. Amit Bhardwaj	
4. Binu Kumar		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0845	Land survey team reached site and set up RTK reference station for land survey.			
0740	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
		Bathymetric survey could not be started in view of strong wind and high swells.			
0850		Land survey started.			
	1730	Land survey terminated and reference station secured.			
1730	1900	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: --- sq.km	Line km: ---	Bathymetry: 21.9 sq.km	Line km: 929.6
		Topo: 0.57 sq.km	Line km: 23.3	Topo: 11.73 sq.km	Line km: 480.3
		Weather downtime today: 10 hours		Cumulative weather downtime: 14 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT


DPR No. 026

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	07-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Sunil Kumar Yadav				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Gaurav Sharma		3. Amit Bhardwaj	
4. Binu Kumar		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0735	0750	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0845	Land survey team reached site and set up RTK reference station for land survey.			
0800	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0850		Land survey started.			
	1230	Bathymetry survey terminated due to high swells and wind.			
	1740	Land survey terminated and reference station secured.			
1740	1900	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.39 sq.km	Line km: 16	Bathymetry: 22.29 sq.km	Line km: 945.6
		Topo: 0.45 sq.km	Line km: 18.4	Topo: 12.18 sq.km	Line km: 498.7
		Weather downtime today: 5 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 027

Client:	Namada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	08-02-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Gaurav Sharma		3. Amit Bhardwaj	
4. Binu Kumar		5.		6.	
7.		8.		9.	
10.					
Equipment	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0745	0845	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0850		Land survey started.			
	1730	Bathymetric survey terminated and reference station secured.			
	1745	Land survey terminated and reference station secured.			
1745	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.15 sq.km	Line km: 47.1	Bathymetry: 23.44 sq.km	Line km: 992.7
		Topo: 0.46 sq.km	Line km: 18.9	Topo: 12.64 sq.km	Line km: 517.6
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
 <b>Party Chief</b>			<b>Client Representative</b>		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 028

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320	
Vessel:	OSaS SMB			Date:	09-02-2021	
Location:	BHADAR DAM			Sheet No:	1 of 1	
Party Chief: Sunil Kumar Yadav				Client Rep.		
<b>Survey Personnel:</b>						
1. Samson Chacko		2. Gaurav Sharma		3. Amit Bhardwaj		
4. Binu Kumar		5.		6.		
7.		8.		9.		
10.						
Equipment	RTK System		SBES System		Auto Level	
	Water Level Meter		Bar Check		Generator	
	Computer				Heave sensor	
						Hypack
Time (hrs)		Activities				
0735	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.				
0740	0845	Land survey team reached site and set up RTK reference station for land survey.				
0810	0820	Bar check carried out.				
0830		Bathymetric survey started.				
0850		Land survey started.				
	1300	Bathymetric survey terminated and reference station secured.				
	1745	Land survey terminated and reference station secured.				
1745	2000	Land Survey team returned to guest house.				
		Today's coverage		Cumulative coverage		
		Bathymetry: 0.38 sq.km		Line km: 15.24		Bathymetry: 23.82 sq.km
		Line km: 16.4		Topo: 13.04 sq.km		Line km: 1007.94
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours		
Plan for next 24 hours: Continue with bathymetric and topographic survey.						
Remarks:						
 Party Chief				Client Representative		


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 029

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	10-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0810	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0810	Land survey team reached site and set up RTK reference station for land survey.			
0810	0825	Bar check carried out.			
0830		Bathymetric survey started.			
0835		Land survey started.			
	1900	Bathymetric survey terminated and reference station secured.			
	1900	Land survey terminated and reference station secured.			
1900	1915	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.05 sq.km	Line km: 42.75	Bathymetry: 24.87 sq.km	Line km: 1050.69
		Topo: 0.30 sq.km	Line km: 12.30	Topo: 13.34 sq.km	Line km: 546.3
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 030

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB	Date:	11-02-2021		
Location:	BHADAR DAM	Sheet No:	1 of 1		
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
Equipment	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0745	0800	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0810		Land survey started.			
	1800	Bathymetric survey terminated and reference station secured.			
	1900	Land survey terminated and reference station secured.			
1900	1915	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: .90sq.km	Line km: 36.03	Bathymetry: 25.77 sq.km	Line km: 1086.72
		Topo: 0.44 sq.km	Line km: 18.04	Topo: 13.78 sq.km	Line km: 564.34
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 031

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	12-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System		SBES System	Auto Level	
	Water Level Meter		Bar Check	Generator	
	Computer			Heave sensor	
				Hypack	
<b>Time (hrs)</b>		<b>Activities</b>			
0735	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0830	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0820		Bathymetric survey started.			
0840		Land survey started.			
	1800	Bathymetric survey terminated and reference station secured.			
	1830	Land survey terminated and reference station secured.			
1830	1900	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.96 sq.km	Line km: 39.11	Bathymetry: 26.73 sq.km	Line km: 1125.83
		Topo: 0.54 sq.km	Line km: 22.14	Topo: 14.32 sq.km	Line km: 586.48
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
Plan for next 24 hours: Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					

 <p align="center"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT


DPR No. 032

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	13-02-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Gaurav Sharma			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0845	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0850		Land survey started.			
	1740	Bathymetric survey terminated and reference station secured.			
	1900	Land survey terminated and reference station secured.			
1900	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 1.03 sq.km	Line km: 40.89	Bathymetry: 27.76 sq.km	Line km: 1166.72
		Topo: 0.47 sq.km	Line km: 19.27	Topo: 14.79 sq.km	Line km: 605.75
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<p align="center"><b>Client Representative</b></p>		
<b>Party Chief</b>					




 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 033

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	14-02-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Gaurav Sharma			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0810	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0750	0840	Land survey team reached site and set up RTK reference station for land survey.			
0815	0830	Bar check carried out.			
0840		Bathymetric survey started.			
0840		Land survey started.			
	1830	Bathymetric survey terminated and reference station secured.			
	1900	Land survey terminated and reference station secured.			
1900	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.74 sq.km	Line km: 30.88	Bathymetry: 28.5 sq.km	Line km: 1197.6
		Topo: 0.36 sq.km	Line km: 14.76	Topo: 15.15 sq.km	Line km: 623.51
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 034

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB	Date:	15-02-2021		
Location:	BHADAR DAM	Sheet No:	1 of 1		
Party Chief: Gaurav Sharma			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko	2. Amit Bhardwaj		3. Binu Kumar		
4.	5.		6.		
7.	8.		9.		
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>	<b>Activities</b>				
0730	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0830	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0820		Bathymetric survey started.			
0840		Land survey started.			
	1815	Bathymetric survey terminated and reference station secured.			
	1800	Land survey terminated and reference station secured.			
1800	1830	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.58 sq.km	Line km: 23.01	Bathymetry: 29.08 sq.km	Line km: 1220.61
		Topo: 0.30 sq.km	Line km: 12.30	Topo: 15.45 sq.km	Line km: 635.81
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 035

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	16-02-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Gaurav Sharma			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0735	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0845	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0850		Land survey started.			
	1745	Bathymetric survey terminated and reference station secured.			
	1730	Land survey terminated and reference station secured.			
1730	1800	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.486sq.km	Line km: 19.46	Bathymetry: 29.66 sq.km	Line km: 1240.07
		Topo: 0.33 sq.km	Line km: 13.53	Topo: 15.78 sq.km	Line km: 649.34
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 036

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	17-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0810	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0830	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0820		Bathymetric survey started.			
0840		Land survey started.			
	1830	Bathymetric survey terminated and reference station secured.			
	1830	Land survey terminated and reference station secured.			
1830	1945	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: 0.43 sq.km	Line km: 17.4	Bathymetry: 29.96 sq.km	Line km: 1257.47
		Topo: 0.645sq.km	Line km: 25.83	Topo: 16.433 sq.km	Line km: 675.17
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 037

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320		
Vessel:	OSaS SMB			Date:	18-02-2021		
Location:	BHADAR DAM			Sheet No:	1 of 1		
Party Chief: Gaurav Sharma				Client Rep.			
<b>Survey Personnel:</b>							
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar			
4.		5.		6.			
7.		8.		9.			
10.							
<b>Equipment</b>	RTK System		SBES System		Auto Level		
	Water Level Meter		Bar Check		Generator		
	Computer				Heave sensor Hypack		
<b>Time (hrs)</b>		<b>Activities</b>					
0750	0820	Bathy team reached site and set up RTK reference station for bathymetric survey.					
0750	0835	Land survey team reached site and set up RTK reference station for land survey.					
0820	0830	Bar check carried out.					
0830		Bathymetric survey started.					
0845		Land survey started.					
	1830	Bathymetric survey terminated and reference station secured.					
	1830	Land survey terminated and reference station secured.					
1830	1940	Land Survey team returned to guest house.					
		Today's coverage			Cumulative coverage		
		Bathymetry: 0.50 sq.km		Line km: 21.36		Bathymetry: 30.53 sq.km	
		Line km: 25.42		Topo: 17.06 sq.km		Line km: 1278.83	
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours		Line km: 700.59	
Plan for next 24 hours: Continue with bathymetric and topographic survey.							
<b>Remarks:</b>							
				<b>Client Representative</b>			
<b>Party Chief</b>							


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 038

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	19-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0810	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0745	0830	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0830		Land survey started.			
	1800	Bathymetric survey terminated and reference station secured.			
	1830	Land survey terminated and reference station secured.			
1830	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.57 sq.km	Line km: 22.96	Bathymetry: 31.104 sq.km	Line km: 1301.79
		Topo: 0.625 sq.km	Line km: 25.01	Topo: 17.693 sq.km	Line km: 725.6
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 039

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	20-02-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Gaurav Sharma			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0830	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey started.			
0830		Land survey started.			
	1740	Bathymetric survey terminated and reference station secured.			
	1800	Land survey terminated and reference station secured.			
1800	1910	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.48sq.km	Line km: 19.15	Bathymetry: 31.58 sq.km	Line km: 1320.94
		Topo: 0.55 sq.km	Line km: 22.15	Topo: 18.246 sq.km	Line km: 747.75
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					

 <p><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT


DPR No. 040

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB	Date:	21-02-2021		
Location:	BHADAR DAM	Sheet No:	1 of 1		
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko	2. Amit Bhardwaj		3. Binu Kumar		
4.	5.		6.		
7.	8.		9.		
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>	<b>Activities</b>				
0745	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0745	0845	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey Including Infill survey for gap filling started.			
0850		Land survey started.			
	1745	Bathymetric survey terminated and reference station secured.			
	1800	Land survey terminated and reference station secured.			
1800	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.29 sq.km	Line km: 11.89	Bathymetry: 31.88 sq.km	Line km: 1332.83
		Topo: 0.63 sq.km	Line km: 25.01	Topo: 18.871 sq.km	Line km: 772.76
		Weather downtime today: 0 hours		Cumulative weather downtime: 19 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					




 <p><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 041

Client: Narmada Water Resources, Water Supply & Kalpsar Department		Project No: P34320		
Vessel: OSaS SMB		Date: 22-02-2021		
Location: BHADAR DAM		Sheet No: 1 of 1		
Party Chief: Gaurav Sharma		Client Rep.		
Survey Personnel:				
1. Samson Chacko	2. Amit Bhardwaj	3. Binu Kumar		
4.	5.	6.		
7.	8.	9.		
10.				
Equipment	RTK System	SBES System	Auto Level	Heave sensor
	Water Level Meter	Bar Check	Generator	Hypack
	Computer			
Time (hrs)		Activities		
0740	0845	Land survey team reached site and set up RTK reference station for land survey.		
0740	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.		
		Bathymetric survey could not be started in view of strong wind and high swells.		
0850	Land survey started.			
	1830	Land survey terminated and reference station secured.		
1830	2000	Land Survey team returned to guest house.		
		Today's coverage	Cumulative coverage	
		Bathymetry: --- sq.km	Line km: ---	
		Bathymetry: 31.89 sq.km	Line km: 1332.83	
		Topo: 0.522 sq.km	Line km: 20.91	
		Topo: 19.393 sq.km	Line km: 793.67	
		Weather downtime today: 10 hours	Cumulative weather downtime: 29 hours	
Plan for next 24 hours: Continue with bathymetric and topographic survey.				
Remarks:				
		<p>Client Representative</p>		
Party Chief				


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 042

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	23-02-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Gaurav Sharma			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0740	0810	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0745	0845	Land survey team reached site and set up RTK reference station for land survey.			
0815	0830	Bar check carried out.			
0835		Bathymetric survey started.			
0850		Land survey started.			
	1745	Bathymetry survey terminated and reference station secured.			
	1740	Land survey terminated and reference station secured.			
1740	1900	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: 0.51 sq.km	Line km: 20.91	Bathymetry: 32.4 sq.km	Line km: 1353.74
		Topo: 0.50 sq.km	Line km: 20.50	Topo: 19.9 sq.km	Line km: 814.17
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 043

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	24-02-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Gaurav Sharma			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0800	Bathy team reached site and set up RTK reference station for bathymetric survey.			
0740	0845	Land survey team reached site and set up RTK reference station for land survey.			
0810	0820	Bar check carried out.			
0830		Bathymetric survey Including Infill survey for gap filling started.			
0850		Land survey started.			
	1750	Bathymetry survey terminated and reference station secured.			
	1800	Land survey terminated and reference station secured.			
1800	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: 0.30 sq.km	Line km: 12.3	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.451 sq.km	Line km: 18.04	Topo: 20.356 sq.km	Line km: 832.21
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
Plan for next 24 hours: Continue with topographic survey.					
Remarks: Completed bathymetry survey of Bhadar dam 1.					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 044

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	25-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0750	0810	Bathy team reached site and Demobilisation started.			
0750	0855	Land survey team reached site and set up RTK reference station for land survey.			
0810	1500	Demobbed bathymetry survey equipment from boat.			
0855		Land survey started.			
	1745	Land survey terminated and reference station secured.			
1745	1900	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: --	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.56 sq.km	Line km: 22.96	Topo: 20.93 sq.km	Line km: 855.17
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> To continue topographic survey.					
<b>Remarks:</b>					
				<p><b>Client Representative</b></p>	
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 045

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	26-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0800	0900	Land survey team reached site and set up RTK reference station for land survey.			
0900		Land survey started.			
	1830	Land survey terminated and reference station secured.			
1830	1930	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: -- sq.km	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.572 sq.km	Line km: 20.91	Topo: 21.502 sq.km	Line km: 878.08
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Continue with topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 046

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	27-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0730	0830	Land survey team reached site and set up RTK reference station for land survey.			
0840		Land survey started.			
	1800	Land survey terminated and reference station secured.			
1800	1915	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: -- sq.km	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.80 sq.km	Line km: 32.8	Topo: 22.322 sq.km	Line km: 910.88
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Continue with topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p align="center"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 047

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	28-02-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
Equipment	RTK System		SBES System		Auto Level
	Water Level Meter		Bar Check		Generator
	Computer				Heave sensor Hypack
Time (hrs)		Activities			
0745	0845	Land survey team reached site and set up RTK reference station for land survey.			
0850		Land survey started.			
	1830	Land survey terminated and reference station secured.			
1830	1930	Land Survey team returned to guest house.			
		Today's coverage		Cumulative coverage	
		Bathymetry: -- sq.km	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.564 sq.km	Line km: 22.55	Topo: 22.886 sq.km	Line km: 933.43
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Continue with topographic survey.					
<b>Remarks:</b>					
 Party Chief			Client Representative		

 <p><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT


DPR No. 048

Client:		Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320
Vessel:		OSaS SMB		Date:	01-03-2021
Location:		BHADAR DAM		Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0800	0900	Land survey team reached site and set up RTK reference station for land survey.			
0900	Land survey started.				
	1845	Land survey terminated and reference station secured.			
1845	1950	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: -- sq.km	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.553 sq.km	Line km: 22.14	Topo: 23.439 sq.km	Line km: 955.57
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Continue with topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					




 <b>OCEAN</b> Science & Surveying  <b>DAILY PROGRESS REPORT</b>	<i>Form No.:</i>	Sy01R
	<i>Revision:</i>	01
	<i>Date:</i>	11/07/2014
	<i>Approved By</i>	PKT

DPR No. 049

<b>Client:</b>	Narmada Water Resources, Water Supply & Kalpsar Department		<b>Project No:</b>	P34320	
<b>Vessel:</b>	OSaS SMB		<b>Date:</b>	02-03-2021	
<b>Location:</b>	BHADAR DAM		<b>Sheet No:</b>	1 of 1	
<b>Party Chief:</b> Gaurav Sharma			<b>Client Rep.</b>		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0900	Land survey team reached site and set up RTK reference station for land survey.			
	0905	Land survey started.			
	1830	Land survey terminated and reference station secured.			
1830	2000	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: -- sq.km	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.584 sq.km	Line km: 23.37	Topo: 24.023 sq.km	Line km: 978.94
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Continue with and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 050

<b>Client:</b>	Narmada Water Resources, Water Supply & Kalpsar Department	<b>Project No:</b>	P34320		
<b>Vessel:</b>	OSaS SMB	<b>Date:</b>	03-03-2021		
<b>Location:</b>	BHADAR DAM	<b>Sheet No:</b>	1 of 1		
<b>Party Chief:</b> Gaurav Sharma			<b>Client Rep.</b>		
<b>Survey Personnel:</b>					
1. Samson Chacko	2. Amit Bhardwaj	3. Binu Kumar			
4.	5.	6.			
7.	8.	9.			
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>	<b>Activities</b>				
0730	0845	Land survey team reached site and set up RTK reference station for land survey.			
0850		Land survey started.			
	1800	Land survey terminated and reference station secured.			
1800	1930	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: -- sq.km	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.56 sq.km	Line km: 22.96	Topo: 24.597 sq.km	Line km: 1001.9
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Continue with topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 051

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	04-03-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0745	0900	Land survey team reached site and set up RTK reference station for land survey.			
0905		Land survey started.			
	1815	Land survey terminated and reference station secured.			
1815	1945	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: -- sq.km	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.553 sq.km	Line km: 22.14	Topo: 25.15 sq.km	Line km: 1024.04
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					


 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 052

Client:	Narmada Water Resources, Water Supply & Kalpsar Department		Project No:	P34320	
Vessel:	OSaS SMB		Date:	05-03-2021	
Location:	BHADAR DAM		Sheet No:	1 of 1	
Party Chief: Gaurav Sharma			Client Rep.		
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level	Heave sensor	
	Water Level Meter	Bar Check	Generator	Hypack	
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0730	0900	Land survey team reached site and set up RTK reference station for land survey.			
0905		Land survey started.			
	1800	Land survey terminated and reference station secured.			
1800	1930	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: -- sq.km	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.38 sq.km	Line km: 15.58	Topo: 25.49 sq.km	Line km: 1039.62
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Continue with bathymetric and topographic survey.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					

 <p style="text-align: center;"><b>DAILY PROGRESS REPORT</b></p>	Form No.:	Sy01R
	Revision:	01
	Date:	11/07/2014
	Approved By	PKT

DPR No. 053

Client:	Narmada Water Resources, Water Supply & Kalpsar Department			Project No:	P34320
Vessel:	OSaS SMB			Date:	06-03-2021
Location:	BHADAR DAM			Sheet No:	1 of 1
Party Chief: Gaurav Sharma				Client Rep.	
<b>Survey Personnel:</b>					
1. Samson Chacko		2. Amit Bhardwaj		3. Binu Kumar	
4.		5.		6.	
7.		8.		9.	
10.					
<b>Equipment</b>	RTK System	SBES System	Auto Level		Heave sensor
	Water Level Meter	Bar Check	Generator		Hypack
	Computer				
<b>Time (hrs)</b>		<b>Activities</b>			
0645	0815	Land survey team reached site and set up RTK reference station for land survey.			
0820		Land survey started.			
	1800	Land survey terminated and reference station secured.			
1800	2000	Land Survey team returned to guest house.			
		<b>Today's coverage</b>		<b>Cumulative coverage</b>	
		Bathymetry: -- sq.km	Line km: --	Bathymetry: 32.7 sq.km	Line km: 1366.04
		Topo: 0.823 sq.km	Line km: 32.923	Topo: 26.372 sq.km	Line km: 1072.543
		Weather downtime today: 0 hours		Cumulative weather downtime: 29 hours	
<b>Plan for next 24 hours:</b> Equipment and team shift to next Location.					
<b>Remarks:</b>					
			<b>Client Representative</b>		
<b>Party Chief</b>					

